Appendix A. Notice of Preparation

NOTICE OF PREPARATION

To: State Clearinghouse,

Responsible Agencies
Trustee Agencies
Other Interested Parties

(please see Distribution List)

From: Lori Lawrence, Environmental Review Clerk

Placer County Planning Department 11414 B Avenue, Auburn, CA 95603

(530) 889-7470 (530) 8

(530) 889-7499 FAX

email: LJLawren@placer.ca.gov

Subject:

Notice of Preparation of a Draft Environmental Impact Report/Environmental

Impact Study

Placer County and the Tahoe Regional Planning Agency (TRPA) will serve as joint Lead Agencies and will prepare a joint Environment Impact Report (EIR)/Environmental Impact Statement (EIS) for the project identified below. The County's EIR is intended to meet the requirements of the California Environmental Quality Act (CEQA) and TRPA's EIS is intended to meet the requirements of TRPA's Code of Ordinances. The Federal Highway Administration (FHWA) will be the Lead Agency for the requirements of the National Environmental Policy Act (NEPA). Please provide your comments as to the scope and content of the environmental information that is germane to you as a private individual or to your agency's statutory responsibilities in connection with the proposed project. Agencies that receive this Notice of Preparation will need to use the joint EIR/EIS prepared by Placer County and TRPA when considering your permit or other approvals for the project, if applicable. It is also important to note that this will not be the final opportunity for private individuals or agencies to comment on this project.

The project description, location, and the potential environmental effects are noted below. Due to the time limits mandated by California State law, your response must be sent at the earliest possible date but not later than **December 23, 2002**.

For further information on the proposed project, or to mail your written response, please contact **Lori Lawrence**, **Placer County Planning Department**, at the address indicated above. A copy of all comments received by Placer County will also be forwarded to TRPA. We request the name of a contact person for your agency, if applicable.

Project Title: Kings Beach Commercial Core Improvement Project

Notice of Public Scoping Workshop

A public scoping workshop for the proposed project is planned for:

Date / Time December 5, 20

December 5, 2002, 7:00 - 9:00 pm

Location

North Tahoe Community Conference Center

Address

8318 North Lake Boulevard (SR28), Kings Beach, CA 96143

All interested parties are invited to attend and provide comments on the scope of the EIR, alternatives to be studied, potential impacts, and on the project in general.

Project Description for Kings Beach Commercial Core Improvement Project

The proposed project involves partial reconstruction of a portion of State Route 28 (SR28) and other improvements within the Community Plan boundaries of Kings Beach, California (see Figure 1). The project involves the following components:

- 1. Roadway improvements
 - Option A: Two vehicle travel lanes in each direction. Turn pockets present at four signalized intersections. Two of the signals exist currently (SR267 and Coon Street), and the other two (Bear Street and Fox Street) are proposed.
 - Option B: One vehicle travel lane in each direction, separated by a center turn lane. Roundabouts would be constructed at the Bear, Coon and Fox Street intersections. The existing signal at SR267 would remain. To accommodate roundabout configuration, block-long segments of Brook, Salmon, and Minnow Streets would be converted to one-way (east-bound) roadways.
- 2. Pedestrian and bicycle access improvements (bike lanes, sidewalks, landscaping and streetscape)
- 3. Water quality improvements
- 4. Replacement parking

The project was initiated by the need to improve pedestrian and bicyclist access along and across SR28 within the Kings Beach Commercial Core. Currently, sidewalks are present in only some locations and where they are not present, pedestrians must walk along the edge of the street or along undeveloped portions of the roadway. In addition, bicyclists must ride in the roadway, competing with automobiles and pedestrians. Facilities for pedestrians and bicyclists will be expanded upon. Improvements for access across SR28 also are proposed to supplement the existing two signalized intersections.

Portions of the existing drainage system, constructed in the 1960s, are undersized and provide no water quality treatment. Recent upgrades north of SR28 have increased drainage network capacity and improved sediment control. However, the restricted capacity of culverts underneath the roadway limits the extent to which up-gradient waters can be conveyed across SR28 right-of-way. The proximity of the roadway to Lake Tahoe limits options available for treatment of storm water runoff. Because of these limitations, existing storm water treatment facilities do not meet standards set by local regulatory agencies. Improvements are proposed that address storm water runoff and water quality treatment, as well as how the project area relates to area-wide drainage and water quality improvement systems.

The final component involves improvements to the aesthetic character of the Kings Beach Commercial Core. Most of the business infrastructure (motels, retail, commercial, etc.) was developed in the 1950s. Because of a comparatively stable client base over the years, few of those facilities have been updated. As a result, TRPA scenic ratings for the Commercial Core area place it below the threshold value. Aesthetic improvements are proposed that enhance the scenic integrity of the Commercial Core.

Probable Environmental Effects

Probable environmental effects of the proposed Kings Beach Commercial Core project could impact several resources. A brief outline of those resources is provided below.

Air quality will be evaluated for both short-term and long-term impacts. Short-term impacts associated with the project will be from construction activities. Over long-term, the project could represent a benefit to the environment by reducing the number of idling cars and providing controlled intersections.

Water quality will be evaluated with regard to conveyance and storm water treatment needs. Water quality planning studies are currently being conducted to refine treatment needs and methods. The project is intended to present a benefit to water quality by removing pollutant loading from the project area.

Because the project will not increase the capacity of existing roadways, a noise study is not proposed. Potential short-term noise impacts resulting from construction activities will be evaluated.

Traffic impacts will be assessed within the project area. A traffic study will be conducted to quantify, in part, when peak volumes occur, how traffic flow will be affected at these times, and where overflow will occur. Pedestrian circulation, vehicle miles traveled, and similar information will also be evaluated. Potential impacts to existing parking will be analyzed.

An evaluation of potential impacts to vegetation and wildlife (including habitat) will be conducted. This will include an evaluation of impacts to special status vegetation and wildlife species.

Soil characteristics will be evaluated for potential environmental effects based on land capability and land coverage, as well as slope and erosion hazard.

Visual resources within the project area will be analyzed within the context of the appropriate scenic roadway and recreation units. Scenic thresholds and impacts will be evaluated from selected viewpoints.

Prehistoric and historic period archaeological and architectural resources will be identified and evaluated based on the location of project disturbance.

Economic impacts of the project will be evaluated. This will include impacts to the community from construction, removal/relocation of parking spaces, change in local circulation patterns, relocation of businesses, emergency response, and others.

Other environmental resources identified through scoping and on-going studies will be evaluated. Project impacts will be assessed in light of established agency thresholds.

If you have further questions or require additional information regarding this matter, please contact **Lori Lawrence** at the address or telephone number provided above. This Notice of Preparation was circulated beginning November 18, 2002.

Attachment: Figure 1. General Study Area Boundary

Figure 2. Alternative Roadway Cross Sections

Figure 3. Roadway Option A – 4 Lanes with Signals

Figure 4. Roadway Option B - 3 Lanes with Roundabouts

Figure 5. Potential Parking Lot and Drainage Treatment Locations

Figure 6. Streetscape Concept Simulations – Curb Sidewalk

Figure 7. Streetscape Concept Simulations – Town Sidewalk with Street Trees

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT NOTICE OF PREPARATION INFORMATION PACKAGE

I. PROJECT NAME AND DESCRIPTION

The proposed project involves partial reconstruction of a portion of State Route 28 (SR 28) and other improvements within the Community Plan boundaries of Kings Beach, California (Figure 1). The Kings Beach Commercial Core Project involves the following components:

- 1. Roadway improvements,
- 2. Pedestrian Access improvements (bike lanes and sidewalks including landscaping and streetscape improvements),
- 3. Water Quality improvements, and
- 4. Aesthetic improvements.

The purpose of this NOP Information Package is to provide project information to agency staff. It is hoped that this information will prove useful when scoping the level and content of the environmental documentation that will be required on behalf of the proposed project.

II. BACKGROUND / EXISTING CONDITIONS

Historically, Kings Beach has been one of the primary commercial and recreational centers in the Lake Tahoe Basin. State Route 28 (SR 28) extends through the Kings Beach commercial area, which is generally defined as extending from the SR 267 intersection at the western boundary to the intersection of SR 28 and Chipmunk Street at the eastern boundary. Land uses are predominantly tourist/recreational and commercial.

Over the years, land use development in Kings Beach has been influenced by the nature of its original subdivision. The 1926 "Brockway Vista" subdivision map laid out rectangular lots in a typical grid system. Many of the lots are small, measuring 7.6m in width and 38.1m in depth. This lay out has resulted in a large number of small structures confined by parcel width.

Originally constructed as a two-lane Forest Reserve road in the early 1930s, SR 28 cuts somewhat diagonally through the subdivision. Parcels in blocks adjacent to the highway are located perpendicular to the road and slightly askew from parcels and blocks in the remainder of the community. The limited width of the roadway allowed for roadside parking and an adequate setback between the roadway and adjacent buildings. During the 1960s, the roadway was expanded to four lanes through the commercial core area. The additional lanes were provided at the expense of the setback between buildings and the road. Roadside parking also was affected. During peak summer periods, there is a shortage of available parking in portions of the commercial core area. In addition, pedestrian crossing of the highway was made more difficult.

Placer County and the Tahoe Regional Planning Agency (TRPA) adopted the Kings Beach Community Plan¹ in 1996. That plan presents a vision intended to guide community enhancement activities. Major components of the Community Plan are directed at the commercial core. These include reconstruction of SR 28, providing improved pedestrian and bicyclist facilities, the installation of streetscape improvements, and the construction of water quality improvements.

The intent of the proposed project is to address specific traffic circulation, bicycle/pedestrian circulation, scenic, and water quality needs of the Kings Beach Commercial Core in a manner consistent with the Community Plan.

III. NEED AND PURPOSE

A need is a condition or circumstance that prompts consideration of a particular action or, as in this case, a proposed project. Understanding the need for the proposed Kings Beach project requires an understanding of land use planning at the regional level, and more specific project considerations.

Need One - Improve Pedestrian and Bicyclist Mobility Along the Commercial Core

Tourists come to Kings Beach to enjoy the areas' aesthetic and recreational resources and facilities. At times, the local population swells by as much as 550 percent. Convenient pedestrian access is a critical component of commercial and recreational activities that occurs in Kings Beach. Currently, sidewalks are present in only some locations. Where sidewalks are not present, pedestrians must walk along the edge of the street or along undeveloped portions of the right-of-way. Improved pedestrian access is needed. This includes access along the commercial core, between parking and the commercial core, and between the commercial core and adjacent recreation areas.

Bicycle use volumes are increasing in Kings Beach and in the Tahoe area generally. It is reasonable to assume that levels of bicycle use will continue to increase with time. Bicycle facilities are not present within the Kings Beach commercial core. Bicyclists are forced to ride in the roadway, competing with automobiles and pedestrians. There is a need to improve bicyclist access along the Commercial core. Meeting this need will require that sufficient space be identified and set aside for use by pedestrians and bicyclists. This might include sidewalks, curbs or other barriers intended to protect pedestrians, bike paths, and/or bike lanes.

There is a <u>need</u> to improve pedestrian and bicyclist access along SR 28 roadway within the Kings Beach Commercial Core.

The Community Plan includes a list of capital improvement projects intended to achieve identified Community Plan goals. Similarly, the Environmental Improvement Program (EIP) established by TRPA, lists projects considered necessary to achieve environmental goals in the

¹ Tahoe Regional Planning Agency, North Tahoe Community Plan, April 1, 1996

Lake Tahoe Basin. Finally, expanding opportunities for pedestrian and bicycle travel is a key element in both regional and community transportation plans. By meeting the identified need for improved pedestrian and bicyclist mobility, the proposed project will implement (fully or partially) projects listed in the *Community Plan*, in the May 2001 *EIP* update, and it will help achieve transportation goals. By doing so, the project will contribute to the achievement of planning goals at the community and regional level.

CIP Number	Project Category	Project Title / Description
Recreation		Recreation Trail System
Traffic / Air Quality	Sidewalk Program	Sidewalks along SR 28
Traffic / Air Quality	Recreation System	SR 28 Bike Lanes
EIP Number	Project Category	Project Title / Description
EIP Number 762 *	Project Category Air Quality / Traffic	Project Title / Description Class II Bike Path, Dollar Hill to North Stateline
		Project Title / Description Class II Bike Path, Dollar Hill to North Stateline Kings Beach Roadwork – Curb and Gutter

^{*} The area of implementation for this EIP project extends through, but is not limited to the Kings Beach Commercial Core Area.

Need Two - Improve Pedestrian and Bicyclist Mobility Across SR 28

Providing safe pedestrian access across SR 28 is equally important. Currently, two signalized intersections are present at Coon Street and SR 267; each has pedestrian activated signals. Eight striped crosswalks are present at various locations along SR 28 in Kings Beach. However, crosswalk markings are visible only between June and November (striping is obliterated during the winter by snow removal equipment). Even where available and visible, these crossings offer the pedestrian only limited protection when trying to cross the roadway.

The Caltrans Traffic Concept Report for SR 28 identifies level-of-service "F" as the concept objective for Kings Beach in 2016, with no projects proposed to increase capacity. When the concept report was completed in 1997, the level-of-service was "B." Conflicts between vehicles and pedestrians were cited as a major factor in the degradation of LOS.

In a recent Caltrans traffic study, five intersections were subjected to a warrant analysis based on 1999 traffic counts. Three intersections – Secline, Deer, and Chipmunk – do not meet warrants. The Bear intersection meets signal warrants based on interruption of continuous service, pedestrian traffic, four-hour volume, and peak-hour volume. The Fox intersection meets signal warrants based on interruption of continuous service and peak-hour volume.

Accident data for the period between January 1, 1998 and December 31, 2000 indicate that the rate of injury accidents, the rate of total accidents, and the overall accident rate within the project area is higher than for other similar facilities. Intersections at Secline, Deer, Coon, and Fox Streets have accident rates higher than the average for similar facilities. Accident levels along the project corridor and at project corridor intersections can be expected to increase as traffic, pedestrian, and bicyclist volumes increase.

^{**} The area of implementation for this EIP project is countywide. While some improvements associated with this EIP project may be located in the Kings Beach Commercial Core Area, they need not be.

There is a <u>need</u> to improve pedestrian and bicyclist access across SR 28 within the Kings Beach Commercial Core.

By meeting the identified need for improved pedestrian and bicyclist access at intersections, the proposed project will implement (fully or partially) projects listed in the *Community Plan*, and it will help achieve regional transportation goals. By doing so, the project will contribute to the achievement of planning goals at the community and regional level.

CIP Number	Project Category	Project Title / Description
Traffic / Air Quality	Highway Improvement	Coon Street Intersection Improvement
Traffic / Air Quality	Highway Improvement	Bear Street Intersection Improvement
Recreation		Recreation Trail System

Need Three - Improve the Aesthetic Character of the Commercial Core

Kings Beach has historically been one of the primary commercial and recreational centers of the Tahoe Basin. Most of the business infrastructure (motels, businesses, rentals) was developed in the 1950s. Because of a comparatively stable client base over the years, few of those facilities have been updated. As a result, they have not captured a share of the higher paying clientele that patronize more updated facilities in neighboring communities.

These factors have had an impact on the community. Placer County has prepared a strategic business development plan Kings Beach. That plan documents a steady slowing in recreation-related business indicators over the last decade, with an actual decline over the last few years. The Kings Beach Commercial Core is ripe for rehabilitation and revitalization. The commercial core is located within Roadway Unit 20. TRPA scenic ratings for this unit place it below the threshold value, and the unit is targeted for scenic restoration.

Providing an enhanced sense of community ("main street") can increase the community's ability to accommodate commercial and recreational activity by visitors to the area. This enhancement should include a strong emphasis on providing a more attractive pedestrian environment. This will result in improved business revenues and a greater willingness on the part of private property owners to invest in building renovations and other community improvements.

There is a <u>need</u> to improve the aesthetic character of the Kings Beach Commercial Core.

Aesthetic improvements should be included that enhance the scenic integrity of the commercial core. These may include entry statements at the east and west ends of the commercial core, the retirement and/or replacement of non-conforming signs, the installation of streetlights, benches, transit facilities, planters intended to separate pedestrians from the roadway, bicycle racks, trash receptacles, and additional landscaping. The goal of these activities would be to provide improved scenic quality ratings within the project area as measured by TRPA.

By meeting the identified need for aesthetic improvements, the proposed project will implement (fully or partially) projects listed in the *Community Plan* and the *Environmental Improvement Program (EIP)*. By doing so, the project will contribute to the achievement of planning goals at the community and regional level.

CIP Number	Project Category	Project Title / Description	
Scenic		SR 28 Improvements	
Scenic		Sign Program	
Traffic / Air Quality	Sidewalk Program	Sidewalks / amenities along SR 28	

EIP Number	Project Category	Project Title / Description	
93 Scenic		Road Unit 20 Restoration	

Need Four - Improve Water Quality

Primary responsibility for the protection of water quality in the project area rests with the California Regional Water Quality Control Board, Lahontan Region. The controlling document is the plan titled Water Quality Standards and Control Measures for the Lake Tahoe Basin (Basin Plan). That plan sets water quality standards for surface and ground waters, including beneficial uses and objectives that must be maintained or attained to protect those uses. Control measures and prohibitions are identified. Portions of the Kings Beach project area are not currently in attainment of objectives set by the Basin Plan.

Most development in the community of Kings Beach occurred during the 1920s and 1930s, and during the late 1940s and 1950s. Drainage issues were not addressed from an area-wide perspective and water quality treatment was seldom integrated into local systems. Over the last twenty years, several erosion control projects have been constructed up-gradient (north) of SR 28. At this time, culverts underneath SR 28 do not meet applicable standards – they are too small to convey the required design flows. The capacity of up-gradient facilities is reduced as soon as they tie into existing roadway facilities. Also, very few storm water treatment facilities are present downstream (south) of SR 28. Facilities are necessary to accommodate and treat storm water generated in the project corridor, and storm water conveyed into the area from up-gradient.

Portions of the existing drainage system, constructed in the 1960's, are undersized and provide no water quality treatment. Recent upgrades north of SR 28 have increased drainage network capacity and improved sediment control. However, the restricted capacity of culverts underneath the roadway limits the extent to which up-gradient waters can be conveyed through the right-of-way. Also, proximity to Lake Tahoe limits options available for the treatment of storm water runoff. Because of these limitations, existing area-wide storm water treatment facilities do not meet standards set by local regulatory agencies.

There is a <u>need</u> to improve area-wide drainage systems and water quality in Kings Beach. These improvements are necessary if Placer County and Caltrans are to achieve water quality goals set by TRPA and Regional Water Quality Control Board plans.

Meeting this need will involve the consideration of four major factors. First, limited space is available to accommodate large treatment facilities that could address area-wide storm water flows. As a result, emphasis needs to be placed on source control. Second, storm water collection facilities will be needed along SR 28, along side streets, and in parking areas. Third, conveyance facilities will need to be sized to accommodate agreed upon design flows. This includes natural streams, such as Griff Creek, and storm water conveyances. Of particular concern will be conveyances that extend under SR 28. Fourth, treatment will be required for collected and conveyed storm water.

By satisfactorily meeting the identified need for improving water quality, the proposed project will implement (fully or partially) several projects listed in the *Community Plan* and in the year 2001 *EIP* update. By doing so, the project will make a substantial contribution toward achieving planning goals at the community and regional level.

CIP Number	Project Category	Project Title / Description
SEZ Restoration		Griff Creek
Water Quality	BMP Implementation	SR 28 Shoulders
Water Quality	BMP Implementation	Parking Lots
Water Quality	BMP Implementation	Backstreet Areas
Water Quality	Area-Wide Drainage	Implements Area-Wide Systems
Water Quality	Treatment Facilities	Conduct Study
EIP Number	Project Category	Project Title / Description
15	Water Quality	Kings Beach Residential Area
649 *	Soils / SEZ	Restore 40 Acres of SEZ – Placer County
733	Water Quality	Kings Beach Industrial Area
10060	Water Quality	Kings Beach Commercial Area

The area of implementation for this EIP project is countywide. While some improvements associated with this EIP project may be located in the Kings Beach Commercial Core Area, they need not be.

Project Purposes

A purpose is a subsidiary action that can be taken while attempting to achieve an identified need. Several potential project purposes have been identified during project team meetings, agency scoping, and public workshops. Placer County has identified the following purposes as pertinent to the present planning process.

- Improve fisheries access along Griff Creek: Culverts under SR 28 along Griff Creek will likely be replaced. This provides an opportunity to design the new conveyance features (as part of the overall proposed water quality improvements) in such a way as to accommodate fish movement during a variety of flow scenarios.
- Minimize adverse impacts to private property: The construction of elements identified as necessary to meeting the project's needs may require intrusions onto private property. To the extent practicable, such intrusions should be limited.
- Provide replacement parking for any parking lost along SR 28 due to the project: The change in parking availability due to various potential project activities (roadway, water quality, and pedestrian access improvements) would vary depending on the project's final configuration. Factors most likely to affect parking impacts include the number and

- nature of intersections slated for improvement, and the width of roadside amenities (sidewalks and landscaping).
- Improve public safety: Providing improved pedestrian and bicyclist facilities, and improved intersections will improve public safety substantially. During project design, attention will be directed toward the identification of other measures that might improve public safety even further. To the extent practicable, such measures will be integrated into the project design.
- Consider post-construction operation and maintenance costs associated with water quality improvements: Once constructed, many water quality improvements will require routine operational expenses and regular maintenance. The project design will attempt to achieve a reasoned blend between functionality and maintainability. Operation and maintenance costs will be estimated for each alternative.
- Maintain circulation patterns: As noted above, SR 28 is a component of the California state highway system and, as such, the project design must maintain an appropriate and adequate circulation pattern. The proposed project will need to be designed and implemented in such a manner that addresses traffic circulation.

These purposes will be considered during the development of the project's preliminary and final design, and during mitigation planning.

It is possible that meeting some or all of these project purposes may allow the proposed project to implement (fully or partially) projects listed in the *Community Plan* and in the year 2000 *EIP* update. By doing so, the project will make a substantial contribution toward achieving planning goals at the community and regional level.

CIP Number	Project Category	Project Title / Description	
Traffic / Air Quality	Parking Program	Community Parking Lots	
SEZ Restoration Griff Creek		Griff Creek	
Recreation		Recreation Trail System	
EIP Number	Project Category	Project Title / Description	
410	Fisheries	Griff Creek Stream Habitat, Culvert Improvements	

IV. LIST OF ALTERNATIVES

CEQA and TRPA require that consideration be given to a range of alternatives that could feasibly achieve the project's goals. The Kings Beach Commercial Core Improvement Project consists of four integrated elements: modification of the roadway, construction of water quality improvements, construction of improved pedestrian access, and construction of parking areas. Alternatives are identified for each element of the overall project.

Roadway Design Options

Caltrans prepared a traffic analysis of the project area. That analysis reviews current and projected levels-of-service, defines seven alternative project configurations, and reviews those alternatives on the basis of how they would affect projected traffic conditions. Also, the analysis

reviews intersection data to determine the need for additional signals. The traffic report concluded that six of the seven alternatives could be dropped from further consideration. The one remaining alternative is proposed for evaluation within the environmental document. Since that time, members of the public have proposed an alternate roadway design. This alternative would reduce the number of lanes and would make use of roundabouts in lieu of signals at key intersections. Two roadway design options, in addition to the No Action/No Project alternative, are proposed for consideration in the environmental document.

- No Action/No Project: No modifications would take place to the roadway.—The existing roadway with two travel lanes in each direction would be retained.
- Roadway Option A: The roadway would consist of two 3.6m wide vehicle travel lanes in each direction (roadway width of 14.4m). Turn pockets would be present at four signalized intersections. Two of the signals exist currently (SR 267 and Coon Street), while the other two (Bear Street and Fox Street) are proposed. Turn pockets would be sized to accommodate anticipated turning vehicle volumes. A continuous center turn lane would not be provided.
- Roadway Option B: The roadway would consist of one 3.6m wide vehicle travel lane in each direction, separated by a 3.6m wide left turn lane (roadway width of 10.8m). Roundabouts would be constructed at the Bear, Coon and Fox street intersections. The existing signal at SR 267 would remain. To accommodate roundabout geometry, blocklong segments of Brook, Salmon, and Minnow streets would be converted to one-way (east-bound) roadways.

Storm Water Treatment Design Options

The Kings Beach Commercial Core Improvement Project will include a storm water collection, conveyance, and treatment system. That system will be designed to accommodate storm water runoff that flows immediately onto the SR 28 right of way. Caltrans is responsible for storm water collected from the immediate right of way, while Placer County is responsible for the collection of storm water that flows into the right of way from immediately adjacent properties (see the attached study area figure). Conveyance facilities will be designed to accommodate Caltrans and Placer County collected flows, and, as necessary, any upstream, pass through flows. Treatment facilities to be constructed as part of the proposed Kings Beach project will be sufficient to accommodate storm water collected from the Caltrans and Placer County areas of project responsibility.

Specific types of treatment and treatment site locations have not yet been identified. However, vacant parcels located within the immediate vicinity have been included in the study area (see the attached study area figure). It is proposed that the environmental document examine many of the identified parcels found most feasible as treatment locations, with the expectation that environmental review will result in a comparative ranking of the parcels. The environmental document will also examine the No Action/No Project alternative in which no storm water collection, conveyance, and treatment system would be installed.

The primary goal of this project element would be to meet water quality goals required by the other project improvements. A secondary goal is to ensure that project specific improvements and facilities are compatible with existing and proposed area-wide systems.

Bicycle-Pedestrian Design Options

Two bicycle-pedestrian access options were identified in the Commercial Core Improvement Project Feasibility Study (Harding ESE 2000). However, only one of these options, in addition to the No Action/No Project option, is recommended for continued consideration. Potentially, a local agency could assume responsibility to maintain improvements located along side the roadway, including sidewalks, planters, street lighting, landscaping, and other amenities.

- <u>No Action/No Project</u>: No modifications would take place. No facilities for bicycle-pedestrian access would be constructed.
- <u>Bicycle-Pedestrian Access (With Striped Bike Lane)</u>: A 3.2m landscape-sidewalk area is proposed along both sides of SR 28, from SR 267 to Chipmunk Street. In some areas, the sidewalk would be 3.2m in width and would not contain landscaping. In other areas, the width of the landscape and sidewalk areas would vary from 1.1 to 1.4m and 1.8 to 2.1m, respectively, to maintain a total width of 3.2m. A 2.4m wide striped lane would be present along each side of the road except for constraint points, such as intersections, etc., where a 1.5m minimum bike lane shall be provided. That 2.4m wide striped lane would allow for parallel parking. Also, a 1.5m, striped lane would be provided for bicycle travel.

Parking Options

LSC Transportation Consultants, Inc. has conducted a parking study (2000) for the Kings Beach commercial core. That study was intended to assess the impacts of proposed streetscape improvements, evaluate potential parking improvements, and provide a plan for recommended improvements. Results of the study show that the current commercial parking supply consists of 1,135 legal spaces (excluding residential and lodging properties). Based on a worst-case analysis, approximately 180 spaces might be lost as a result of the project. The immediate project goal is to replace lost parking spaces. By providing additional parking in appropriate locations, parking losses induced by the project could be offset.

Twenty potential parking lot locations were identified as part of the parking study (LSC 2000), or as a result of subsequent field reviews. It is proposed that the environmental document examine many of the identified locations found most feasible as potential parking sites, with the expectation that environmental review will result in a comparative ranking of the parcels. Selection criteria might include operational advantages and disadvantages (such as ease of traffic and pedestrian movements), visibility to motorists, financial feasibility, and environmental issues. The environmental document will also examine the No Action/No Project option in which case, no parking would be constructed.

Project Alternatives

Based on the preceding discussion, the completed project would have a potential curb to curb width of either 17.4m or 19.2m under Roadway Option A. This includes a total roadway width of 14.4m. Parking and a potential bike lane along both sides of SR28 would add another 1.5m to 2.4m in width. For Roadway Option B, curb to curb width will equal 13.8m to 15.6m and will include a total roadway width of 10.8m and 3.0m to 4.8m of total bike lane. Beyond the curb, the project will result in an additional 6.4m of landscape sidewalk area (3.2m on each side of the roadway).

Overall project alternatives will be defined based on reasoned combinations of roadway, pedestrian, water quality, and parking options. Specific project alternatives will be defined as studies proceed. The goal would be to have a discrete number of defined project alternatives by the time of the notice of preparation.

V. PROPOSED PROJECT - THE PREFFERED ALTERNATIVE

At this time, Placer County and Caltrans have not identified a preferred alternative. Each of the element project alternatives will be analyzed equally and the end result of the environmental review will be an identification of a recommended alternative.

VI. ENVIRONMENTAL COMPONENTS

Each of the following components are envisioned to be addressed and evaluated in the environmental document:

- 1. <u>Air Quality</u>: Air Quality will be evaluated for both short-term and long-term impacts. Short-term impacts associated with the project will be from construction activities. Long-term impacts include stationary, mobile and point source emissions.
- 2. <u>Water Quality</u>: Water Quality will be evaluated for capacity and storm water treatment and analysis of existing conditions. A preliminary Drainage Master Plan has been prepared by Placer County. Additional studies are under way to refine treatment needs and methods.
- 3. <u>Noise</u>: Noise will also be evaluated for potential short-term and long-term impacts. The short-term analysis will be based on construction activities. Long-term noise impacts will be evaluated including stationary, mobile and point source emissions.
- 4. <u>Soils/Geology</u>: Soil characteristics will be evaluated for potential environmental effects based on Land Capability, Land Coverage as well as the slope and erosion hazard within the project area.

- 5. <u>Wildlife</u>: The evaluation will include potential effects on existing wildlife habitat, if any, as well as any species identified as sensitive within the project area.
- 6. <u>Vegetation</u>: Any impacts as a result of this project to existing native vegetation will be addressed. Sensitive plant species will be identified if any exist.
- 7. <u>Traffic</u>: Traffic impacts will be assessed at each intersection within the project area. Pedestrian circulation, vehicle miles traveled, etc. will also be evaluated. A preliminary Traffic Analysis has been prepared by Caltrans.
- 8. <u>Parking</u>: Any potential impacts to existing parking will be analyzed as well as mitigation to replace loss of parking spaces as a result of this project. LSC Transportation Consultants, Inc. have also prepared a Parking Study.
- 9. <u>Hazardous Waste</u>: Any disturbance of contaminated areas, exposure to workers during construction process, or spills as a result of construction will be evaluated.
- 10. <u>Scenic</u>: The visual resource will be analyzed for the appropriate scenic roadway unit and recreation unit. Scenic thresholds and impacts will be evaluated in the environmental document from selected viewpoints.
- 11. <u>Cultural and Historic</u>: An evaluation will be based on site disturbance and mitigation measures will be identified if any artifacts are encountered during construction.
- 12. <u>Economics</u>: The effects of relocated parking spaces for local businesses as well as the impacts related to the improvement of pedestrian access will be analyzed.
- 13. <u>Public Utilities</u>: The impacts to the local public utilities will be addressed in the environmental document.

VII. PROBABLE EFFECTS TO THE ENVIRONMENT

Probable environmental effects of the proposed Kings Beach Commercial Core Project may include impacts on air quality, water quality, noise, traffic, parking, wildlife, vegetation, soils, scenic resources, cultural and historic resources, and economics as referenced previously. Project impacts will be assessed in light of established agency thresholds. Mitigation measures will be proposed for all identified significant impacts.

VIII. NAMES AND ADDRESSES OF NOTIFIED PERSONS/AGENCIES

The following agencies have been invited to participate in scoping the environmental document for the Kings Beach Commercial Core Improvement Project.

Placer County

Ken Grehm, Bob Costa, Rebecca Bond - Project Manager 11414 B Avenue Auburn, CA 95603

CalTrans- District 3

Dick Melim, Mike Forga, Steve Hetland, Mike Bartlett P.O. Box 911 Marysville, CA 95901

Federal Highway Administration

RC Slovensky, Christina Hibbard 980 9th Street, Suite 400 Sacramento, CA 95814

Tahoe Regional Planning Agency

Richard Wiggins, Charles Emmett P.O. Box 1038 Zephyr Cove, NV 89448

North Tahoe Public Utility District

John Hassenplug
P.O. Box 139
Tahoe Vista, CA 96148

Lahontan Water Quality Control Board

Lauri Kemper, Robert Erlich 2501 Lake Tahoe Boulevard South Lake Tahoe, CA 96150

California Department of Fish and Game - Region 2

Ron Perrault

1701 Nimbus Road Rancho Cordova, CA 95670

California Tahoe Conservancy

Ray Lacey, Dave Zander
2161 Lake Tahoe Boulevard, Suite 2
South Lake Tahoe, CA 96150

North Tahoe Regional Advisory Council

Steve Kastan

P.O. Box 1238 Carnelian Bay, CA 96140

Truckee-North Tahoe Transportation Management Association

Jennifer Merchant

P.O. Box 7108 Tahoe City, California 96145

North Lake Tahoe Resort Association

Ron McIntyre

P.O. Box 1757 Tahoe City, CA 96145

North Tahoe Business Association and Commercial Property Owners

Theresa May Duggan P.O. Box 1023 Kings Beach, CA 96143

League to Save Lake Tahoe

Rochelle Nason, Jon-Paul Harris 955 Emerald Bay Road South Lake Tahoe, CA 96150

Army Corps of Engineers

Michael Finan 1325 J Street

Sacramento, CA 95814-2922

IX. LEAD AGENCY

It is anticipated that the environmental document prepared on behalf of the Kings Beach Commercial Core Improvement Project will need to comply with legal requirements established by the California Environmental Quality Act (CEQA), the National Environmental Policy Act (NEPA), and TRPA. Responsibility for compliance with NEPA lies with the Federal Highway Administration (FHWA). Placer County is responsible for compliance with CEQA; other state agencies will participate either as trustee agencies or responsible parties. TRPA will be responsible for compliance with its Code of Ordinances.

The level of documentation anticipated as necessary to comply with each is discussed below:

• CEQA: At this time, Placer County is recommending that an Environmental Impact Report be prepared. Issues to be addressed include the potential for aesthetic impacts,


- impacts to special status plant and animal species, water quality impacts, impacts to cultural resources, noise and air quality impacts, the disruption of local utilities, and other potential impacts to resources administered or regulated by the State of California.
- NEPA: At this time, FHWA is recommending that an Environmental Assessment be prepared. Issues to be addressed include compliance with U.S. Corps of Engineers regulations regarding the management of wetlands, U.S. Fish and Wildlife regulations regarding special status plants and animals, and federal regulations regarding the administration of cultural resources. If significant impacts are identified, an environmental impact statement may need to be prepared.
- TRPA: At this time, TRPA is recommending that an Environmental Impact Statement be prepared. Issues to be addressed include project compliance with ordinances dealing with water quality, land use planning (the *Community Plan*), coverage, noise and air quality, visual resources, cultural resources, traffic, and other resources administered or regulated by TRPA.


It is anticipated that all of these regulatory needs can be satisfied within the context of a single environmental document. It is estimated that the environmental document will require 24 to 36 months to complete.


X. PROJECT TIME SCHEDULE

Key scheduling milestones for the Kings Beach Commercial Core Improvement Project are identified below. Tentative completion dates are also provided.

PSR-PDS Approved
Begin Environmental Study and Project Report
Project Approval and Environmental Clearance
Submit Utility Conflict Maps
County Submits Maps to Caltrans Right-of-Way
Engineering Appraisal Maps Approved by Caltrans
District PS&E Approval
All Permits Acquired
Complete PS&E and Bid Package
Right-of-way Certification
Advertise for Construction Bids
All Funding Secure
Begin Construction
Complete Construction









COMMERCIAL CORE IMPROVEMENT PROJECT DWAY OPTION A - 4 LANES WITH SIGNALS ROA KINGS BEACH

(Plan size prints are available from the Dept.



of Public Works) (Plan size prints are available from the Dept.


AY OPTION B - 3 LANES WITH ROUNDABOUTS



KINGS BEACH CORE IMPROVEMENT PROJECT STREETSCAPE CONCEPT SIMULATIONS




BEFORE




AFTER

Figure 6. Curb Sidewalk with Informal Planting

KINGS BEACH CORE IMPROVEMENT PROJECT STREETSCAPE CONCEPT SIMULATIONS



BEFORE



AFTER

Figure 7. Town Sidewalk with Street Trees



PLACER COUNTY PLANNING DEPARTMENT

AUBURN OFFICE TAHOE OFFICE

11414 B Avenue

565 W. Lake Blvd./P. O. Box 1909

Reserved for Date Stamp

Auburn, CA 95603

Tahoe City CA 96145

530-889-7470 /FAX 530-889-7499 530-581-6213 /FAX 530-581-6282 **Web page:** www.placer.ca.gov/planning **Email:** planning@placer.ca.gov

INITIAL PROJECT APPLICATION

NOTE: PURSUANT TO THE POLICY OF THE BOARD OF SUPERVISORS, THE PLANNING DEPARTMENT CANNOT ACCEPT APPLICATIONS ON TAX DELINQUENT PROPERTY. APPLICATIONS SUBMITTED ON PROPERTIES WHICH CONTAIN ZONING VIOLATIONS MAY ALSO BE REJECTED BY THE COUNTY.

NOTICE: THIS PROJECT MAY BE SUBJECT TO FEES IMPOSED BY THE DEPARTMENT OF FISH AND GAME. (FISH AND GAME CODE SECTION 711.4 ET. SEQ.; PUBLIC RESOURCES CODE SECTION 10005) UNLESS A PROJECT IS DENIED NO ACTION WHICH REQUIRES PAYMENT OF FEES SHALL BE DEEMED FINAL UNTIL SUCH FEES ARE PAID (SECTION 21089(B) OF THE PUBLIC RESOURCES CODE).

	OFFICE USE ONLY	
Zoning Several, primarily commerce Map # 34	Environmental Determination: F	ile#s: 614Q-3739
Map # 34 V	Exempt #	
G.P. Designation Same as Joning		
	Negative Declaration	Accepted by <u>&C</u>
Applicable G.P./C.P.: Community 16 Kings Black General	<u>x</u> EIR Name of EIR:	Hearing Body Brd Supes.
Kings Black General		Date Filed 11-18-02
Geographical Area <u>East</u>	SCH#	Date Accepted as Complete:
Sphere of Influence Airport Overflight	Posters	
Airport Overflight	Taxes	Affordable Housing A IM
	Tax Rate Area	Supervisorial Dist 5
	A	
TO BE C	OMPLETED BY THE APPLICA	NT
1. Project Name (current and previous) <u>Ki</u>	ngs Beach Commercial Core Impro	vement Project
	<u></u>	
2. Property Owner <u>California Department</u>	- · · · - · - ·	County, Private Owners
Full Address		
TelephoneF	ax	E-Mail
3. Applicant Placer County Department of	•	
Full Address <u>11444 B Avenue</u> , DeWitt C	enter, Auburn, CA 95603	
Telephone (530) 889-7615 F	ax <u>(530)</u> 886-3540	E-Mail rbond@placer.ca.gov
4. Size of Property (acreage or square foota		
5. Assessor's Parcel Number(s) Not applica	ble	
6. Project Location Project area is located	in the community of Kings Beach.	along the north shore of Lake Tahoe
near the California/Nevada state line, in		
project limits (Kings Beach commercial		
the western boundary to the intersection		
Brook, and Salmon Avenues are addition		
the south. See Figure 1. for project area		
Be specific: cross street	s, distance and direction from neare	st intersection, etc.)

		CONTINUED ON REVE	RSE
7. ————————————————————————————————————		mits by Placer County does the pro _X_ Environmental Impact Assessr _Extension of Time General Plan Amendment Major Subdivision (5+ parcels) Minor Boundary Adjustment Minor Subdivision (4 and under	ment Quest. Minor Use Permit X Project undertaken by County Rezoning Variance Other (Explain)
8.		approval by other governmental ag WA, Lahontan RWQCB, California	gencies? X Yes No. If so, which Tahoe Conservancy
9.	Electricity Sierra Pacific Powe Telephone Pacific Bell	ies provide the following services? Fire Protection North Tahoe Fir Natural Gas Elementary School	Water NTPUD
	Describe the project in detail so phasing, duration and construct attach additional pages, if necess The proposed project is a "material proposed project involves for pedestrian access improvements a portion of SR28 is needed to improvements to improve traffinclude either A.) Two vehicl intersections. Two signals exist Street) are proposed, or B.) Roundabouts would be construct would remain. Pedestrian access roadway, along with landscape a of new drainage and water treats to protect the water quality of provide off-highway parking are	to that a person unfamiliar with the stion activities associated with the stary. In street" beautification project for integrated project elements, we water quality improvements, and address grade variations that causific circulation and pedestrian croes travel lanes in each direction of the currently (SR267 and Coon Street Cone vehicle travel lane in each extend at the Bear, Coon, and Fox Street at the Bear,	e project would understand the purpose, size, project. In response to this question, please the commercial core of Kings Beach. The hich include modification of the roadway, replacement parking. Partial reconstruction of se poorly draining low spots and intersection ssings. Roadway options being considered with turn pockets present at four signalized eet) and the other two (Bear Street and Fox direction, separated by a center turn lane, eet intersections. The existing signal at SR267 dewalks and bike lanes along each side of the project includes replacement and construction lards set by local and state regulatory agencies so provide parallel parking along SR28 and roposed project improvements. Construction uction season and completing in the 2008
11.		re-described project, and to receive	for project approvals by Placer County, to act all notices, correspondence, etc. from Placer
	harmless from any defense cost brought as a result of an approve effect on a form provided by the The signature below authorizes	ets, including attorneys' fees or of ral concerning this entitlement. I also the County and available for my inspe- any member of the Placer County	Development Review Committee (DRC), and
	Signature(s) of Owner(s):	ssary, to enter the property/structure Please	(s) that is(are) the subject of this application. Print
	folial Code		ert Costa Publicharks Manager



PLACER COUNTY PLANNING DEPARTMENT

Reserved for Date Stamp

AUBURN OFFICE **11414 B Avenue**

TAHOE OFFICE

565 W. Lake Blvd./P. O. Box 1909

Auburn, CA 95603

Tahoe City CA 96145 530-889-7470 /FAX 530-889-7499 530-581-6213 /FAX 530-581-6282

Web page: www.placer.ca.gov/planning Email: planning@placer.ca.gov

ENVIRONMENTAL IMPACT ASSESSMENT QUESTIONNAIRE

~		aps: 20 full size, <u>folded</u> , 1 <u>reduced</u> to 81/2x11" Receipt No plications: 20 Filing Fee:	
		the policy of the Board of Supervisors, the Planning Department cannot accept applications on to property with existing County Code violations.	x
SEE F	ILI	IG INSTRUCTIONS ON LAST PAGE OF THIS APPLICATION FORM	
(ALL)	1.	Project Name (same as on IPA) Kings Beach Commercial Core Improvement Project	
PLNG	2.	What is the general land use category for the project? (e.g.: residential, commercial, agricultural, cindustrial, etc.) Commercial, recreation, and residential)r —
PLNG	3.	What is the number of units or gross floor area proposed? Not applicable	_
DPW	4.	Are there existing facilities on-site (buildings, wells, septic systems, parking, etc.)?	
		Yes X No If yes, show on site plan and describe: <u>Buildings, roadways, parking, and stort water drainage facilities are located within the project area.</u>	<u>n</u>
DPW	5.	Is adjacent property in common ownership? Yes No_X_ Acreage	
		Assessor's Parcel Numbers Provided on the attached plans	_
PLNG	6.	Describe previous land use(s) of site over the last 10 years: There has been no change from existing land uses including commercial, recreation, and residential.	g
GEOL	OG	Y & SOILS	
NOTE:		Detailed topographic mapping and preliminary grading plans may be required following review of the information presented below.	v
DPW	7.	Have you observed any building or soil settlement, landslides, slumps, faults, steep areas, rock falls mud flows, avalanches or other natural hazards on this property or in the nearby surrounding area Yes No_X_	
		If yes, describe:	_
DPW	8.	How many cubic yards of material will be imported? <u>Unknown at this time</u>	_
		Exported? <u>Unknown</u> Describe material sources or disposal sites, transport methods as haul routes: <u>Any exported material would be sent to a TRPA and Placer County approved landflocated outside the Lake Tahoe Basin. Sources of any needed fill have not been determined. Fill as material slated for disposal would be transported via truck.</u>	ill
DPW	9.	What is the maximum proposed depth and slope of any excavation? The majority of the project woul require only slight modification of surfaces for roadway and parking lot construction. The maximum	

		proposed depth for excavation will be in association with utility relocation and installation of storm
		water conveyance structures. The project area is relatively flat and no hillsides are present to excavate. Fill? There will be limited amount of fill necessary for the proposed project. Fill will be used in
		association with surface modification for roadways and parking lots. Fill will also be used to replace
		material excavated during utility relocation and the installation of storm water conveyance structures.
DPW	10.	Are retaining walls proposed? Yes NoX If yes, identify location, type, height, etc:
DPW	11.	Would there be any blasting during construction? Yes No_X If yes, explain:
DPW	12.	How much of the area is to be disturbed by grading activities? This is unknown at this phase of the project.
PLNG	13.	Would the project result in the direct or indirect discharge of sediment into any lakes or streams?
DEH		Yes No_X If yes, explain:
DPW	14.	Are there any known natural economic resources such as sand, gravel, building stone, road base rock, or mineral deposits on the property? Yes NoX If yes, describe:
		EE & HYDROLOGY
		eliminary drainage studies may be required following review of the information presented below.
DPW	15.	Is there a body of water (lake, pond, stream, canal, etc.) within or on the boundaries of the property?
		Yes X No If yes, name the body of water here and show location on site plan: <u>Lake Tahoe</u> , <u>Griff Creek</u> , and an unnamed ephemeral drainage.
DEH	16.	If answer to #15 is yes, would water be diverted from this water body? Yes No_X
DEH	17.	If yes, does applicant have an appropriative or riparian water right? Yes NoX
DEH	18.	Where is the nearest off-site body of water such as a waterway, river, stream, pond, lake, canal, irrigation ditch, or year-round drainage-way? Include name, if applicable: There is an unnamed stream east of Tahoe Vista, CA, approximately 0.5 miles west of the project.
		What percentage of the project site is presently covered by impervious surfaces? The current roadway, parking areas, and parcels on which storm water facilities are present exhibit impervious coverage. Proposed locations for sidewalks and other roadside improvements are characterized by soft coverage (i.e., compacted and unvegetated sediment). At this point, coverage has not been quantified. It is assumed that existing coverage accounts for approximately 80% of the proposed project area.
		After development? Soft coverage will be replaced by impervious coverage associated with sidewalks and roadside parking. Construction of off-site parking may also represent additional coverage. At this time, detailed coverage estimates have not been prepared.
DPW	19.	Would any run-off of water from the project enter any off-site canal/stream? Yes NoX
DEH		If answer is yes, identify:
DEH	20.	Will there be discharge to surface water of waste waters other than storm water run-off?
		Yes No_X If yes, what materials will be present in the discharge?
		What contaminants will be contained in storm water run-off? Storm water runoff derived from constructed roadway and parking lot surfaces will contain contaminants typical of such surfaces, including grease, oil, sediment, and some metals. The proposed project contains elements that would allow for the collection, conveyance, and treatment to the maximum extent practicable of all storm water

	<u></u>	runoff.
DPW	21.	Would the project result in the physical alteration of a body of water? Yes No_X_
		If so, how?
		Will drainage from this project cause or exacerbate any downstream flooding condition?
		Yes No_X If yes, explain:
DPW	22.	Are any of the areas of the property subject to flooding or inundation? Yes_X_ No_ If yes, accurately identify the location of the 100-year floodplain on the site plan. Lake Tahoe and Griff Creek drainage area have been identified as areas inundated by the 100-year flood.
DPW	23	Would the project alter drainage channels or patterns? Yes X No If yes, explain: A component of the project involves collection, conveyance, and treatment of urban storm water runoff. In the process of doing so, the project may have the potential to alter existing urban drainage patterns. The extent to which these urban drainage patterns will be altered is yet to be determined.

VEGETATION AND WILDLIFE

- NOTE: Detailed studies or exhibits such as tree surveys and wetland delineations may be required following review of the information presented below. Such studies or exhibits may also be included with submittal of this questionnaire. (See Filing Instructions #8 and #9 for further details.)
- PLNG 24. Describe vegetation on the site, including variations throughout the property: The commercial and residential areas within and adjacent to the project area are relatively flat with a vegetated overstory dominated by Jeffrey pine, incense cedar, and some white fir. Many of the trees within the project area are considered late seral/old growth vegetation. Griff Creek is located on the west edge of the project area and supports the largest area of riparian vegetation in the project area. The riparian vegetation includes willows, mountain alder, rushes, sedges, grasses, and forbs.
- PLNG 25. Estimate how many trees of 6-inches diameter or larger would be removed by the ultimate development of this project as proposed: The project should require only limited tree removal in conjunction with the roadway improvements, off-site parking, and off-site water quality improvements. Project design will minimize tree removal to the maximum extent possible. The number of trees to be removed that are 6-inches in diameter or larger is not known at this time.
- PLNG 26. Estimate the percentage of existing trees which would be removed by the project as proposed <u>Very little</u> tree removal is anticipated as a result of the proposed project (see response to #25). As a result, the percentage of existing trees to be removed will be quite low.
- PLNG 27. What wildlife species are typically found in the area during each of the seasons? Wildlife associated with Griff Creek's riparian corridor includes song sparrow, mallard, brook trout and other fishes. Wildlife found throughout the rest of the project area includes species associated with coniferous forest such as pygmy nuthatch and mountain chickadee, as well as species found commensally with humans including cliff swallow and western gray squirrel.
- PLNG 28. Are rare or endangered species of plants or animals (as defined in Section 15380 of the California Environmental Quality Act Guidelines) found in the project area? Suitable habitat for Tahoe yellow cress does occur in and adjacent to the project area, including the coarse sands of active beaches, stream inlets, beach dunes, and backshore depressions, all within a few feet of the existing water table.

 A field investigation was conducted in July 2001 and again in September 2002 along the beachfront and backshore areas within the project. Tahoe yellow cress was not located within the project area during either survey. In addition, general habitat for the Truckee barberry was also present; however, this species has not been identified within the project area.
- PLNG 29. Are any Federally listed threatened or endangered plants, or candidates for listing, present on the project

		site as proposed? If uncertain, a list is available in the Planning Department: The bald eagle was identified by agencies as potentially occurring within the project area. While suitable nesting habitat is	
		not present, this species may use the area to forage. The Truckee barberry was also surveyed for within suitable habitat in the project area, but was not identified to occur.	
PLNG	30.	Will the project as proposed displace any rare of endangered species (plants/animals)? No	
PLNG		What changes to the existing animal communities' habitat and natural communities will the project cause as proposed? The majority of the project will occur in previously disturbed areas. Changes, if any, will be minimal. Landscaping proposed as part of the project may provide some limited habitat, especially for species tolerant of human presence.	
PLNG	32.	Is there any rare, natural community (as tracked by the California Department of Fish and Game Natural Diversity Data Base) present on the proposed project? A search of the database indicates that none are present.	
PLNG	33.	Do wetlands or stream environment zones occur on the property (i.e., riparian, marsh, vernal pools, etc.)? Yes_X_ No	
PLNG	34.	If yes, will wetlands be impacted or affected by development of the property? Yes_X No	
PLNG	35.	Will a Corps of Engineers wetlands permit be required? Yes X No	
PLNG	36.	Is a letter from the U.S. Army Corps of Engineers regarding the wetlands attached?	
		Yes No_X	
FIRE	PRO	DTECTION	
DPW	37.	How distant are the nearest fire protection facilities? Within the project area	
		Describe: A fire station is located at the intersection of SR28 and Hwy 267 and is staffed by the local fire department.	
DPW	38.	What is the nearest emergency source of water for fire protection purposes? Municipal	
		Describe the source and location: Hydrants occur throughout project area and Kings Beach	
DPW	39.	What additional fire hazard and fire protection service needs would the project create? None	
		What facilities are proposed with this project? None	
		For single access projects, what is the distance from the project to the nearest through road? N/A	
		Are there off-site access limitations that might limit fire truck accessibility, i.e. steep grades, poor road alignment or surfacing, substandard bridges, etc.? YesNoX If yes, describe:	

NOIS	SE	
NOT	E:	Project sites near a major source of noise, and projects which will result in increased noise, may require a detailed noise study prior to environmental determination.
DEH	40	Is the project near a major source of noise? <u>Yes</u> If so, name the source(s): Vehicle traffic along State Route 28
DEH	41	What noise would result from this project - both during and after construction?
		Construction would temporarily elevate noise levels but there is no long term noise anticipated beyond what the project area currently experiences.
		ALITY ecific air quality studies may be required by the Placer County Air Pollution Control District (APCD). It is suggested that applicants with residential projects containing 20 or more units, industrial, or commercial projects contact the APCD before proceeding.
APCD	42	
		Auto emissions from highway and roadway traffic and commercial, industrial, and residential sources
APCD	43.	What are the type and quantity of vehicle and stationary source (e.g. woodstove emissions, etc.) air pollutants which would be created by this project at full buildout? Include short-term (construction) impacts: Short term sources of air pollutants will be related to construction of the project and may include construction equipment exhaust and dust. The quantity of emissions associated with construction of the project has not yet been determined. In the long term, the project does not increase the capacity of the roadway and will not result in an increase in air pollutants associated with roadway use.
APCD	44.	Are there any sensitive receptors of air pollution located within one quarter mile of the project (e.g. schools, hospitals, etc.)? <u>Yes (schools)</u> Will the project generate any toxic/hazardous emissions? <u>No. The schools are located several blocks away from project elements.</u>
APCD	45.	What specific mobile/stationary source mitigation measures, if any, are proposed to reduce the air quality impact(s) of the project? Quantify any emission reductions and corresponding beneficial air quality impacts on a local/regional scale. To reduce air quality impacts from short term sources, dust abatement measures will be implemented as well as all other Placer County and TRPA imposed standards for construction within the Lake Tahoe Basin. It should be noted that one purpose of the project is to efficiently move traffic through the Kings Beach Commercial Core area. As a result, it is anticipated that the project will have beneficial impacts to air quality at the local level. The project will also result in the stabilization of areas now characterized as soft cover (compacted and unvegetated sediment). That stabilization effort will have beneficial impacts to air quality as well.
APCD	46.	Will there be any land clearing of vegetation for this project? Yes How will the vegetation be disposed? At this time, it is expected that vegetation clearing will be required only in conjunction with offsite parking lots and installation of water quality treatment facilities. All material will be disposed of at a TRRA and Placer County enproved landfill legated outside of the Lake Taboo Pagin

WATER

NOTE: Based upon the type and complexity of the project, a detailed study of domestic water system capacity and/or groundwater impacts may be necessary).

DPW 47. For what purpose is water presently used onsite? <u>Current water use within the immediate project area</u> (roadway, potential parking, and potential water quality treatment areas) is limited. <u>Some potential parking and water quality areas are currently occupied by commercial and residential facilities and those facilities are supplied by municipal sources.</u>

		What and where is the existing source? <u>NTPUD</u> the Kings Beach, including the project area.	provides municipal water service to the community of	
		Is it treated water intended for domestic use? Yes		
		What water sources will be used for this project? The only use of water associated with the proposed project is the irrigation of landscaping during the growing season. Construction of the proposed project does not include a domestic water system nor will there be a need for groundwater withdrawal. Water used for irrigation of landscaping will be provided by NTPUD.		
		Domestic: None Irrig	ation: Municipal	
		Fire Protection: Municipal Other	: Water trucks for dust control during construction	
	What is the projected peak water usage of the project? <u>Summer – for irrigation of landscaping.</u> Is the project within a public domestic water system district or service area? <u>Yes</u>		ect? Summer – for irrigation of landscaping.	
			n district or service area? Yes	
If yes, will the public water supplier serve this project? Yes		ect? Yes		
		What is the proposed source of domestic water? Do	omestic service not required	
. ,		What is the projected peak water usage of the project? Summer – for irrigation of landscaping.		
DEH	48.	8. Are there any wells on the site? <u>Unknown</u> If	so, describe depth, yield, contaminants, etc:	
		Show proposed well sites on the plan accompanying	g this application.	

AESTHETICS

NOTE: If the project has potential to visually impact an area's scenic quality, elevation drawings, photos or other depictions of the proposed project may be required.

- PLNG 49. Is the proposed project consistent/compatible with adjacent land uses and densities? Yes
- PLNG 50. Is the proposed project consistent/compatible with adjacent architectural styles? Yes
- PLNG 51. Would aesthetic features of the project (such as architecture, height, color, etc.) be subject to review?

 Yes By whom? TRPA, Placer County, and Caltrans
- PLNG 52. Describe signs and lighting associated with the project: <u>Standard Caltrans signage will be included as needed along the roadway</u>. Street lighting will be included as part of the proposed project. <u>Design of lighting will be consistent with TRPA and Placer County standards</u>.
- PLNG 53. Is landscaping proposed? Yes If so, describe and indicate types and location of plants on a plan

 Landscaping is proposed for along SR28 and may be included as an element in offsite parking.

 Vegetation included will be consistent with TRPA's recommended plant list. Roadways and sidewalks will have planters and tree pockets.

ARCHAEOLOGY/HISTORY

NOTE: If the project site is on or near an historical or archaeological site, specific technical studies may be required for environmental determination.

- PLNG 54. What is the nearest historic site, state historic monument, national register district, or archaeological site?

 Records indicate that Washoe Indians did occupy terraces on either side of Griff creek as it enters Lake

 Tahoe. Traces of their presence were found during an archaeological inventory of the project area.

 Historic period activities in the area began in the 1870s and were related to the lumbering industry.

 Traces of this use have not been identified in the project area. Development of the community of Kings

 Beach began in the 1920s. This information is in the process of being collected. An architectural inventory will be conducted to determine if buildings are present that reflect this early part of the community's development.
- PLNG 55. How far away is it? <u>Based on studies conducted to date, no archaeological sites are present in the area of immediate project impact. Whether or not architectural resources are present has not been determined.</u>

PLNG	56	Are there any historical, archaeological or culturally significant features on the site (i.e. old foundations, structures, Native American habitation sites, etc.)? <u>Please see the response to item 55.</u>		
SEW	AG	${\mathbb E}$		
NOTE	C: Bas	sed upon the type and complexity of the project, a detailed analysis of sewage treatment and disposal alternatives may be necessary to make an environmental determination.		
DEH	57.	How is sewage presently disposed of at the site? Municipal sewage treatment facilities		
DEH	58.	How much wastewater is presently produced daily? The proposed project will not include any discharge to municipal sewage treatment facilities.		
DEH	59.	What is the proposed method of sewage disposal? <u>Sewage and wastewater will not be generated as a component of the project.</u>		
		Is there a plan to protect groundwater from wastewater discharges? Yes No X If yes, attach a draft of this plan.		
DEH	60.	How much wastewater would be produced daily? None		
DEH	61.	List all unusual wastewater characteristics of the project, if any. What special treatment processes are necessary for these unusual wastes? None		
		Will pre-treatment of wastewater be necessary? Yes No X If yes, attach a description of pre-treatment processes and monitoring system.		
DEH	62.	Is the groundwater level during the wettest time of the year less than 8 feet below the surface of the ground within the project area? Yes, in portions of the project area		
DEH		Is this project located within a sewer district? Yes		
		If so, which district? North Tahoe Public Utilities District Can the district serve this project? No need identified		
DEH	64.	Is there sewer in the area? Yes		
DEH	65.	What is the distance to the nearest sewer line? Within the project area		
		OUS MATERIALS		
Hazardous materials are defined as any material that, because of its quantity, concentration, or physical or chemical characteristics, poses a significant present or potential hazard to human health and safety or to the environment if released into the workplace or the environment. "Hazardous materials" include, but are not limited to, hazardous substances, hazardous waste, and any material which a handler or the administering agency has a reasonable basis for believing that it would be injurious to the health and safety of persons or harmful to the environment if released into the workplace or the environment (including oils, lubricants, and fuels).				
DEH	66.	Will the proposed project involve the handling, storage or transportation of hazardous materials? Yes No_X		
DEH	67.	If yes, will it involve the handling, storage, or transportation at any one time of more than 55 gallons, 500 pounds, or 200 cubic feet (at standard temperature and pressure) of a product or formulation containing hazardous materials? Yes No_X		
DEH	68.	If you answered yes to question #66, do you store any of these materials in underground storage tanks? Yes No If yes, please contact the Environmental Health Division at (916) 889-7335 for an explanation of additional requirements.		
SOLI	D //	ASTE		
DEH		What types of solid waste will be produced? Excavated soils and standard construction debris.		
1/1/11	υ Σ.	How much? <u>Unknown</u> How will it be disposed of? <u>All material will be removed to a</u>		
		Tien with the disposed of: Mit material will be removed to a		

		TRPA and Placer County approved landfill located outside of the Lake Tahoe Basin.			
PARKS/RECREATION					
PLNG	70.	How close is the project to the nearest public park or recreation area? Adjacent to the project area			
	,	Name the area Kings Beach State Recreation Area			
		IMPACT			
PLNG		How many new residents will the project generate? None			
PLNG		Will the project displace or require relocation of any residential units? No What changes in character of the neighborhood (surrounding uses such as pastures, farmland, residential)			
PLNG	75.	would the project cause? None			
PLNG	74.	Would the project create/destroy job opportunities? In the short term, construction related job opportunities will be created. In the long term, the project can be characterized as part of a larger redevelopment of Kings Beach. This should contribute to the revitalization of the area and provide opportunities for jobs.			
PLNG	75.	Will the proposed development displace any currently productive use? There is a potential			
		If yes, describe: <u>Certain project alternatives</u> , <u>construction of a round-about for example</u> , <u>may displace current productive uses</u> . <u>Commercial or other retail development may have to be removed if this alternative is selected</u> .			
TRAN	ISPO	ORTATION/CIRCULATION			
		ailed Traffic Studies prepared by a qualified consultant may be required following review of the			
		information presented below.			
DPW	76.	Does the proposed project front on a County road or State Highway? Yes X No			
		If yes, what is the name of the road? <u>State Route 28</u> . <u>Off-site parking lots and water quality treatment facilities would likely front onto local streets.</u> Given that <u>Kings Beach is unincorporated</u> , these streets are county roads.			
DPW	77.	If no, what is the distance to the nearest County road?			
		Name of road? <u>Secline, Deer, Bear, Coon, Fox, and Chipmunk Streets, also Minnow, Salmon, Brook, Trout, and Rainbow streets.</u>			
DPW	78.	Would any non-auto traffic result from the project (trucks, trains, etc.)? Yes NoX			
		If yes, describe type and volume:			
DPW	79.	What road standards are proposed within the development? <u>Those provided by California Department of Transportation and Federal Highway Administration.</u>			
		Show typical street section(s) on the site plan.			
DPW	80.	Will new entrances onto County roads be constructed? Yes No_X			
		If yes, show location on the site plan.			
DPW	81.	Describe any proposed improvements to County roads and/or State Highways:			
		Project components include the reconstruction of State Route 28, water quality treatment facilities, bike lanes, pedestrian pathways, landscaping, sidewalks, lighting, traffic signals, and other aesthetic improvements.			
DPW	82.	How much additional traffic is the project expected to generate? (Indicate average daily traffic (ADT), peak hour volumes, identify peak hours. Use Institute of Transportation Engineers' (ITE) trip generation rates where project specific data is unavailable): None – no change from existing conditions are			

	,						
		anticipated					
DPW	83.	Would any form of transit be used for traffic to/from the project site? None, other than what is existing					
DPW	84.	What are the expected peak hours of traffic to be caused by the development (i.e., Churches: Sundays, 8:00 a.m. to 1:00 p.m.; Offices: Monday through Friday, 8:00 a.m. to 9:00 a.m., and 4:00 p.m. to 6:00 p.m.)? No change is anticipated from existing conditions.					
DPW	85.	Will project traffic affect an existing traffic signal, major street intersection, or freeway interchange? Yes X No					
DPW	86.	6. What bikeway, pedestrian, equestrian, or transit facilities are proposed with the project? A bike lane is proposed for both sides of SR28, as well as a pedestrian walkway. At least one transit bus stop is also proposed.					
Name	and t	title (if any) of person completing this Questionnaire:					
Signat	ture: _	Solvey Costa Date: 11-18-02					
Title:	Title: Public Works Marriger Telephone: 530-889-7524						



PLACER COUNTY PLANNING DEPARTMENT

11414 B Avenue, Auburn, CA 95603 (530) 889-7470/FAX (530) 889-7499

INITIAL STUDY

In accordance with the policies of the Placer County Board of Supervisors regarding implementation of the California Environmental Quality Act, this document constitutes the Initial Study on the proposed project. This Initial Study provides the basis for the determination whether the project may have a significant effect on the environment. If it is determined that the project may have a significant effect on the environment, an Environmental Impact Report will be prepared which focuses on the areas of concern identified by this Initial Study.

I. BACKGROUND

TITLE OF PROJECT:

Kings Beach Commercial Core Improvement Project

EIAQ #3739

II. EVALUATION OF ENVIRONMENTAL IMPACTS:

- A. A brief explanation is required for all answers except "No Impact" answers.
- B. "Less than Significant Impact" applies where the project's impacts are negligible and do not require any mitigation to reduce impacts.
- C. "Potentially Significant Unless Mitigation Incorporated" applies where the incorporation of mitigation measures has reduced an effect from "Potentially Significant Impact" to a "Less than Significant Impact." The County, as lead agency, must describe the mitigation measures, and briefly explain how they reduce the effect to a less-than-significant level (mitigation measures from Section IV, EARLIER ANALYSES, may be cross-referenced).
- D. "Potentially Significant Impact" is appropriate if there is substantial evidence that an effect is significant. If there are one or more "Potentially Significant Impact" entries when the determination is made, an EIR is required.
- E. All answers must take account of the entire action involved, including off-site as well as on-site, cumulative as well as project-level, indirect as well as direct, and construction as well as operational impacts [CEQA, Section 15063 (a) (1)].
- F. Earlier analyses may be used where, pursuant to the tiering, program EIR, or other CEQA process, an effect has been adequately analyzed in an earlier EIR or Negative Declaration [Section 15063(c)(3)(D)]. Earlier analyses are discussed in Section IV at the end of the checklist.
- G. References to information sources for potential impacts (e.g., general plans/community plans, zoning ordinances) should be incorporated into the checklist. Reference to a previously prepared or outside document should include a reference to the pages or chapters where the statement is substantiated. A source list should be attached, and other sources used, or individuals contacted, should be cited in the discussion.

Environmental Issues			Potentially	
(See attachments for information sources)		Less Than	Significant	
(200 4		Significant	Unless	Potentially
	No Impact	Impact	Mitigation	Significant
		ппрасі	Incorporated	Impact

1.	AND USE PLANNING. Would the proposal:			
æ	Conflict with general plan/community plan/specific plan designation(s) or zoning, or policies contained within such plans?			
ł	Conflict with applicable environmental plans or policies adopted by responsible agencies with jurisdiction over the project?	\boxtimes		
C	Be incompatible with existing land uses in the vicinity?		\boxtimes	
Ċ	Affect agricultural and timber resources or operations (e.g., impacts to soils or farmlands and timber harvest plans, or impacts from incompatible land uses)?	\boxtimes		
e	Disrupt or divide the physical arrangement of an established community (including a low-income or minority community)?			
f	Result in a substantial alteration of the present or planned land use of an area?		\boxtimes	

Planning Department

<u>Item 1a</u> - Although the project is intended to implement the goals of the Kings Beach Community Plan of 1996, some design elements may differ from those originally envisioned in that document which must be analyzed for potential impacts.

<u>Item 1c</u> - Some preliminary design concepts indicated a potential need for the demolition of some structures, and consequent displacement of uses, for some of the existing commercial developments in the study area. This component therefore has the potential to disrupt or divide the physical arrangement of the established community.

Item 1e and f - See above comments

Department of Public Works

<u>Item 1a</u> - Placer County and Tahoe Regional Planning Agency (TRPA) adopted the North Tahoe Community Plan (Community Plan) in 1996. That plan presents a vision intended to guide Kings Beach's community enhancement activities. Major components of the Community Plan are directed at the commercial core. These include reconstruction of SR28, providing improved pedestrian and bicyclist facilities, the installation of streetscape improvements, and the construction of water quality improvements.

The Community Plan includes a list of capital improvement projects intended to achieve identified Community Plan goals. Similarly, the Environmental Improvement Program (EIP) established by TRPA, lists projects considered necessary to achieve environmental goals in the Lake Tahoe Basin. Finally, expanding opportunities for pedestrian and bicycle travel is a key element in both regional and community transportation plans. By meeting the identified need for improved pedestrian and bicyclist mobility, the proposed project will implement (fully or partially) projects listed in the Community Plan, in the May 2001 EIP update, and it will help achieve transportation goals. By doing so, the project will contribute to the achievement of planning goals at the community and regional level.

Environmen (See attachm	ntal Issues nents for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact
implement (By meeting projects list quality, the year 2001 E	g the identified need for improved pedestrian and bicyclist access (fully or partially) projects listed in the Community Plan, and it was the identified need for aesthetic improvements, the proposed ted in the Community Plan and the EIP. By satisfactorily meets proposed project will implement (fully or partially) several project proposed project will implement (fully or partially) several project.	ill help achi project wi ing the iden ects listed in	eve regions Il impleme ntified need n the Comr	al transporta ent (fully or d for improv nunity Plan	tion goals. partially) ving water and in the
project alter states that to may not be	matives may necessitate the need to amend the Community Plan. raffic levels of service will remain at a certain level. Under some met.	As it current project alto	ntly stands, ernatives, l	The Commi	unity Plan ice criteria
	measures, including amendments to the Community Plan, may be a vice that may occur under some project alternatives. No other mea			potential en	ange m
2. PO	PULATION AND HOUSING. Would the proposal:				
a.	Cumulatively exceed official regional or local population projections?	\boxtimes			
b.	Induce substantial growth in an area either directly or indirectly (e.g., through projects in an undeveloped area or extension of major infrastructure)?	$\boxtimes_{\underline{I}}$			
c.	Displace existing housing, especially affordable housing?				
3 GE	OLOGIC PROBLEMS. Would the proposal result in or expose p	people to po	tential imp	acts involvir	ıg:
a.	Unstable earth conditions or changes in geologic substructures?	\boxtimes			
b.	Significant disruptions, displacements, compaction or overcrowding of the soil?	\boxtimes			
c.	Substantial change in topography or ground surface relief features?				
d.	The destruction, covering or modification of any unique geologic or physical features?	\boxtimes			
e.	Any significant increase in wind or water erosion of soils, either on or off the site?	\boxtimes			
f.	Changes in deposition or erosion or changes in siltation which may modify the channel of a river, stream, or lake?	\boxtimes			

Exposure of people or property to geologic and

 \boxtimes

Environmental Issues			Potentially	
(See attachments for information sources)		Less Than	Significant Unless	Potentially
	No Impact	Significant	Mitigation	Significant
		Impact	Incorporated	Impact

geomorphological (i.e. avalanches) hazards such as earthquakes, landslides, mudslides, ground failure, or similar hazards?

Department of Public Works

Item 3c - Examination of the Soil Survey of the Tahoe Basin, California and Nevada (SCS 1974) indicates that the soils represented in the project area are not inherently unstable. The potential for unstable soil conditions is remote. The majority of the project area will require only slight modification of surfaces for roadway and parking lot construction. However, there is the potential for larger changes to topography within drainage basin areas. Mitigation measures are described below to reduce potential impacts. No unique geologic or physical features are present within the project area. No impacts to these types of features will occur as a result of the project. The proposed project will not result in a significant increase of erosion on or off site. The proposed project does not contain components that will result in changes in depositional or erosional processes within and in the vicinity of the project area. Finally, the proposed project will not expose people or property to geologic hazards such as earthquakes, landslides, mudslides, ground failure, or similar hazards.

Mitigation measures, such as modifications in design and the addition of landscaping to drainage basins, will reduce impacts to topography or ground surface relief to a less than significant level. No other mitigation measures are anticipated.

4. W	ATER: Would the proposal result in:				
a.	Changes in absorption rates, drainage patterns, or the rate and amount of surface runoff?	`			
b.	Exposure of people or property to water related hazards such as flooding?		\boxtimes		
c.	Discharge into surface waters or other alterations of surface water quality (e.g., temperature, dissolved oxygen, or turbidity)?		\boxtimes		
d.	Changes in the amount of surface water in any water body?		\boxtimes		
e.	Changes in currents, or the course of direction of water movements?		\boxtimes		
f.	Change in the quantity of groundwater, either through direct additions of withdrawals, or through interception of an aquifer by cuts or excavations, or through substantial loss of groundwater recharge capability?				
g.	Altered direction or rate of flow of groundwater?		\boxtimes		
h.	Impacts to groundwater quality?				\boxtimes
i.	Substantial reduction in the amount of groundwater otherwise available for public water supplies?	\boxtimes			
j.	Impacts to the watershed of important surface water resources,			\boxtimes	

ĺ	Environmental Issues			Potentially	
	(See attachments for information sources)		Less Than	Significant	
1			Significant	Unless	Potentially
		No Impact	<u> </u>	Mitigation	Significant
			Impact	Incorporated	Impact

including but not limited to, Lake Tahoe, Folsom Lake, Hell Hole Reservoir, Rock Creek Reservoir, Sugar Pine Reservoir, French Meadows Reservoir, Combie Lake, and Rollins Lake?

Department of Public Works

Elements of the proposed project will lead to a change in absorption rates, drainage patterns, and surface runoff. Analyses that are currently being conducted will show if these changes lead to potentially significant impacts and if mitigation measures are necessary. Runoff from proposed impervious surfaces including roadways, parking lots, and sidewalks, will be collected and directed toward storm water treatment facilities. These facilities will be designed to remove heavy sand particles and grease/oil. Discharge from these facilities will be dissipated through areas that provide infiltration and evaporation. Combined, these features will be designed to provide storage for storm events that will be sufficient to detain the 20-year, 1-hour storm. The components within the proposed project will be designed to accommodate 100-year storm events. Therefore, the proposed project will not expose people or property to water related hazards beyond what is currently present. By filtering sand and grease/oil from impermeable surfaces, the proposed project should improve water quality by reducing sediment and nutrient transport. Analyses are being conducted to determine the extent to which the collection, conveyance, and treatment of urban storm water runoff will affect the amount of surface water in nearby water bodies. In addition, in the process collecting and conveying runoff, the project may have the potential to alter existing urban drainage patterns. The extent to which these urban drainage patterns will be altered is yet to be determined. It is unlikely that there will be a significant impact to the amount of surface water or the direction of water movement as a result of the proposed project. The storm water treatment facilities could result in a minor addition to ground water but it is not expected to greatly affect the quantity of ground water in the area. Other on-site development will not result in the change in quantity of the groundwater nor will it affect recharge rates. It is also unlikely that the project will result in the alteration of the direction or rate of flow of ground waters. The treatment of storm water runoff will reduce the potential discharge of contaminents to surface and groundwaters, especially when compared with the current site conditions. As a result, the proposed project may provide a net improvement to ground water quality. However, because the proposed project involves the infiltration of surface runoff, analyses may show that these efforts produce an impact to groundwater quality. Therefore, mitigation may be required. Construction of the proposed project does not include a domestic water system nor will there be a need for groundwater withdrawal. The only use of water associated with the proposed project is the irrigation of landscaping during the growing season. Water used for irrigation of landscaping will be provided by the North Tahoe Public Utility District. As previously stated, the project has the potential to alter urban drainage patterns that flow to Lake Tahoe. Although the proposed storm water treatment facilities are likely to have an overall beneficial effect on this watershed, analyses may show an impact that requires mitigation.

Mitigation measures will be incorporated if analyses show that the proposed project will lead to significant changes in absorption rates, drainage patterns, or surface runoff. Other measures will be implemented to avoid impacts to groundwater quality and the Lake Tahoe watershed, should analyses determine this is necessary. No further mitigation measures are anticipated.

5. AD	R QUALITY. Would the proposal:			
a.	Violate any air quality standard or contribute to an existing or projected air quality violation?			
b.	Expose sensitive receptors to pollutants?		\boxtimes	
c.	Have the potential to increase localized carbon monoxide levels at nearby intersections in exceedance of adopted standards?			

Environme (See attache	ntal Issues nents for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact		
d.	Create objectionable odors?		\boxtimes				
Air Polluti	on Control District						
	t is located in the Lake Tahoe Air Basin in Placer County. Air Qual onstruction emissions and dust.	ity concerr	ns includes	exhaust fron	n		
6. TR	ANSPORTATION/CIRCULATION Would the proposal result	in;					
a.	Increased vehicle trips or traffic congestion?			\boxtimes			
ъ.	Hazards to safety from design features (e.g., sharp curves or dangerous intersections) or incompatible uses (e.g., farm equipment)?						
c.	Inadequate emergency access or access to nearby uses?						
d.	Insufficient parking capacity on-site or off-site?			\boxtimes			
e.	Hazards or barriers for pedestrians or bicyclists?		\boxtimes				
f.	Conflicts with adopted policies supporting alternative transportation (e.g., bus turnouts, bicycle racks)?	\boxtimes					
g.	Rail, waterborne, or air traffic impacts?	\boxtimes					
Departmen	t of Public Works						
The proposed project will not increase the capacity of the roadway. A level of use consisted with past and existing patterns is expected. As a result, the proposed project will not cause an increase in vehicle trips. However, depending on the selection of certain project alternatives, an increase in congestion may occur that may require mitigation. All project features will be designed to current standards and will not represent a hazard to safety. If the proposed project, through selection of certain alternatives, leads to an increase in traffic congestion, there is the potential for inadequate emergency access that may require mitigation. The proposed project will remove a portion of the existing parking in the Kings Beach Commercial Core area. The reduction in parking will be mitigated by the creation of new parking spaces within the project area. No net loss of parking will occur as a result of the proposed project. However, certain business may end up with a reduced number of parking spaces. This may represent an impact to that individual business. A major component of the proposed project includes providing facilities for pedestrians and bicyclists within the project area. Therefore, the project does not represent a hazard or barrier nor will it conflict with these transportation uses. The proposed project is not located near an airport or railroad. It will have no impacts to these modes of transportations. Mitigation for the possible increase in traffic congestion under certain project alternatives will be defined after completion							
of traffic and be identified Commercial	alyses. To facilitate access for emergency uses, alternative routes the Any parking removed to incorporate project components will be Core Improvement Project area. This will occur as close to individual No other mitigation measures are anticipated.	nat avoid porestored wi	otentially c ithin the Ki	ongested are ngs Beach	as will		

	ental Issues ments for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact
7.	BIOLOGICAL RESOURCES. Would the proposal result in im	pacts to:			
a.	Endangered, threatened or rare species or their habitats (including, but no limited to plants, fish, insects, animals, and birds)?				
b.	Locally occurring natural communities (e.g., oak woodlands, mixed conifer, annual grasslands, etc.)?	\boxtimes			
c.	 Significant ecological resources including: Wetland areas including vernal pools; Stream environment zones; Critical deer winter ranges (winter and summer), migratory routes and fawning habitat; Large areas of non-fragmented natural habitat, including but not limited to Blue Oak Woodlands, Valley Foothill Riparian, vernal pool habitat; Identifiable wildlife movement zones, including but not limited to, non-fragmented stream environment zones, avian and mammalian routes, and known concentration areas of waterfowl within the Pacific Flyway; 				
8. EI	6) Important spawning areas for anadromous fish?		e Seria digentale and series		
a.	NERGY AND MINERAL RESOURCES. Would the proposal: Conflict with adopted energy conservation plans?	\boxtimes			
Ъ.	Use non-renewable resources in a wasteful and inefficient manner?	\boxtimes			
c.	Result in the loss of availability of a known mineral resource that would be of future value to the region and state residents?			. 🗆	
9, H	AZARDS. Would the proposal involve:				
a.	A risk of accidental explosion or release of hazardous substances (including, but not limited to, oil, pesticides, chemicals, or radiation)?				\boxtimes
b.	Possible interference with an emergency response plan or emergency evacuation plan?				
c.	The creation of any health hazard or potential health hazard?	\boxtimes			
d.	Exposure of people to existing sources of potential health hazards?				

Environme	ntal Issues ments for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact			
e.	Increased fire hazard in areas with flammable brush, grass, or trees?	\boxtimes						
Environm	ental Health			·				
	contamination may be encountered that has migrated into the right and storage tanks operations. This should be addressed in the EIR.	of-way fr	om current	t or historica	1			
10. NO	DISE. Would the proposal result in:							
a.	Increases in existing noise levels?							
b.	Exposure of people to noise levels in excess of County standards?							
Environm	ental Health							
Construction addressed in	on activities have the potential to increase the ambient noise levels in the EIR.	n the projec	et vicinity.	This should	be			
A	BLIC SERVICES. Would the proposal have an effect upon; or revices, in any of the following areas:	sult in need	for new o	r altered gov	ernment			
a.	Fire Protection?	\boxtimes						
b.	Sheriff Protection?	\boxtimes						
c.	Schools?	\boxtimes						
d.	Maintenance of public facilities, including roads?			\boxtimes				
e.	Other governmental services?	\boxtimes						
Departme	nt of Public Works							
Neither the type nor level of use within the project area will change as a result of the proposed action. Therefore, the need for most public services is not expected to change when compared with the existing condition. However, the proposed project will include the installation of storm water drainage facilities and other components that require maintenance. Impacts may result that requires mitigation if these components are not properly maintained.								
	To reduce potential impacts from installation of new components within the project area, regularly scheduled maintenance will occur to ensure proper functioning condition of these components. No other mitigation measures are anticipated.							
12. UT	ILITIES AND SERVICE SYSTEMS. Would the proposal result stantial alterations to the following utilities:	in a need f	or new sys	tems or supp	lies, or			
a.	Power or natural gas?	\boxtimes						

Environme (See attach	ntal Issues ments for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact
b.	Communication systems?	\boxtimes			
c.	Local or regional water treatment or distribution facilities?				\boxtimes
d.	Sewer, septic systems, or wastewater treatment and disposal facilities?				
e.	Storm water drainage?		\boxtimes		
f.	f. Solid waste materials recovery or disposal?				
g.	g. Local or regional water supplies?				
Departme	nt of Public Works				
result in the generation of solid waste from excavated soils and standard construction debris. Placer County, the project proponent, will be responsible for contracting the collection and removal of solid waste. The licensed contractor is required to comply with all applicable regulations. In accordance with Section 64.5c of the Code, any solid waste will be collected and transported to a TRPA approved landfill located outside of the Tahoe Basin. Water will be used to support proposed landscaping, however, this use of additional water will not exceed the maximum permitted capacity of the service provider (North Tahoe Public Utility District).					is e will be support
13. AE	Affect a scenic vista or scenic highway?		\boxtimes		
b.	Have a demonstrable negative aesthetic effect?	\boxtimes			
c.	Create adverse light or glare effects?				
Planning I	<u>Department</u>				
The project	t will have an effect on State Route 28, a designated scenic corridor rovements.	r, but all of	the changes	s are anticipa	ated to be
14. CU	LTURAL RESOURCES. Would the proposal:				
a.	Disturb paleontological resources?	\boxtimes			
b.	Disturb archaeological resources?	\boxtimes			
c.	Affect historical resources?				

Environmental Issues (See attachments for information sources)	No Impact	Less Than Significant Impact	Potentially Significant Unless Mitigation Incorporated	Potentially Significant Impact
d. Have the potential to cause a physical change, which would affect unique ethnic cultural values?				
e. Restrict existing religious or sacred uses within the potential impact area?	\boxtimes			
Planning Department				
The environmental document should examine and disclose any potential impastructures that could potentially be removed in connection to some f the suggestion.	cts to historested alterna	ic resource tives may l	es. Some of the	ne al value.
15. RECREATION. Would the proposal:			The state of the	
a. Increase the demand for neighborhood or regional parks or other recreational facilities?	\boxtimes			
b. Affect existing recreational opportunities?				
III. MANDATORY FINDINGS OF SIGNIFICANCE				
A. Does the project have the potential to degrade the quality of the environment, substantially reduce the habitat of a fish or wildlife species, cause a fish or wildlife population to drop below self-sustaining levels, threaten to eliminate a plant or animal community, reduce the number or restrict the range of rare or endangered plants or animals, or eliminate important examples of the major periods of California history or prehistory?				
B. Does the project have impacts that are individually limited, but cumulatively considerable? ("Cumulatively considerable" means that the incremental effects of a project are considerable when viewed in connection with the effects of past projects, the effects of other current projects, and the effects of probable future projects.)	. 🗆			
C. Does the project have environmental effects, which will cause substantial adverse effects on human beings, either directly or indirectly?				
Planning Department				
The analysis of the project must take into consideration all other activities in the area, proposed or which could be reasonably foreseen, that could have cumulative impacts.				

IV. EARLIER ANALYSIS

Earlier analyses may be used where, pursuant to the tiering, program EIR, or other CEQA process, one or more effect has been adequately analyzed in an earlier EIR or Negative Declaration [State CEQA guidelines Section 15063(c)(3)(D)]. In this

case a dis	scussion should identify the following on attached shee	ts.			
A. E	Carlier analyses used. Identify earlier analyses and sta	te where they are available for review.			
a	B. Impacts adequately addressed. Identify which effects from the above checklist were within the scope of, and adequately analyzed in, an earlier document pursuant to applicable legal standards. Also, state whether such effects were addressed by mitigation measures based on the earlier analysis.				
d		Potentially Significant Unless Mitigation Incorporated," ted or refined from the earlier document and the extent to ect.			
Authority	: Public Resources Code Sections 21083 and 21087.				
	e: Public Resources Code Sections 21080(c), 21080.1, 21080 Mendocino, 202 Cal. App. 3d 296 (1988); Leonoff v. Monter	0.3, 21082.1, 21083, 31083.3, 21093, 21094, 21151; Sundstrom v. rey Board of Supervisors, 222 Cal. App. 3d 1337 (1990).			
v. ot	HER RESPONSIBLE AND TRUSTEE AGENCIE	S WHOSE APPROVAL IS REQUIRED			
⊠ Cali	ifornia Department of Fish and Game	☐ Local Agency Formation Commission (LAFCo)			
⊠ Cali	fornia Department of Transportation (e.g. Caltrans)	California Department of Health Services			
⊠ Cali	ifornia Regional Water Quality Control Board	California Integrated Waste Management Board			
☐ Cali	ifornia Department of Forestry	☐ Tahoe Regional Planning Agency			
⊠ U.S	. Army Corp of Engineers	California Department of Toxic Substances			
⊠ U.S	. Fish and Wildlife Service				
☐ Nati	ional Marine Fisheries Service				
VI. DE	TERMINATION (to be completed by the Lead Ag	ency)			
A.	I find that the proposed project is categorically exemp	ot (Class) from the provisions of CEQA.			
В.	I find that the proposed project COULD NOT have a significant effect on the environment, and a NEGATIVE DECLARATION will be prepared.				
C.	I find that although the proposed project COULD have WILL NOT be a significant effect in this case because have been added to the project. A MITIGATED NE	se the mitigation measures described herein			
D.	I find that the proposed project is within the scope of impacts addressed in an previously adopted Negative Declaration, and that only minor technical changes and/or additions are necessary to ensure its adequacy for the project. An ADDENDUM TO THE PREVIOUSLY-ADOPTED NEGATIVE DECLARATION will be prepared.				
E.	I find that the proposed project MAY have a significa ENVIRONMENTAL IMPACT REPORT is requir	•			
F	I find that the proposed project MAV have a significa	int effect(s) on the environment, and at least one			

	effect has not been adequately analyzed in an earlier document pursuant to applicable legal standards. Potentially significant impacts and mitigation measures that have been adequately addressed in an earlier document are described on attached sheets (see Section IV above). An ENVIRONMENTAL IMPACT REPORT will be prepared to address those effect(s) that remain outstanding (i.e. focused, subsequent, or supplemental EIR).	
G.	I find that the proposed project is within the scope of impacts addressed in a previously certified EIR, and that some changes and/or additions are necessary, but none of the conditions requiring a Subsequent or Supplemental EIR exist. An ADDENDUM TO THE PREVIOUSLY-CERTIFIED EIR will be prepared.	
H.	I find that the proposed project is within the scope of impacts addressed in a previously-certified Program EIR, and that no new effects will occur nor new mitigation measures are required. Potentially significant impacts and mitigation measures that have been adequately addressed in an earlier document are described on attached sheets, including applicable mitigation measures that are imposed upon the proposed project (see Section IV above). NO FURTHER ENVIRONMENTAL DOCUMENT will be prepared [see CEQA Guidelines, Section 15168(c)(2)], 15180, 15181, 15182, 15183.	
VII. EN	IVIRONMENTAL REVIEW COMMITTEE (Persons/Departments Consulted):	
Bill Com	nbs, Planning Department	
Rebecca	Bond, Department of Public Works	
Roger Da	avies, Environmental Health Services	
Ann Hob	obs, Air Pollution Control District	
Signature	e: Nu faurence for BILL COMBS 11/15/62 ENVIRONMENTAL REVIEW COMMITTEE CHAIRPERSON Date	

T:\CMD\CMDP\LORI\EIAQ\3739



PLACER COUNTY PLANNING DEPARTMENT

11414 B Avenue/Auburn, California 95603/Telephone (530) 889-7470/FAX (530) 889-7499 Web Page: http://www.placer.ca.gov/planning E-Mail: ljlawren@placer.ca.gov

January 6, 2003

Charles Zeier Harding ESE, Inc. 1572 E. College Parkway, Suite 162 Carson City, NV 89706

Subject:

Kings Beach Commercial Core Improvement Project

Dear Mr. Zeier:

The Notice of Preparation (NOP) review period for the subject proposal ended **December 23**, **2002**. Comments regarding the NOP are attached for your review and response in the Environmental Impact Report (EIR). Any additional comments that may be received will be forwarded to you by fax.

Sincerely,

LORI LAWRENCE

Planning Technician/Environmental Coordinator

Attached comments:

Robert Erlich, California Regional Water Quality Control Board-Lahontan

Virginia Esperanza, California Tahoe Conservancy

Daniel Sussman, League to Save Lake Tahoe

Comments recorded at 12/5/02 Scoping Meeting

Kerry Wicker, California Department of Fish & Game

Rick Marshall

Tom Burt

Keith Vogt

Kenneth Arnett

Candy Dowdle

Larry Dowdle

Wyatt Ogilvy

Theresa May Duggan

Dave Owen

Kathryn Kelly
Anthony Graeber
Tom & Priscilla Mills
Scott Shane
Jill Sarick
Randall Osterhuber
William Johnson
Judy Layton
Mary Ann Burt
Mike Thomas

cc:

Dan LaPlante

Bob Costa

Ken Grehm

Jennifer Merchant

Daniel Sussman

Amy Linnerooth

ERC members



California Regional Water Quality Control Board

Lahontan Region

HECEIVED

Gray Davis

Internet Address: http://www.swrcb.ca.gov/rwqcb6 2501 Lake Tahoe Boulevard, South Lake Tahoe, California 96150 Phone (530) 542-5400 • FAX (530) 544-2271

DEC 2 5 2007

DEC 2 3 2002

PLANNING DEPARTMENT

Lori Lawrence, Environmental Review Clerk (sent via facsimile 12-23-2002) Placer County Planning Department 11414 B Avenue Auburn, CA 95603

STAFF COMMENTS ON THE NOTICE OF PREPARATION OF A DRAFT ENVIRONMENTAL IMPACT REPORT/ENVIRONMENTAL IMPACT STATEMENT FOR THE KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT (SCH# 2002112087)

The staff of the California Regional Water Quality Control Board, Lahontan Region (Regional Board) has received the Notice of Preparation of a Draft Environmental Impact Report/ Environmental Impact Statement for the Kings Beach Commercial Core Improvement Project (KBCCIP). Thank you for the opportunity to participate early in the planning process for the projects in the Kings Beach community and to provide comments on the environmental process. As requested by your agency, this letter provides Regional Board staff (staff) views on issues, potential alternatives, and assumptions which we believe should be used as part of the environmental review process for the KBCCIP.

Proposed Project and Overall Issues

The project description states that the proposed project involves reconstruction of portions of State Route 28 (SR 28) and other improvements within the Community Plan boundaries of Kings Beach. The project involves roadway improvements, pedestrian and bicycle access improvements, replacement parking, upgrades to drainage system capacity, and water quality improvements.

Placer County has been studying the entire Kings Beach watershed to assess the role of the KBCCIP in meeting water quality objectives and to plan for water quality improvement projects further upstream from the KBCCIP General Study Area. The KBCCIP project is at the bottom of the watersheds in Kings Beach. If the preferred water quality improvements proposed for the KBCCIP will not result in storm water ruonff which meets water quality objectives at the points of discharge to Lake Tahoe, additional water quality improvement projects will be required by 2008 within or above the KBCCIP project area. Please explain how the environmental documents can address the potential need for additional projects in assessing the impacts of the water quality alternatives being considered.

Increasing the conveyance system capacity could have negative impacts on water quality by more easily conveying nutrients, fine sediment and other pollutants in storm water directly to Lake Tahoe. Improvements to storm water collection facilities will improve the quality storm water delivered to Lake Tahoe only if treatment BMPs will be effective in removing pollutants

from conveyed runoff. While source control by stabilization or protection of unpaved surfaces is very important, treatment is required for storm water runoff from paved areas which contain pollutants originating from atmospheric deposition, snow removal and de-icing practices, road wear, and other processes.

Much of the privately-owned land adjacent to SR 28 in the Commercial Core is already paved, and runoff from these lands will reach the County's conveyance system. The need statement acknowledges that limited space is available within the project area to accommodate large treatment facilities for area-wide storm water flows, and states that treatment will be required for collected and conveyed storm water. If these space limitations are severe, alternatives which consider treatment facilities which could be located outside of the KBCCIP study area should be explored. Active treatment systems to remove pollutants from conveyed storm water should be one of the water quality alternatives analyzed in the environmental documents.

It is not clear how the project will, on its own, or in conjunction with future projects within the KBCCIP project area or within other parts of the developed watershed, meet water quality requirements. Three previous letters which also address these issues are enclosed. These letters provide additional information on water quality issues that have been discussed during project planning in 2001 and 2002. Sections that concern the environmental process are highlighted by arrows.

Notice of Preparation Information Package

<u>Page 5. Need Four – Improve Water Quality.</u>

The correct name for the document referred to as the Basin Plan is the Water Quality Control Plan for the Lahontan Region. Chapter 5 of the Basin Plan is the Water Quality Standards and Control Measures for the Lake Tahoe Basin. The Basin Plan contains numerical storm water effluent limitations for both surface discharges and runoff discharged to infiltration systems. Chapter 4 of the Basin Plan discusses the implementation program and time schedules required to protect beneficial uses and to achieve water quality objectives. In the Lake Tahoe Basin, governmental agencies assigned to maintain roads are required to retrofit existing roads to handle storm water runoff from the 20-year, 1-hour storm, and to restabilize all eroding slopes by 2008.

In addition to the requirements in the Basin Plan, Board Order No. 6-00-82 contains the Regional Board's Waste Discharge Requirements for Placer County for Storm Water/Urban Runoff Discharge. With few exceptions (storm water discharge from federal, state, or regional entities), Placer County is responsible for all storm water/urban runoff within its boundaries. Placer County is participating in an implementation program which has a goal of completing storm water/erosion control projects to achieve compliance with permit requirements (including the numerical storm water effluent limitations) by 2008. Requirements for Caltrans Storm Water Discharges are written into another NPDES permit (Order NO. 99-06 – DWQ). Caltrans is responsible for meeting numerical effluent limitations for storm water generated within their facilities and for completing retrofit projects by 2008.

Page 7-10 Lists of Alternatives.

While addressing the separate elements of the project, i.e., roadway, water quality, pedestrian access, parking, the environmental analysis should consider how the alternatives for each element affect meeting the needs identified for the other elements. In addressing needs to improve pedestrian and bicycle access along and across SR 28 and to improve aesthetic character of the Commercial Core, alternatives that decrease the amount of impermeable cover would make it easier to achieve water quality objectives by reducing the amount of storm water runoff generated which requires treatment within the project area.

Page 8 Storm Water Treatment Design Options.

To help determine how water quality improvements for the KBCCIP project area will help Placer County meet the 2008 retrofit requirements, Placer County has studied the entire watershed draining to the KBBCIP project area. If treatment facilities for the KBCCIP project are designed to be sufficient to accommodate only storm water collected from Caltrans and Placer County rights-of-way within the project area, it is not clear how Placer County can provide treatment for all storm water originating within the project area. A discussion of additional improvements required to treat runoff originating above the KBCCIP is also required in analyzing the water quality benefits of storm water treatment alternatives.

Page 10 Environmental Components - Water Quality

If the preferred alternative does not include adequate treatment BMPs to meet water quality requirements, the County should consider future environmental impacts from additional required water quality retrofit projects within the Commercial Core area and nearby developed portions of the Kings Beach watersheds.

Page 14 Project Time Schedule

While estimating that the environmental document will require 24 to 36 months, the project time schedule identifies no milestones between 09/2001 and 4/2004. Additional milestones should be identified in the project alternatives selection, project design, funding, and environmental review processes.

Initial Project Application

Geology and Soils

- 9. Deep excavations may also be required for installation of water quality treatment facilities.
- 13. Sediment could be discharged into lakes or streams during construction if appropriate construction site BMPs are not installed and maintained. Additional sediment could be discharged to Lake Tahoe if conveyance system capacities are increased, and if treatment BMPs are not able to remove conveyed sediment.

Drainage and Hydrology

18. Any increase in coverage which increases storm water runoff should be mitigated. Opportunities to increase infiltration with permeable pavement or permeable snow storage areas

should be analyzed. Where allowed by site conditions, on-site infiltration should be used to reduce storm water runoff which would otherwise reach the regional conveyance systems and require treatment.

- 20. Irrigation return flows and construction wash water could be discharged to surface waters. Nutrients and fine sediment which affect lake clarity should be mentioned as contaminants in storm water runoff.
- 21. The project may involve physical alteration of the in-channel pond constructed in Griff Creek north of SR 28.

Vegetation and Wildlife

31. Changes to riparian habitat along Griff Creek could result from increasing the capacity of culverts under SR 28.

Hazardous Materials

66-68. Project construction may involve handling, storage and transportation of hazardous materials such as oils, lubricants, and fuels.

Initial Study

Land Use Planning

1.b. If the preferred alternative does not produce storm water discharge which meets effluent limitations and other water quality requirements, additional projects will be required by 2008 within or adjacent to the project area. Construction of these projects may result in additional costs and environmental impacts.

Geological Problems

3.e-f. Increasing the capacity of culverts could result in additional erosion of soils or changes in deposition or siltation along streams.

Water

The explanation provided by the Department of Public Works suggests that the project will be designed to provide storage sufficient to detain the 20-year, 1-hour storm. Regional Board staff has repeatedly expressed concerns that it has not yet been demonstrated that designs which have a storage capacity to detain the 20-year, 1-hour storm (particularly if runoff is calculated only for public rights-of-way) will be adequate to meet water quality objectives and numerical effluent limitations. Until water quality objectives are better defined, and there is an understanding how water quality alternatives will be analyzed to determine whether they meet water quality objectives, it will be difficult to reach agreement on the preferred water quality alternative. Analysis of impacts will be difficult without additional information on the type, location, and size of storm water treatment BMPs.

4.c-g. Some of the BMPs considered may have potential significant impacts. Additional information on these BMPs should be provided before determining that these impacts are less

than significant. Impacts from construction should be analyzed and avoidance or mitigation measures should be used.

Biological Resources

7.c Impacts to wetlands or stream environmental zones should be analyzed and mitigation measures should be described.

Hazards

9. c-d. Vector control issues should be considered in selecting storm water conveyance and treatment BMPs.

The Regional Board looks forward to working with you to develop an effective and acceptable environmental document that will ensure the protection of Lake Tahoe. Should you have any questions concerning these comments, please Doug Smith, Acting Chief, Lake Tahoe Watershed Unit at (530) 542-5453 or me at (530) 542-5433.

Sincerely,

Robert Erlich

Environmental Scientist

west Erlich

Enclosures: Regional Board staff letter to Rebecca Bond dated November 8, 2002

Regional Board staff letter to Leslie Burnside dated August 23, 2002 Regional Board staff letter to Dave Zander dated November 27, 2001

Bill Coombs/ Placer County Planning Department Larry Benoit and Charles Emmett/ Tahoe Regional Planning Agency John Holder and Mike Forga/ Caltrans District 3 Dave Zander/ California Tahoe Conservancy State Clearinghouse

RE- T:KBCCIP-NOP Comments



California Regional Water Quality Control Board

Lahontan Region

Gray Davis
Governor

Winston H. Hickox
Secretary for
Environmental
Protection

Internet Address: http://www.swrcb.ca.gov/rwqcb6 2501 Lake Tahoe Boulevard, South Lake Tahoe, California 96150 Phone (530) 542-5400 • FAX (530) 544-2271

November 8, 2002

Rebecca Bond Associate Civil Engineer Placer County Department of Public Works 11444 B Avenue DeWitt Center Auburn, California 95603

DRAFT COMMENTS ON KINGS BEACH WATER QUALITY PLANNING GRANT TASKS 3-5

Using a planning grant from the California Tahoe Conservancy, Placer County Department of Public Works (County) is completing planning activities to identify a preferred design alternative for the entire Kings Beach watershed area. The County is evaluating total runoff flows, pollutant loadings, and potential treatment locations and strategies for the entire watershed. This information will be used to design water quality improvements for the multi-agency Kings Beach Commercial Core Improvement Project and for future County projects within developed areas in Kings Beach.

The County submitted draft reports for agency review on Task 3 (Studies of Existing Conditions to Meet Regulatory and Funding Agency Needs) and Task 4 (Selection of Overall-Project Water Quality Improvements to be Studied) in mid-October 2002, and requested agency input on the selection of four alternatives for further study. The County's schedule calls for the consultant to evaluate the alternatives and present a draft report with a preferred alternative (Task 5) by November 20, 2002.

The consultant gave us two additional draft reports on the hydrologic design and pollutant load estimation approach at our October 30, 2002 meeting. We are concerned that those two reports contain information needed for our review of Tasks 3 and 4 as well as the Task 5, and that County's completion schedule does not allow adequate time for us to review these important planning grant products. The information on hydrologic design and the pollutant load estimation approach does not enable us to adequately assess whether proposed alternatives will meet water quality objectives. It is important to the Regional Board that Placer County consider alternatives that are designed to be effective in removing nutrients and fine particulate loads under realistic site conditions.

Comments on Task 3 draft report

I have previously expressed my concerns that the Task 3 focus on 20-year 1-hour treatment design volume should not imply that facilities sized to contain 1-inch of runoff would meet the Regional Board's effluent limits or even maximize the cost-benefit ratio of efforts to reduce nutrient and fine sediment loads. To better assess proposed treatment methods, I suggested that designs consider the flows and loads the facilities would actually receive. Task 3 specifically

called for the calculation for total runoff to include volumes for all impervious surfaces within the watershed, so I believe the report is deficient in neglecting runoff from impervious surfaces outside of the right-of-way. Ignoring the impervious surfaces on developed parcels within Kings Beach results in underestimating the flows reaching the existing or proposed infiltration/detention facilities, and overestimating the size of the design storm that could actually be infiltrated or treated in these facilities. Therefore, the estimate that an additional 5.41 acre-feet of infiltration capacity would be adequate to meet treatment requirements may be too low. Please add columns to Tables 2.0 and 3.0 showing required treatment capacity based on volumes from all impervious surfaces within the watershed. It would also be prudent to add additional columns which include expected runoff from permeable surfaces both on rights-of-way and on other parcels at least throughout the developed portion of the watershed.

The estimation of runoff curve numbers and directly connected impervious cover for the developed watershed already appears in the Hydrologic Approach report and could be used in estimating total runoff from all impervious areas and total expected runoff from the developed watersheds under existing and fully-BMPed private parcel conditions. If you provide new estimates of existing and required treatment capacities which include additional contributing areas, please specify which Antecedent Moisture Condition class and hydrologic soil groups you are using in estimating runoff curve numbers. Based on soil mapping, it appears that approximately 85% of the developed portion of Kings Beach is in Hydrologic Soil Group C.

The explanation that contributions from private properties were not calculated because the purpose of Task 3 is to determine the portion of treatment capacity the public entities were responsible for and that "TRPA addresses infiltration of runoff on private properties by requiring the installation of BMPs on private property" is inaccurate. The municipal NPDES storm water permit (Board Order No. 6-00-82) states that Placer County is responsible for storm water/urban runoff within the legal boundaries of Placer County, excluding runoff from Caltrans and other federal, state and regional entities. Along with TRPA and the Regional Board, the County has an interest in and incentive for promoting installation of BMPs on private property. If effective BMPs are not installed on private property, Placer County will need to provide substantial additional treatment beyond designing primarily for flows and loads generated only from the rights-of-way.

The planning for projects within the Kings Beach watershed should account for the current level of BMP installation and effectiveness on private properties and consider how much additional treatment and flow reduction for runoff from private parcels can be realistically expected. For example, some commercial properties may be 90% impervious cover and located in areas with relatively high seasonal water tables. While it may be possible for the property owner to install BMPs to remove pollutants from storm runoff, infiltration or detention is not feasible. Little reduction in flow would be expected, and it may not be practical to exclude this runoff from the runoff generated from public rights-of-way by creating a separate conveyance for "treated" private runoff. Some runoff from private parcels would be expected even if BMPs are installed

on all private parcels, and limiting estimation of treatment design volume needs to impermeable rights-of way will interfere with your ability to realistically evaluate load reduction from design alternatives.

Comments on Task 4 draft report

- 2.1 Scoping of the Problem. While the concept of a linear relationship between load reduction and capital costs seems reasonable, the information provided on design volumes or flows, load estimation and load reduction estimation, and project costs is not adequate to determine that there is a linear relationship between load reduction and capital costs. The high estimated costs of Alternatives 11-13 each includes \$16 million of mandatory BMP compliance costs, while the other alternatives do not show any costs for additional capital improvements or maintenance which would be needed in the absence of mandatory BMP compliance. An additional \$20-30 million of capital and maintenance costs were added for chemical treatment plant(s) for Alternatives 12 and 13, even though "chemical" treatment could be as simple as a sack of flocculant in vaults designed to handle overflows from sedimentation/infiltration basins.
- 2.1.2 Sources of sediment and other pollutants does not list abrasives and deicers or road wear products.
- 2.3 Identification of Tools. This section rates lists of source control and treatment type BMPs by estimated load reduction classes. Sidewalk installation and pavement rehabilitation are given high ratings for estimated load reduction, while load reduction is rated as "none" for parking barriers and "low-moderate" for sediment basins. While this rating system addresses relative load reduction for individual BMPs, we recommend you look at a series of BMPs in the context of how they would be designed and used as part of a treatment train. For example, infiltration galleries or basins might only have moderate-high load reduction if they are sized to not bypass flows frequently during the wet season, or if there are other BMPs such as vaults with flow-dependent filtration/adsorption systems to handle much of the discharge from longer duration runoff events that would overflow the basins without generating high discharge rates.
- <u>2.4 Strategic Emphases</u>. I am having difficulty understanding the use of the Table 1 which generally repeats the same lists of constraints for each strategy in the developed watershed. The Active Strategy only identifies total conveyance to a treatment plant. Alternatives 12 and 13 emphasize the active strategy for developed areas and exclude most of the flow strategy and conventional strategy load reduction BMPs. There are no alternatives that combine the active strategy with substantial conventional and flow strategy treatment BMPs. There are inconsistencies between Table 1 and the draft alternatives matrix. Basins are part of the conventional strategy in Table 1 and the flow strategy in the alternatives matrix.
- 3.0 Alternatives Development The two-dimensional matrix is a useful approach which is easily understood. However, there should be additional work to develop hybrid strategies within the high load reduction column. It is difficult to select high cost alternatives for further study without

having more information on how large the incremental load reduction benefits would be. Since there is little interest in proceeding with further work on the low or moderate load reduction columns, it would be useful to see development of more reasonable high load reduction alternatives before selecting alternatives for further study. Only two weeks are available for development of the detailed alternatives and for the preparation of the draft report identifying the preferred alternative. These are crucial steps in the water quality planning process, and should not be rushed. There may be several alternatives in the high-load, moderate or high maintenance categories that could be developed, and should be seriously considered as alternatives selected for further study.

Comments on draft Hydrologic Approach¹

Designing for a treatment volume equal to a 24-hour precipitation depth of 90% of the storms should not imply that designs would treat 90% of the storm runoff. While the Hydrologic Approach paper says that "As treatment capacity increase beyond the inflection point, there is little increase in the number of 24-hour storm events for which the entire runoff volume is treated" there would still be significant increase in the % of the volume of rainfall that could be treated. The draft report states that the inflection point corresponding to the 90 percentile storm approximates the inflection point of the precipitation frequency curve and represents the optimization of treatment efficiency for a 24-hour runoff volume. Please provide further evidence to support this statement.

It should be possible to calculate what % of total (average annual or period of record) precipitation occurs during the largest 10% of the storms. Please also calculate a 24-hour precipitation depth that accounts for 90% of the average annual precipitation. The 90% storm design standard also assumes that antecedent moisture conditions have no impact on available treatment volume, and that there is a good correlation between precipitation and runoff, even in winter. While much of the winter precipitation occurs as snow, there are significant rain events each winter, and snowmelt during warm spells or in late winter also would have major impacts on available storage capacity in treatment facilities sized for 90% storm.

Using 1931-1961 precipitation data from Tahoe City from a rather old and admittedly obscure 1967 report² on probabilities of precipitation in the western states, the probability of receiving at least 1.0 inch of precipitation/week exceeds 20% for the five months from November through March. The probability of at least 2 inches of precipitation/week each year exceeds 10% for approximately the same five months. The probability of at least 0.6 inch/week generally ranges

¹ The document I received ended at page 6. Please inform me if I did not receive the complete document.

² Gifford, R.O., Ashcroft, G.L., and Magnuson, M.D., Probability of Selected Precipitation Amounts in the Western Region of the United States. Agricultural Experiment Station, University of Nevada, T-8. 1967

from 40-60% during this period. This information may help you assess Antecedent Moisture Conditions class when working with runoff curve numbers.

The report also uses a threshold storm method based on identifying a threshold storm (4.3 inches/24 hr) at which runoff dominance shifts from the developed watershed to the undeveloped watershed. The analysis lacks a discussion of whether runoff dominance has any relationship with pollutant load dominance. Since tributary runoff from the upper watershed (largely undeveloped) might be expected to have lower pollutant concentrations than urban runoff, please explain the significance of the shift in runoff dominance in terms of pollutant loads. The report then acknowledges that treatment of 4.3 inches of runoff is unfeasible and suggests using the portion of the runoff volume (1.8 inches) under the rising limb of a SCS type IA storm distribution for the 24-hour 4.3-inch storm.

The comparison with historic rainfall section uses an annual exceedence rather than partial-duration series to assess the recurrence period for 24-hour storms at Tahoe City. Figure 4 (Annual exceedence series for 24-hour storm Tahoe City, CA) would be more useful if displayed on Gumbel paper, so we can more easily see data points from the 1-10 year recurrence intervals which includes your design storm. Considering annual exceedence rather than partial-duration series ignores all storms that are less than the annual maximum storm. There may be several storms in a single year that exceed the design storm depths being considered, but only one storm a year is considered in the annual exceedence series. Table 1, which appears to based on the annual exceedence series, displays frequency values for the frequency of only the annual maximum storms that exceed the treatment capacity. Please provide information on the total number of storms over the 59-year period of record that exceed the proposed design storm depths. This information should be available from the Tahoe City precipitation data set used in Figure 1.

At least some hourly precipitation data is available from a DRI website on SNOTEL sites. http://www.wrcc.dri.edu/snotel/snocali.html. This information can be used to provide more information on typical shorter duration storm intensities. The Tahoe City Cross-(Country ski area) is the site nearest to Kings Beach. Hourly precipitation after 1996 is available as long as the period displayed is 30 days or less.

An example to demonstrate my concern about the 90 percentile storm as a water quality design standard is found in Tahoe City SNOTEL data from last year: Approximately 28" of total precipitation was recorded during the 2001-2002 WY. About 1/3 of the annual precipitation occurred when 9" was recorded from Nov 21-Dec 2, including about 4" during two 2-inch-24-hr rain events separated by 36 hours of dry weather. Your report acknowledges that these storms were among the few recent storms that would exceed proposed treatment capacity. Within this 10-day period there actually were 5 precipitation events of 1-inch or more precipitation.

Though none of the events were close to a 20-year 1-hour (approximately 1-inch/hr/hr) design storm, your design approach and alternatives analysis should be modified to adequately assess whether these storms would actually be treated or bypassed by the proposed facilities.

Comments on draft Pollutant Load Estimation Approach

This material was reviewed only briefly. This approach appears to rely chiefly on relating the project area to tributary monitoring at Incline and Third Creeks. Most of the developed area in Kings Beach does not discharge to the major tributary (Griff Creek) and, as an "intervening area" between major tributaries, discharges directly to Lake Tahoe. While tributary monitoring at Incline and Third Creeks includes some runoff from developed areas, tributary monitoring data may not be a appropriate for scaling procedures to estimate loads from the developed areas in Kings Beach which are not tributary to Griff Creek. Development extends further up the hill and is more dispersed in the Third and Incline watersheds, while development is concentrated on smaller parcels closer to the lake at Kings Beach.

Some data on pollutant loads and concentrations within developed "intervening areas" has been collected by TRG, and should be incorporated into load estimation. Data from two years of Caltrans stormwater monitoring should also be used in estimated loads, as well as information on use of abrasives and deicers by Caltrans and Placer County.

The report states that for each of the four alternatives selected, each storm event captured would be evaluated for BMP efficiency, and a bypass load would be estimated. Since most of the treatment proposed in the County's preferred alternatives (7-10) is provided in sedimentation/infiltration basins, how will the load estimation handle antecedent precipitation? How will the load estimation handle runoff volume and load from private parcels within the subwatersheds which would reduce available basin capacity? The load estimation approach report also assumes that the bypass fraction (based on sizing basins for the 90% storm event from only the impermeable areas in the rights-of-way) in the developed watershed is not significant.

Additional work on and buy-in from reviewing agencies is needed on the Hydrologic and Pollutant Load Estimation approaches before these approaches are used in the evaluation of preferred alternatives.

Alternatives for further study

I am reluctant to choose from the alternatives put forward. Hybrid strategies that could provide more load reduction at a lower cost than Alternatives 10-13 need further development. All alternatives need to either include: 1) mandatory BMP compliance (with some details on the plan to achieve compliance) with a realistic appraisal of expected load and flow originating from private land following BMP compliance, or 2) how County and County-Caltrans shared facilities will treat runoff from private land with an assessment of load and flow originating from private land. Alternatives should be analyzed for load reduction potential using design sizing criteria other than just the 20-year 1-hour storm runoff from paved rights-of-way. A combination of

BMPs that should be designed for concentrated runoff infiltration volumes, BMPs designed for concentrated runoff treatment flows, and BMPs that can reduce the volumes and peak flows that need to be conveyed should be considered.

Since treatment volume size is a constraint, all alternatives could incorporate more efforts to reduce the collection and concentration of flows. For example, along some east-west streets flow from the south side of a crowned road may already sheet flow onto adjacent developed or undeveloped parcels. Use of publicly-owned parcels may already being considered, but public funding for enhancement of existing undersized BMPs or to make proposed infiltration BMPs on private parcels large enough to handle adjacent street runoff has not been considered. Paying \$1000/parcel for several hundred parcels for materials or excavation costs may be cost-effective when compared to costs for curb and gutter, storm drains, sand traps, vaults, and basins.

Methods to better evaluate the performance of the design alternatives should be improved before rating the alternatives. Rather than analyzing just whether proposed treatment volumes are adequate (if treatment BMPs are empty) to contain a design storm depth, the analysis should consider BMP treatment alternative performance during a range of storm runoff events. Previous storms and snowmelt runoff and their impacts on available storage in volume-sized BMPs should be considered. If basins or galleries are full, are bypassed flows routed to other treatment BMPs or conveyed to the lake? What is the design capacity (volume or flow) of BMPs that would receive bypass flows? Consider how the alternatives would perform if the selected design storm occurred when treatment basins or galleries were half-full, or completely full. Consider how the alternative would perform during a 48 hour storm at twice the rainfall depth of the treatment storm. Some alternatives may be very effective at the design storm, but perform very poorly during the 10% of the storms that may carry 30% of the flow. Other alternatives may not perform as well during the design storm, but performance would not drop off as rapidly during larger storms. An approach to estimate load reduction over an entire water year should have been developed, reviewed, and agreed upon before we were asked to evaluate the thirteen design alternatives. It is important that this issue be resolved before completing substantial work on analyzing alternatives for the purpose of selecting a preferred alternative (Task 5).

Variants of Alternatives 8 and 9 deserve further study, and I would like to see the development of an Alternative 11 modified to include expanded snow hauling to a snow storage site with a treatment plant or other advanced filtration/adsoprtion system designed to remove pollutants from snow melt and possibly from vactor decant liquids. Snow haul should be considered for snow from subwatersheds where the ability to provide adequate treatment is limited. Snow haul need not be limited to snow from public roads. Alternative 11 should include infiltration galleries or basins sized for larger runoff volumes, as well as other BMPs such as in-line filtration/adsorption for all but the highest discharges that would otherwise be bypassed when infiltration BMPs are full.

Alternative 12 should be modified to include some aspects of the active strategy within subwatersheds where adequately-sized treatment facilities cannot otherwise be built. It should not be necessary to route all flows within developed Kings Beach watersheds to chemical treatment plants; key elements of the "flow-based" or "conventional" strategies may be the main treatment in some of the subwatersheds. More work should be done to look at feasible and lower-cost chemical or mechanical treatment processes that could be installed in sub-watershed scale facilities.

If at all possible, the County should take some additional time to better develop the alternatives to be selected for further study, and ensure that the further study and selection of preferred alternatives adequately assesses water quality benefits. If you have questions regarding these comments please contact me at (530) 542-5433.

Sincerely,

Robert Erlich

Environmental Scientist

Robert Erlin

c. Dave Zander – CTC
 Larry Benoit, Charles Emmett – TRPA
 John Holder, Caltrans District 3

T:KBWQPG Task 3-5 comments 11-02



California Regional Water Quality Control Board

Lahontan Region



Internet Address: http://www.swrcb.ca.gov/rwqcb6 2501 Lake Tahoe Boulevard, South Lake Tahoe, California 96150 Phone (530) 542-5400 • FAX (530) 544-2271

August 23, 2002

Leslie Burnside (via e-mail only, with copy to Rebecca Bond Placer Co.)
Associate Environmental Scientist
Harding ESE, Inc.
Engineering and Environmental Services
1572 East College Parkway, Suite 162
Carson City, NV 89706

Kings Beach Water Quality Planning: Identification of Substantial Pollutant Sources and Water Quality Treatment Potential

Thank you again for your patience. I still have not been able to spend as much time as I would have hoped on this review, but I hope even these comments may be useful. Please share these with Rebecca Bond and others who have submitted comments.

2.1.2 Pollutant Source Descriptions

Page 2. Caltrans has already published information based on one year of sampling Tahoe Basin highway runoff at 3 south shore locations, and has been sampling at 6 locations in 2001-2002. I believe Caltrans has looked at nutrients concentrations related to sediment size, and provides some information on how Tahoe stormwater runoff compares with other runoff characterization sites in California for constituents such as nutrients and metals. Also check with Alan Heyvaert (UCD-TRG) or Dave Roberts (Lahontan RB-TMDL unit) for updates on their initial studies on intervening watershed runoff characterization for different land use types.

Can you provide additional information on air-borne deposition of various pollutants from various sources (dust, wood smoke, vehicles)? Even if some types of air-borne deposition would be uniform on undeveloped and developed lands, would the developed lands be more of a source because impermeable surfaces would not retain the pollutants.

Page 3. While effluent standards are currently set for total nitrogen and total phosphorus, we may be most interested in reducing biologically available or dissolved forms. Consider dropping "total" from the nitrogen and phosphorus parenthesis following the "Nutrients" bullet.

2.2 Field Investigation and Verification of Pollutant Sources

Page 4. During wetter years, I've observed roadside seeps and discharge from springs and ephemeral streams along the north and east sides of the developed portions of Kings Beach, even after spring snow melt. Flow from these sources generally travel along roadside conveyances, and may be routed into stormwater treatment facilities. Can you identify any of these flow sources on your maps identifying existing runoff patterns?

Page 5. Hydrologic Connectivity. Appendix B mentions streams and/or SEZ. Can we use this distinguish between connectivity to surface waters and near surface groundwaters? If the parcel is noted as SEZ, can you note whether the SEZ is related to channels or high water tables? More stormwater pre-treatment would be needed for infiltration in areas which are close to seasonal high water tables.

2.22 Rationale for Ranking, also Figure 2.0

Though we have discussed technical (GIS) issues which made it difficult delineate road polygons, it would be very useful to show roads ranked as sources (perhaps based on information from Caltrans and Placer County on how much abrasives and de-icers are applied).

Page 6-7

Show significant source areas (dirt roads, bank erosion, etc.) within large parcels in appropriate colors on Figure 2.

3.0 Pollutant Source Control

Since deposition of airborne pollutants may be substantial, and could lead to loading from "hydrologically-connected" parcels that don't otherwise appear to be sources, the watershed based strategy should have some discussion of source control methods to reduce this loading, e.g., vegetation filter strips or other methods to retain on site, requirements to sweep, rather than use hoses or blowers to clean paved surfaces.

4.0 Potential Water Quality Treatment Sites

Page 9. Volume of flow and pollutant loading rates were listed as evaluated, but not assessed in Appendix C. Please explain when these factors will be used. Since some pollutant removal processes are based on flow (e.g., filtration) rather than volume please incorporate rankings that do not focus only on volume. There may be other areas in the report where it would be useful to specify the pollutant removal process, and whether it is flow-dependent or volume-dependent

Table 1.

Source Control Alternatives.

Can you include discussion of heated pavements/roadways as a source control alternatives? There has been some new work on conductive pavements in Ottawa, which do not require heating pipes. May be costly, and may not have a long track record, but it should be mentioned, since it may be able to nearly eliminate use of abrasives.

Sincerely,

Robert Erlich

Environmental Scientist

Robert Ellis



California Regional Water Quality Control Board

Lahontan Region

Winston H. Hickox Secretary for Environmental Protection

2501 Lake Tahoe Boulevard, South Lake Tahoe, California 96150 Phone (530) 542-5400 • FAX (530) 544-2271

MEMORANDUM

TO:

Dave Zander

Erosion Control Grants Program

CALIFORNIA TAHOE CONSERVANCY

FROM:

Robert Erlich

Environmental Scientist

LAHONTAN REGIONAL WATER QUALITY CONTROL BOARD

DATE:

November 27, 2001

COMMENTS ON THE KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT (KBCCIP) DRAFT WORK PLAN SUBMITTED BY PLACER COUNTY

Lahontan Regional Water Quality Control Board (Regional Board) staff have received a copy of the above-mentioned document. We understand that the Draft Work Plan will guide Placer County Department of Public Works (Placer County) in developing tasks, schedule, and budget for the KBCCIP. Regional Board staff have reviewed the Draft Work Plan and have the following comments.

Previous Kings Beach Studies and Water Quality Goals

Task 2.0 of the Draft Work Plan refers to tools developed during the KBCCIP Feasibility Study completed in 2000. The County has also developed a Kings Beach Drainage Master Plan. The Feasibility Study and Drainage Master Plan emphasized conveyance needs and improvements that could trap coarse sediments. Table 6 in the Feasibility Study summarizes recommendations from the Drainage Master Plan for sub-area water quality improvements, but does not discuss how to assess the effectiveness of the proposed project in meeting water quality goals set by LRWQCB and TRPA.

Proposed Workplan Tasks

Initial planning should include a comprehensive watershed analysis to estimate current pollutant loads, their sources, types of pollutant removal mechanisms being considered, and the ability of current and proposed facilities to treat runoff. Though it is useful to identify potential treatment sites early in the planning process, the proposed tasks do not assess how the proposed sites (or other sites within or outside of the project boundaries) could be used to meet water quality goals which require treatment to remove fine sediment and dissolved nutrients. Tasks 2 and 3 screen potential treatment sites using a variety of criteria. Although Task 4.0 addresses current facilities,

the evaluation appears limited to the ability of existing BMPs to treat the 20-year, 1-hour storm event from only road rights-of-ways.

Only Task 3.2.f (\$9,100 combined consultant and county cost) considers whether proposed treatment sits are conducive to the treatment options being considered. For a project with proposed total capital costs exceeding \$24 million, and drainage improvement costs exceeding \$5 million (KBCCIP Project Study Report), the initial workplan needs much more emphasis on determining which treatment options can be used and how the project can meet its water quality objectives. Adequate resources should be set aside for tasks to identify pollutant load reduction associated with proposed BMPs and/or changes to land use or maintenance practices associated with this project.

Municipal Permit

Regional Board Order No. 6-00-82, NPDES Permit No. CAG616001 (Municipal Permit) contains specific Waste Discharge Requirements for the City of South Lake Tahoe, El Dorado County, and Placer County storm water and urban runoff. In addition to the 20 year, 1-hour design storm, the Municipal Permit includes numeric effluent guidelines specifying maximum allowable pollutant concentrations for storm water discharges. The analysis of current treatment facilities discussed in Task 4.0 should focus on the ability to meet effluent limits as required by the Municipal Permit as well as the potential to reduce overall pollutant loads. The Municipal Permit also holds the permittees responsible for all storm water runoff within their legal jurisdictional boundaries. As such, Placer County is responsible for meeting required runoff quality from commercial and residential properties. The planning of water quality improvements for Kings Beach should include an inventory of commercial parcels with and without BMPs and account for the runoff volume and pollutant load generated from these parcels. An analysis of expected commercial and residential BMP implementation would also be useful, along with an outreach program to encourage private and commercial property owners to install appropriate BMPs. Any water quality improvements should account for additional runoff from sites unlikely to implement BMPs within the next few years.

Treatment Options and Site Selection

Although the Draft Work Plan includes a thorough discussion of potential site analysis, there is little mention of which types of treatment processes (e.g., filtration, coagulation, infiltration, sweeping) may be used to remove pollutants of concern from stormwater and which BMPs may be installed. Regional Board staff encourage considering a broad range of BMPs to address storm water treatment, including vault systems, shallow wetland treatment basins, the use of adsorptive media, installation of regional storm water treatment plants sized for design storm runoff or for treatment of hauled snow and vactor wastes, and other innovative treatment options. Potential to upgrade existing facilities with new technologies to improve pollutant removal should also be reviewed. Since various BMPs have different site requirements, the site selection

Dave Zander KBCCIP workplan comments

process for new facilities should account for a wide range of potential BMPs. Access for maintenance and monitoring and required maintenance frequency should also be included in the site selection screening process.

Conclusions

Regional Board staff appreciate the time invested in the Draft Work Plan and the opportunity to comment early in the process. Thoughtful planning is the first step toward implementing successful water quality improvement projects. We would like to see additional emphasis placed on clearly defined water quality goals based on pollutant load reduction and compliance with the conditions of the Municipal Permit. By focusing BMP efforts on reducing fine sediments and dissolved nutrients, the Kings Beach Commercial Core Improvement Project can have positive impact on water quality in the Lake Tahoe Basin. The Guidance Document for Implementing BMPs in the Lake Tahoe Basin prepared by the Tahoe Interagency Roadway Runoff Subcommittee is available for additional information for both contractors and project planners. Please contact Robert Larsen at (530) 542-5439 if you are interested in a copy of the Guidance Document.

We appreciate your efforts to protect water quality in the Lake Tahoe Basin. If you have any questions please contact me at (530) 542-5433.

cc: Bob Costa Engineering Manager Placer County Department of Public Works

DATE PECEIVED

CALIFORNIA TAHOE CONSERVANCY

2161 LAKE TAHOE BOULEVARD, SUITE 2 SOUTH LAKE TAHOE, CA 96150 (530) 542-5580

DEC 30 2002

PLANNING DEPARTMENT

December 23, 2002

Lori Lawrence, Environmental Review Clerk Placer County Planning Department 11414 B Avenue Auburn, CA 95603

RE: Notice of Preparation for the Kings Beach Commercial Core Improvement Project

Dear Ms. Lawrence,

Thank you for the opportunity to respond to the Notice of Preparation (NOP). We are pleased that the County is undertaking this comprehensive project, and encourage maintaining the current proposed schedule in order to begin improvements in Summer 2006.

At this time, I would like to provide comments on the Kings Beach Commercial Core Improvement Project on behalf of the California Tahoe Conservancy's Public Access and Recreation Program. This program recognizes the need to provide regional access and recreation opportunities throughout the Basin, with an emphasis on providing access to regionally-significant lakefront and natural areas that receive or can accommodate significant visitor use. Trails linking recreation facilities are also given high priority.

The NOP states that the project was initiated by the need to improve pedestrian and bicyclist access along and across State Route 28 within the Kings Beach Commercial Core. To this end, we would like to emphasize the importance of safely-designed bicycle lanes. Where feasible, the project design should include bicycle paths that are separated from the roadway. However, recognizing that right-of-way width and other constraints may not allow this separation, sufficient space in the roadway must be identified and set aside for use by bicyclists, as mentioned in Section III (Need and Purpose) of the NOP Information Package.

The description of the Bicycle-Pedestrian Access option in Section IV (List of Alternatives) is unclear. Specifically, please clarify if there will be a 1.5m-wide striped bicycle lane in addition to the 2.4m-wide striped lane designated for parallel parking. If so, this configuration would be consistent with Caltrans and the American Association of State Highway and Transportation Officials (AASHTO) standards for Class II bicycle lanes. For your information, I have included excerpts of the Caltrans *Highway Design Manual* and the AASHTO *Guide for the Development of Bicycle Facilities* related to these standards. The bicycle lane striping, like other amenities proposed by the project, will need to be regularly maintained.

Lastly, regarding the bicycle lane, since the project is indeed listed under various Air Quality / Transportation Projects in the Environmental Improvement Program, the environmental

assessment should include some discussion that the lane may contribute to air quality benefits by providing a viable alternative to motorized travel, thus reducing vehicle miles travelled.

The project's emphasis on the pedestrian is a much-needed improvement to the Kings Beach Commercial Core. We suggest that native species be used for street trees, as they would be better-suited to both the environmental conditions and the character of the area. Furthermore, street improvements and amenities should not hinder access by the physically disabled. To the extent practical, the project should also be compatible with existing amenities provided by the Conservancy's projects, most notably the Kings Beach Plaza project on the south side of State Route 28 between Bear and Coon Streets.

Finally, Figure 5 of the NOP Information Package identifies several Conservancy and North Tahoe Public Utility District (NTPUD) properties as potential parking lot and drainage treatment improvement sites. Please recognize that the use of Conservancy properties, as well as any NTPUD property purchased through a grant from the Conservancy, must be consistent with the original purposes of acquisition. As you may be aware, the Public Access and Recreation Program is currently developing conceptual plans for the Secline Beach area (including the NTPUD property identified in Figure 5) and a land use and market feasibility study for the Conservancy property at the southeast corner of Coon and State Route 28. We will make every effort to coordinate our work with that of your proposed project.


Please call me at 530-542-5580, extension 130 if you have any questions about my comments, or if our program staff can be of help in any way.

Sincerely,

Virginia A Esperar

enclosures

ouide for the development of bicycle for ials





1999

prepared by the aashto task force on geometric design




Figure 5. Bicycle Lane Markings



Design Bike Lanes

Bike Lanes

Bike lanes can be incorporated into a roadway when it is desirable to delineate available road space for preferential use by bicyclists and motorists, and to provide for more predictable movements by each. Bike lane markings, as exemplified in Figure 5, can increase a bicyclist's confidence in motorists not straying into their path of travel. Likewise, passing motorists are less likely to swerve to the left out of their lane to avoid bicyclists on their right. Also see Chapter 2, Other Design Criteria, for additional information which applies to bike lanes. Drainage grates, railroad crossings, traffic control devices, etc., need to be evaluated and upgraded if necessary for bicycle use.

Bike lanes should be one-way facilities and carry bike traffic in the same direction as adjacent motor vehicle traffic. Two-way bike lanes on one side of the roadway are not recommended when they result in bicycles riding against the flow of motor vehicle traffic. Wrong-way riding is a major cause of bicycle crashes and violates the rules of the road as stated in the *UVC*³. Bicycle-specific wrong-way signing may be used to discourage wrong-way travel. However, there may be special situations where a two-way bike lane for a short distance can eliminate the need for a bicyclist to make a double crossing of a busy street or travel on a sidewalk. This should only be considered after careful evaluation of the relative risks and should be well documented in the project file.

On one-way streets, bike lanes should generally be placed on the right side of the street. Bike lanes on the left side are unfamiliar and unexpected for most motorists. This should only be considered when a bike lane on the left will substantially decrease the number of conflicts, such as those caused by heavy bus traffic or unusually heavy turning movements to the right, or if there are a significant number of left-turning bicyclists. Thus, left-side bike lanes should only be considered after careful evaluation. Similarly, two-way bike lanes on the left side of a one-way street could be considered with a suitable separation from the motor vehicle traffic after a complete engineering study of other alternatives and relative risks.

Bike Lane Widths

To examine the width requirements for bike lanes, Figure 6 shows four typical locations for such facilities in relation to the roadway. For roadways with no curb and gutter, the minimum width of a bike lane should be 1.2 m (4 feet). If parking is permitted, as in Figure 6(1), the bike lane should be placed between the parking area and the travel lane and have a minimum width of 1.5 m (5 feet). Where parking is permitted but a parking stripe or stalls are not utilized, the shared area should be a minimum of 3.3 m (11 feet) without a curb face and 3.6 m (12 feet) adjacent to a curb face as shown in Figure 6(2). If the parking volume is substantial or turnover is high, an additional 0.3 to 0.6 m (1 to 2 feet) of width is desirable.

Bike lanes should never be placed between the parking lane and curb lane. Bike lanes between the curb and parking lane can create obstacles for bicyclists from opening car doors and poor visibility at intersections and driveways and they prohibit bicyclists from making left turns.

Figure 6(3) depicts a bike lane along the outer portion of an urban curbed street where parking is prohibited.

The recommended width of a bike lane is 1.5 m (5 feet) from the face of a curb or guardrail to the bike lane stripe. This 1.5-m (5-foot) width should be sufficient in cases where a 0.3-0.6 m (1-2 foot) wide concrete gutter pan exists, given that a minimum of 0.9 m (3 feet) of ridable surface is provided, and the longitudinal joint between the gutter pan and pavement surface is smooth. The width of the gutter pan should not be included in the measurement of the ridable or usable surface, with the possible exception of those communities that use an extra wide, smoothly paved gutter pan that is 1.2 m (4 feet) wide as a bike lane. If the joint is not smooth, 1.2 m (4 feet) of ridable surface should be provided.

Since bicyclists usually tend to ride a distance of 0.8-1.0 m (32-40 inches) from a curb face, it is very important that the pavement surface in this zone be smooth and free of structures. Drain inlets and utility covers that extend into this area may cause bicyclists to swerve, and have the effect of reducing the usable width of the lane. Where these structures exist, the bike lane width may need to be adjusted accordingly.


Figure 6(4) depicts a bike lane on a roadway in an outlying area without curbs and gutters. This location is in an undeveloped area where infrequent parking is handled off the pavement. Bike lanes should be located within the limits of the paved shoulder at the outside edge. Bike lanes may have a minimum width of 1.2 m (4 feet), where the area beyond the paved shoulder can provide additional maneuvering width. A width of 1.5 m (5 feet) or greater is preferable and additional widths are desirable where substantial truck traffic is present, or where motor vehicle speeds exceed 80 km/h (50 mph).

A bike lane should be delineated from the motor vehicle travel lanes with a 150-mm (6-inch) solid white line. Some jurisdictions have used a 200-mm (8-inch) line for added distinction. An additional 100-mm (4-inch) solid white line can be placed between the parking lane and the bike lane (see Figure 7). This second line will encourage parking closer to the curb, providing added separation from motor vehicles, and where parking is light it can discourage motorists from using the bike lane as a through travel lane.

Bike lanes should be provided with adequate drainage to prevent ponding, washouts, debris accumulation and other potentially hazardous situations for bicyclists. The drainage grates should be bicycle-safe. When an immediate replacement of an incompatible grate is not possible, a temporary correction of welding thin metal straps across the grates perpendicular to the drainage slots at 100-mm (4-inch) center-to-center spacing should be considered.




Design Bike Lanes




* The optional solid white stripe may be advisable where stalls are unnecessary (because parking is light) but there is concern that motorists may misconstrue the bike lane to be a traffic lane.

(1) ON-STREET PARKING



*3.9 m (13 ft) is recommended where there is substantial parking or turnover of parked cars is high (e.g. commercial areas).

(2) PARKING PERMITTED WITHOUT PARKING STRIPE OR STALL



*If rumble strips exist there should be 1.2 m (4ft) minimum from the rumble strips to the outside edge of the shoulder.

Figure 6. Typical Bike Lane Cross Sections




Design Bike Lanes (15) Barrier Posts. It may be necessary to install barrier posts at entrances to bike paths to prevent motor vehicles from entering. When locating such installations, care should be taken to assure that barriers are well marked and visible to bicyclists, day or night (i.e., install reflectors or reflectorized tape).

Striping an envelope around the barriers is recommended (see Figure 1003.1G). If sight distance is limited, special advance warning signs or painted pavement warnings should be provided. Where more than one post is necessary, a 1.5 m spacing should be used to permit passage of bicycle-towed trailers, adult tricycles, and to assure adequate room for safe bicycle passage without dismounting. Barrier post installations should be designed so they are removable to permit entrance by emergency and service vehicles.

Generally, barrier configurations that preclude entry by motorcycles present safety and convenience problems for bicyclists. Such devices should be used only where extreme problems are encountered.

Figure 1003.1G Barrier Post Striping



(16) Lighting. Fixed-source lighting reduces conflicts along paths and at intersections. In addition, lighting allows the bicyclist to see the bicycle path direction, surface conditions, and obstacles. Lighting for bicycle paths is important and should be considered where riding at night is expected, such as bicycle paths serving college students or commuters, and at highway intersections. Lighting should also be considered through underpasses or tunnels, and when nighttime security could be a problem.

Depending on the location, average maintained horizontal illumination levels of 5 lux to 22 lux should be considered. Where special security problems exist, higher illumination levels may be considered. Light standards (poles) should meet the recommended horizontal and vertical clearances. Luminaires and standards should be at a scale appropriate for a pedestrian or bicycle path.

1003.2 Class II Bikeways

Class II bikeways (bike lanes) for preferential use by bicycles are established within the paved area of highways. Bike lane stripes are intended to promote an orderly flow of traffic, by establishing specific lines of demarcation between areas reserved for bicycles and lanes to be occupied by motor vehicles. This effect is supported by bike lane signs and pavement markings. Bike lane stripes can increase bicyclists' confidence that motorists will not stray into their path of travel if they remain within the bike lane. Likewise, with more certainty as to where bicyclists will be, passing motorists are less apt to swerve toward opposing traffic in making certain they will not hit bicyclists.

Class II bike lanes shall be one-way facilities. Two-way bike lanes (or bike paths that are contiguous to the roadway) are not permitted, as such facilities have proved unsatisfactory and promote riding against the flow of motor vehicle traffic.

- (1) Widths. Typical Class II bikeway configurations are illustrated in Figure 1003.2A and are described below:
 - (a) Figure 1003.2A-(1) depicts bike lanes on an urban type curbed street where parking stalls (or continuous parking stripes) are marked. Bike lanes are located between the parking area and the traffic lanes. As indicated, 1.5 m shall be the minimum width of bike lane where parking stalls are marked. If parking volume is substantial or turnover high, an additional 0.3 m to 0.6 m of width is desirable.

Bike lanes shall not be placed between the parking area and the curb. Such facilities increase the conflict between bicyclists and opening car doors and reduce visibility at intersections. Also, they prevent bicyclists from leaving the bike lane to turn left and cannot be effectively maintained.


- (b) Figure 1003.2A-(2) depicts bike lanes on an urban-type curbed street, where parking is permitted, but without parking stripe or stall marking. Bike lanes are established in conjunction with the parking areas. As indicated, 3.3 m or 3.6 m (depending on the type of curb) shall be the minimum width of the bike lane where parking is permitted. This type of lane is satisfacory where parking is not extensive and where turnover of parked cars is infrequent. However, if parking is substantial, turnover of parked cars is high, truck traffic is substantial, or if vehicle speeds exceed 55 km/h, additional width is recommended.
- (c) Figure 1003.2A-(3) depicts bike lanes along the outer portions of an urban type curbed street, where parking is prohibited. This is generally the most desirable configuration for bike lanes, as it eliminates potential conflicts resulting from auto parking (e.g., opening car doors). As indicated, if no gutter exists, the minimum bike lane width shall be 1.2 m. With a normal 600 mm gutter, the minimum bike lane width shall be 1.5 m. The intent is to

provide a minimum 1.2 m wide bike lane, but with at least 0.9 m between the traffic lane and the longitudinal joint at the concrete gutter, since the gutter reduces the effective width of the bike lane for two reasons. First, the longitudinal joint may not always be smooth, and may be difficult to ride along. Secondly, the gutter does not provide a suitable surface for bicycle travel. Where gutters are wide (say, 1.2 m), an additional 0.9 m must be provided because bicyclists should not be expected to ride in the gutter. Wherever possible, the width of bike lanes should be increased to 1.8 to 2.4 m to provide for greater safety. 2.4 m bike lanes can also serve as emergency parking areas for disabled vehicles.

Striping bike lanes next to curbs where parking is prohibited only during certain hours shall be done only in conjunction with special signing to designate the hours bike lanes are to be effective. Since the Vehicle Code requires bicyclists to ride in bike lanes where provided (except under certain conditions), proper signing is necessary to inform bicyclists that they are required to ride in bike lanes only during the course of the parking prohibition. This type of bike lane should be considered only if the vast majority of bicycle travel would occur during the hours of the parking prohibition, and only if there is a firm commitment to enforce the parking prohibition. Because of the obvious complications, this type of bike lane is not encouraged for general application.


Figure 1003.2A(4) depicts bike lanes on a highway without curbs and gutters. This location is in an undeveloped area where infrequent parking is handled off the pavement. This can be accomplished by supplementing the bike lane signing with R25 (park off pavement) signs, or R26 (no parking) signs. Minimum widths shall be as shown. Additional width is desirable, particularly where motor vehicle speeds exceed 55 km/h.

Figure 1003.2A Typical Bike Lane Cross Sections (On 2-lane or Multilane Highways) Parking Stalls or Optional 100 mm Solid Stripe




"The optional solid white stripe may be advisable where state are unnecessary (because parking is light); but there is concern that motorists may discontrue the bike take to be a traffic lane.


(1) STRIPED PARKING



* 8.9 is recommended where there is substantial parking or turnover of peaked cars is high (sig. commercial aleas).

(2) PARKING PERMITTED WITHOUT PARKING STRIPE OR STALL





The typical traffic lane width next to a bike lane is 3.6 m. Lane widths narrower than 3.6 m must receive approval as discussed in Index 82.2. There are situations where it may be necessary to reduce the width of the traffic lanes in order to stripe bike lanes. In determining the appropriateness of narrower traffic lanes, consideration should be given to factors such as motor vehicle speeds, truck volumes, alignment, and sight distance. Where favorable conditions exist, traffic lanes of 3.3 m may be feasible.

Bike lanes are not advisable on long, steep downgrades, where bicycle speeds greater than 50 km/h are expected. As grades increase, downhill bicycle speeds will increase, which increases the problem of riding near the edge of the roadway. In such situations, bicycle speeds can approach those of motor vehicles, and experienced bicyclists will generally move into the motor vehicle lanes to increase sight distance and maneuverability. If bike lanes are to be striped, additional width should be provided to accommodate higher bicycle speeds.

If the bike lanes are to be located on oneway streets, they should be placed on the right side of the street. Bike lanes on the left side would cause bicyclists and motorists to undertake crossing maneuvers in making left turns onto a two-way street.

(2) Striping and Signing. Details for striping and signing of bike lanes are included under Topic 1004.

Raised barriers (e.g., raised traffic bars and asphalt concrete dikes) or raised pavement markers shall not be used to delineate bike lanes. Raised barriers prevent motorists from merging into bike lanes before making right turns, as required by the Vehicle Code, and restrict the movement of bicyclists desiring to enter or exit bike lanes. They also impede routine maintenance. Raised pavement markers increase the difficulty for bicyclists when entering or exiting bike lanes, and discourage

motorists from merging into bike lanes before making right turns.

Bike lane stripes should be placed a constant distance from the outside motor vehicle lane. Bike lanes with parking permitted (3.3 m to 3.9 m between the bike lane line and the curb) should not be directed toward the curb at intersections or localized areas where parking is prohibited. Such a practice prevents bicyclists from following a straight course. Where transitions from one type of bike lane to another are necessary, smooth tapers should be provided.

(3) At-grade Intersection Design. Most auto/bicycle accidents occur at intersections. For this reason, bikeway design at intersections should be accomplished in a manner that will minimize confusion by motorists and bicyclists, and will permit both to operate in accordance with the normal rules of the road.

Figure 1003.2B illustrates a typical at-grade intersection of multilane streets, with bike lanes on all approaches. Some common movements of motor vehicles and bicycles are shown. A prevalent type of accident involves straightthrough bicycle traffic and right-turning motorists. Left-turning bicyclists also have problems, as the bike lane is on the right side of the street, and bicyclists have to cross the path of cars traveling in both directions. bicyclists are proficient enough to merge across one or more lanes of traffic, to use the inside lane or left-turn lane. However, there are many who do not feel comfortable making this maneuver. They have the option of making a two-legged left turn by riding along a course similar to that followed by pedestrians, as shown in the diagram. Young children will often prefer to dismount and change directions by walking their bike in the crosswalk.

Figure 1003.2C illustrates recommended striping patterns for bike lanes crossing a motorist right-turn-only lane. When confronted with such intersections, bicyclists will have to merge with right-turning motorists. Since bicyclists are typically traveling at speeds less than motorists, they should signal and merge

where there is sufficient gap in right-turning traffic, rather than at any predetermined location. For this reason, it is recommended that all delineation be dropped at the approach of the right-turn lane. A pair of parallel lines (delineating a bike lane crossing) to channel the bike merge is not recommended, as bicyclists will be encouraged to cross at a predetermined location, rather than when there is a safe gap in right-turning traffic.

A dashed line across the right-turn-only lane is not recommended on extremely long lanes, or where there are double right-turn-only lanes. For these types of intersections, all striping should be dropped to permit judgment by the bicyclists to prevail. A Bike Xing sign may be used to warn motorists of the potential for bicyclists crossing their path.

At intersections where there is a bike lane and traffic-actuated signal, installation of bicyclesensitive detectors within the bike lane is desirable. Push button detectors are not as satisfactory as those located in the pavement because the cyclist must stop to actuate the push button. It is also desirable that detectors in left-turn lanes be sensitive enough to detect bicycles (see Chapter 9 of the Traffic Manual and Standard Plans for bicycle-sensitive detector designs). See Figure 1003.2D for bicycle loop detector pavement marking.

At intersections (without bike lanes) with significant bicycle use and a traffic-actuated signal, it is desirable to install detectors that are sensitive enough to detect bicycles.

(4) Interchange Design. As with bikeway design through at-grade intersections, bikeway design through interchanges should be accomplished in a manner that will minimize confusion by motorists and bicyclists. Designers should work closely with the local agency in designing bicycle facilities through interchanges. Local Agencies should carefully select interchange locations which are most suitable for bikeway designations and where the crossing meets applicable design standards. The local agency may have special needs and desires for continuity through interchanges which should be considered in the design process.

When a bike lane approaches a ramp intersection that intersects the local facility at or close to 90° (typical of a compact or spread diamond configuration), then Figure 1003.2C may be the appropriate method of getting bike lanes through the interchange.

However, when a bike lane approaches one or more ramp intersections that intersect the local facility at various angles other than 90° (typically high-speed, skewed ramps), Figure 1003.2E should be considered.

Figure 1003.2E, shows a bike lane through a typical interchange. The 150 mm bike lane stripe should be dropped 30 m prior to the ramp intersection as shown in the figure to allow for adequate weaving distance. The shoulder width shall not be reduced through the interchange area. The minimum shoulder width shall match the approach roadway shoulder width, but not less than 1.2 m or 1.5 m if a gutter exists. If the shoulder width is not available, the designated bike lane shall end at the previous local road intersection.

Depending on the intersection angles, either Figure 1003.2C or 1003.2E should also be used for multilane ramp intersections. Additionally, the outside through lane should be widened to 4.2 m when feasible. This allows extra room for bicycles to share the through lane with vehicles. The outside shoulder width should not be reduced through the interchange area to accommodate this additional width.

1003.3 Class III Bikeways

Class III bikeways (bike routes) are intended to provide continuity to the bikeway system. Bike routes are established along through routes not served by Class I or II bikeways, or to connect discontinuous segments of bikeway (normally bike lanes). Class III facilities are shared facilities, either with motor vehicles on the street, or with pedestrians on sidewalks, and in either case bicycle usage is secondary. Class III facilities are established by placing Bike Route signs along roadways.



League to Save Lake Tahoe

www.keeptahoeblue.org

MAIN OFFICE

955 Emerald Bay Road South Lake Tahoe, CA 96150 (530) 541-5388 • Fax (530) 541-5454

NORTH SHORE OUTREACH CENTER P.O. Box 7890 • 600 N. Lake Blvd Tahoe City, CA 96145 (530) 584-1660 · Fax (530) 584-1663

John D. Jorgenson, President William C. Callender, Treasurer Stephanie Mooers, Secretary

Vice Presidents: James V. de la Vergne Thomas Mertens William Russell-Shapiro

Executive Director: Rochelle Nason

Board of Directors: Adolphus Andrews, Jr. David Brandenburger William C. Callender James V. de la Vergne Anne C. Harper Fritzi N. Huntington John D. Jorgenson Charles Levin, D.D.S. Dennis Neeley William R. Marken Charles Clark McLeod, Jr. Thomas Mertens Stephanie Mooers Thomas C. Mooers Patricia H. Ronald Christine Rozance, M.O. William Russell-Shapiro Roland Westergard William W. Wilson

December 23, 2002

Lori Lawrence, Environmental Review Clerk Placer County Planning Department 11414 B Avenue Auburn, CA 95603

RE: Notice of Preparation of a Draft EIR/EIS for Kings Beach Commercial Core Improvement Project

Dear Ms. Lawrence,

The League to Save Lake Tahoe appreciates the opportunity to comment on this NOP. Below are our questions and concerns related to this document.

The 3-Lane with roundabouts alternative was developed in response to resident input on the subject. While the League has yet to endorse this alternative, or the 4-Lane with added stoplights alternative, we feel that there are several points of advantage to the 3-Lane alternative that should be noted. The 3-Lane alternative would be less detrimental to local air quality than the 4-Lane alternative. Stoplights would result in an increase in the number of idling cars, which contribute a higher localized concentration of PM₁₀ to the air. As opposed to stoplights, roundabouts would shuttle cars along, albeit at low speeds (10-15 mph). In addition, it should be noted that stoplights do not always provide for low accident rates, as evidenced by the higher than average accident rate at Coon Street (NOP p.3).

The NOP provides before and after visual simulations just east of the junction of SR28 with SR267 (Fig. 6). In the upcoming Draft EIR/EIS please include visual simulations for both alternatives at an intersection, such as SR28 with Bear Road, which is in the heart of the commercial core area.

Under option A the curb to curb width of the street would be 17.4 m to 19.2 m depending on bike lanes (NOP p. 10). In keeping with the goals of this project, bike lanes should not be excluded anywhere in the project area. At the same time, the alternative that produces the least amount of impermeable soil coverage will likely provide the best opportunity for water treatment, and would create less total runoff to be treated. Figure 2 shows the curb to curb width of the street as 22.2 m for option A and 18.6 m under option B. These numbers are inconsistent with those provided in the first paragraph of

15305436804

NOP page 10. It may be that the numbers from page 10 do not provide adequate room for parking. Please clarify the correct measurements in the Draft EIR/EIS. Please note, as well, that the space for a sidewalk/landscaped area bordering the street is not uniform throughout the project area.

The analysis in the EIR/EIS should not be limited to the two alternatives listed in the NOP. It may be advantageous to look at hybrids of the alternatives or to consider dropping Fox Street from the list of intersections in need of signals or roundabouts. On a similar note, it may be beneficial to introduce traffic calming infrastructure at the two ends of the commercial core area to help produce the "Main Street" feeling that boosts local economic conditions.

Finally, please insure that the project analysis performed in the Draft EIR/EIS focuses intensely on the potential environmental benefits of this project and the wishes of the residents of Kings Beach. Potential environmental benefits include traffic improvement and water quality improvements.

Thank you for the opportunity to comment on the Notice of Preparation for the Kings Beach Draft EIR/EIS. Please contact me with any questions.

Sincerely,

Daniel Sussman

Environmental Monitor

League to Save Lake Tahoe

Kings Beach Commercial Core Improvement Project Comments Recorded at December 5, 2003 Public Scoping Meeting at the Street Amenities Table

Person 1

Owns a business on North Lake Boulevard, located a few buildings east of Deer Street. Doesn't like the proposed trees. They will grow and block the storefronts from view of drivers passing on the street.

TRPA required her to landscape the street outside of her business. Will the project rip out her landscaping?

The project needs more parking. The parking entrance on the streetscape simulation is illegal. Caltrans required the parking entrance for her business to be located on Trout Avenue, behind the building, instead of directly off of North Lake Boulevard (Highway 28).

Prefers skinny sidewalks over wide sidewalks.

Doesn't know if new streetlights are necessary, since streetlights already exist.

The bicycle lane is not safe.

Person 2

Doesn't like the trees. They're not native species and don't go with the character of Kings Beach.

Doesn't like that the sidewalks replace the informal parking spaces that currently exist.

What is the plan for snow removal on Highway 28 and on the sidewalks?

Doesn't want Kings Beach to turn into San Francisco; wants town to retain its own character.

Persons 3 and 4

Like the sidewalks a lot—they would be much safer for pedestrians.

Streetlights are definitely needed. Right now it is very, very dangerous for pedestrians, especially ones walking to and from the casinos.

The curbs are good, because they protect the walkers.

The trees and other improvements are great because they will give the town some life and make the main street prettier. Right now the street looks dead.

Parking in the bike lane is dangerous for bikers. What if someone opens a car door on them? With the cars parked, is there enough room for the bicycle lane?

There should be more parking, especially near the cinema. At night, the parking lot for the miniature golf place is empty, and people have to park on the street. Would it be possible for the County to work out an agreement with the miniature golf place so that parking is available to the public (outside of miniature golf hours)?

"Kerry Wicker" < KWICKER@dfg.ca.gov>

To:

<LJLawren@placer.ca.gov>

Date:

12/20/02 8:38AM

Subject:

NOP, Kings Beach Commercial Core Improvement Project Comments

Dear Ms. Lawren:

Thank you for distributing the NOP on the above-referenced project. Due to time constraints, I am emailing the following comments:

1. Under Section II of the Initial Study, how will there be no impact upon

fisheries resources, per item 7 if water conveyance/treatment changes

are made? How do these 'no impact" evaluations compare with the ess

than significant impacts findings of Section II Item 4 and Section III?

2. Please include the following in the draft EIR: 1) An evaluation of fisheries resource impacts, unless the Wildlife Evaluation section will

discuss this resource; 2) Caltrans' traffic analysis; 3) the stormwater

treatment design options; 4) the LSC parking study (2000); and 5) he

streetscape simulation "after" photos for Option B.

Thank you,

Kerry Wicker Environmental Scientist CA Dept. of Fish and Game, SV-CS Region 1701 Nimbus Road, Suite A Rancho, Cordova, CA 95670 (916) 358-4353

CC:

"Dale Watkins" < DWatkins@dfg.ca.gov>

"rick marshall" <rickmarshall@inreach.com>

To:

"Rebecca Bond" <RBond@placer.ca.gov>, <mdarling@dfg.ca.gov>,

<rperrault@dfg.ca.gov>, <Ben_bramer@dot.ca.gov>, <Damion_Farley@dot.ca.gov>,

<dick_melim@dot.ca.gov>, <hamid_hakim@dot.ca.gov>, <John_Holder@dot.ca.gov>,

<Mike_Bartlett@dot.ca.gov>, <Mike_DeWall@dot.ca.gov>, <Mike_Forga@dot.ca.gov>,

<roger_brown@dot.ca.gov>, <Sean_Penders@dot.ca.gov>, ""Candace Rousselet""

<CRoussel@placer.ca.gov>, "Grehm"" <KGrehm@placer.ca.gov>, ""Mark Heckey""

<MHeckey@placer.ca.gov>, "Kastan"" <SKastan@placer.ca.gov>, <BWarden@rb6s.swrcb.ca.gov>,

<LKemper@rb6s.swrcb.ca.gov>, <RErlich@rb6s.swrcb.ca.gov>, <cemmett@trpa.org>,

<cneible@trpa.org>, <gmcnamara@trpa.org>, <lbarnett@trpa.org>, <rwhitney@trpa.org>,

<rwiggins@trpa.org>, <DLaPlant@placer.ca.gov>, <Steve Hetland@dot.ca.gov>,

<BCombs@placer.ca.gov>

Date:

12/2/02 8:01AM

Subject:

Kings Beach

Hi all,

I have had no response so I will try everyone in hopes someone has an answer.

Thank you, the attached word document looks Great. Are the diagrams attached and I'm not seeing them?

Regarding the issue of two vs. four lanes for the new corridor. As an environmental science major in college I learned that slowing down traffic and creating idling cars dramatically increases air pollution. Look at Tahoe City for proof that two lanes creates congestion and idling cars. Unfortunately because of the lay of the land in Tahoe City there is no getting around their congestion problem on Hwy 28.

One of the things we have going for us in Kings Beach is that we provided enough space for a four lane highway thru town. To create congestion and increase air pollution in this basin would be taking a step backwards when Kings Beach finally has the potential with this downtown improvement project to be a world class resort town. The issue of bicycle and pedestrian safety can be solved by constructing bike lanes, slowing the speed limit to 25 MPH, coordinating the traffic signals to disperse traffic thru town at a regulated pace and finally creating more crosswalks or even pedestrian bypasses over the highway.

The addition of trees, faux cobblestone sidewalks, and antique looking gas lamps would increase Placer County's revenue base over time significantly by increasing property values. The addition of adequate water treatment for our street and highway runoff will ensure that we finally meet our Federal commitments under the Clean Water Act. If all the agencies, people and politicians work hard this much needed project will be done in a time frame that we all can be proud of.

Thank you for your time, Rick Marshall

tom burt <tbtbtb1964@yahoo.com>

To:

<dlaplant@placer.ca.gov>

Date:

12/5/02 10:52PM

Subject:

Kings Beach

Tom Burt Box 2572

Kings Beach 96143

Comments on project.

- 1. Keep the four lanes
- 2. Sidewalks suck in the winter with snow plowing. Who Pays and maintains that?? If you put sidewalks, Keep them narrow and keep as much parking on the street as possible. No Trees planted in the sidewalks nor any of the street lights that were in any of the mock ups. Stop landscaping Lake Tahoe. This is not San Francisco. Also trees block the view of the lake and they block the business fronts from view of the people on the road.
- 3. No round abouts. They look okay on paper but the don't work well in reality.
- 4. Turn Brook St. into a one-way street going East for the block between Bear and Coon. Thus taking the major cluster out of the Bear street corner.
- 5. The biggest suggestion I can give is to have the law enforcement actually enforce the speed limit in Kings Beach. Wow! what a big slow down in Traffic that would be. It would eliminate the Pedestrian problem, and make the businesses happy that the people would be going slow thru town. I can not say the last time I saw a speeder get a ticket in Kings Beach. I see and know of many people getting tickets for seat belts though???? If the law enforcement actually did there job, say just in Kings Beach, it would become known like the 15 mph school zones in Northern Nevada as the place not to speed. Have you ever been in a school zone in Nevada?? No-one speeds. Just think of Kings Beach that way. Everyone happy except the police who have to actually do there job and enforce the law.

"Keith D Vogt" <k vogt@charter.net>

To:

<dlaplant@placer.ca.gov>

Date:

12/10/02 11:45AM

Subject:

Kings Beach Commercial Core Improvement Project

Dan...

Thanks for the Public Workshop on Dec. 5 regarding the Core Improvement Project for Kings Beach.

I've attended quite a number of the public events in the past and after each one I find myself more informed and understand the issues more clearly.

I left the workshop on the 5th with a feeling of not being completely satisfied. Maybe it was my physical condition as I was in the beginning stages of a cold, but upon reflection I think it had more to do with the structure of the workshop. While it was a great benefit to be able to talk to the individuals who were responsible for the various displays, I felt there was a need for some kind of "community" exchange after talking to the display personnel. But that's in the past and we'll move on.

I have given considerable thought and have surveyed the area of the proposed Fox round-about. I'm not sure why the staff has chosen that location to exhibit as an example of a round-about, but that location is certainly unacceptable as a round-about for numerous reasons, which I'm sure others have pointed out. Least of which is the new building currently under construction on the NE corner and the removal of parking for KFC & the Subway businesses. We don't need to hurt our local businesses any more than they will be by the interruption during the project.

I am certainly a supporter of the round-about concept having spent time in Scotland this past summer and experienced driving through numerous communities that have round-abouts. It was my observation and after talking with local Scotland residents that round-abouts are "just the normal part of life" and people couldn't imagine stop lights at the various street crossings in their communities. I think round-abouts could become a "normal part of life" for us in KB as well.

Back to the Fox location... I know CalTrans/County are not supportive of doing a round-about at the Chipmunk location because of its location at the "bottom of the hill". I'd like to offer a couple of positive reasons why this would be an advantage to everyone. First, admittedly people do come down the hill faster than the posted speed limit, but what better way to govern that speed limit than by posting additional signs of the coming round-about at Chipmunk which would, by its configuration slow down the traffic entering KB. Second, the Chipmunk crossing is the most blighted area along Hwy 28 in the KB area. What better way to enhance the entrance to KB than to retrofit that area with a round-about and erect a beautiful sign welcoming people to Kings Beach.

Of course I'm operating on the "assumption" that one of the objectives of the core improvement project is to S-L-O-W down the traffic through the Kings Beach area. At least that's the view of a large number of local residents and business people. It is not uncommon when I come from the east into KB for people to pass me after passing Chipmunk and increase their speed, even though there is a posted 30mph limit. On numerous occasions I have seen people crossing the Fox/Hwy 28 crossing and taking their lives in their hands because of speeders coming from both the east and the west. We have been very fortunate that people have not been killed trying to cross the streets at numerous locations throughout the core area.

I'm not sure you heard of, or remember the gentleman who had a temporary "blackout" and ran across Hwy29 at Fox and crashed into the movie theatre where a woman was killed. It was later determined the gentleman was going above the speed limit and his speeding was a contributing factor to the accident. If we have a "divider" throughout the core project, this would have an effect of reducing this type of accident.

Thanks for "listening" and I look forward to the next community meeting.

K...

Keith D. Vogt President/CEO Ovations at Lake Tahoe, Inc. www.ovationsatlaketahoe.org www.tahoejazz.org



DEC 1 6 2002

PLANNING DEPARTMENT

December 10, 2002 Page 1 of 2

Ms. Lori Lawrence, Environmental Division Placer County Planning Department 11414 B Avenue Auburn, California 95603

Re: Initial Response Comments, Draft EIR
Kings Beach Commercial Core Improvement Project
Placer County, California.

Dear Ms. Lawrence,

This letter is in response to the Draft EIR for the above referenced project. Please consider and address the following specific comments as related the following project components:

Alternative "A" (four lane/signalized roadway)

This alternative which will essentially retain the existing road configuration which has been documented to be detrimental to the goals and objectives of the 1996 Draft Kings Beach Community Plan. The four lane highway configuration doses not allow safe pedestrian crossing or circulation, encourages excessive traffic speed and does not promote viable commercial opportunities.

Alternative "B" (3 lane roadway w/ roundabouts)

This alternative, with significant design modification, is consistent with the goals and objective of the Kings Beach Draft Community Plan, and is the preferred alternative for the following reasons:

Pedestrian circulation: This alternative allows wider sidewalks, pedestrian friendly plaza opportunities, safer street crossings and discourages excessive vehicle speeds based on ASTO National Traffic science.

December 10, 2002 Page 2 of 2

<u>Drainage opportunities:</u> The areas within the roundabouts will provide a location for proposed drainage structures, thus minimizing the need for public condemnation and acquisition of satellite parcels from private landowners consistent with TRPA water quality objectives and policies.

Landscaping opportunities: This alternative will provide additional opportunities for landscaping and is consistent with TRPA scenic threshold objectives.

Economic vitality: This alternative will also provide economic vitality to a commercial core which has been compromised by the current four lane highway configuration as documented in the Kings Beach Community Plan.

In order for the above thresholds and environmental compliance to be realized, Alternative "B" $\underline{\text{must be re-engineered with the following}}$ $\underline{\text{modifications:}}$

Highway alignment and Street intersection offset:

In order for roundabouts to be constructed in Kings Beach, it is necessary that the <u>design consider a re-alignment of the Highway centerline and corresponding street intersection offset to minimize right of way acquisition of private lands.</u> A road re-alignment to the south will allow Caltrans to work with its Public partners (State of California Conservancy) which is the abutting landowner for the majority of the effected right of way. This will minimize the need for public condemnation and acquisition of private lands and minimize impact in existing private commercial properties.

December 10, 2002 Page 3 of 3

Highway 267 Intersection- MUST BE INCORPORATED INTO PROJECT AREA

The existing signal at the intersection of Highway 267 and Highway 28 must be eliminated and replaced with a roundabout. Preliminary traffic studies associated with this project have failed to incorporate increased traffic flows generated by the Highway 267 bypass and build out of the Martis Valley. National traffic data suggests that the roundabout configuration will not work if used in conjunction with existing signalized intersections. This intersection must also be realigned and offset northerly and westerly to minimize the number of private lands subject to right of way acquisition.

Please insure that the above specific are specifically addressed as required by CEQA Law.

Thank you.

Kenneth R. Arnett, P.L.S.

To Dan LaPlante From: Candy Dowdle

9699 North Lake Blvd. Brockway, California 96143-0612

530-546-9134

Comments: I think THE most important thing to do in Kings Beach is SLOW DOWN the traffic, both for pedestrian safety and to benefit our shops and restaurants. I think a three (3) lane configuration with one lane in each direction and bike lanes and a middle left turn lane at intersections is MANDATORY! A wide center median strip where pedestrians could stop safely would be nice. Currently drivers going west out of Brockway are up to 50 mph when they hit the 30 mph speed limit sign at Chipmunk. Pedestrians trying to get to the beach "may" get the westbound traffic to stop, and even the left lane of eastbound traffic. But the driver in the right lane of eastbound cars thinks the guy in the left lane is stopped to make a turn, and he will keep on flying through the crosswalk - (if there is a crosswalk.) Conversely, this also happens for pedestrians going North from the beach side of the highway.

My husband and I walk to Kings Beach often, and we also ride bicycles down this stretch of road, and we have experienced this hundreds of times. I think sidewalks and bike lanes all the way to the Stateline are needed. A lot more people would walk or bicycle if the traffic wasn't so bad. A whole lot of people have to walk to Crystal Bay to work in the casinos there. I vote for roundabouts at the intersection of Hwy. 267, and Chipmunk Street, and maybe Coon Street. Then, reduce the speed limit to 25mph, like it is in Tahoe City and Crystal Bay and enforce it like it was in front of a school!

The second most important thing for Kings Beach is to alleviate the parking problems. For our shops, motels and restaurants to be patronized you have to make it convenient for the people to get in to them. We want our town to be attractive and a more "village" like atmosphere. If our retailers were more successful, the blighted areas would get cleaned up. I vote for satellite parking lots around town and off Hwy. 28. However, you will then have MORE pedestrians and bicyclists to get across the highway again, which brings us back to the issue of slowing down the traffic.

The third problem in Kings Beach to Crystal Bay is the dirt/gravel applied to the roads in winter. Our roads are always dirty and dusty to the point that you can't even see! I've come out of the Kings Beach Community Conference Center at 9pm and it looked like the whole town was in a fog. This loose gravel is slippery and dangerous to walk on when you are coming down the hill west towards Chipmunk St.

I have lived (full time) on Hwy. 28 for nine years and I know the problems of traffic during increased use periods. That is only a few DAYS each year through this area. We are only talking about a stretch of highway that is 8/10's of a mile, but one where the motels, restaurants, shops, beach and movies are always across the highway. Slowing down the traffic could be done with roundabouts, signals at cross walks, speed bumps or better enforcement of the speed limits. This would be a win-win-win situation for everyone, except the person who likes to speed! This stretch of road belongs to the community first, and to CAL TRANS second. It should not be that the main responsibility of CAL TRANS is to get drivers into and out of Nevada faster. I would like to re-emphasize that the speed limit be reduced, and even all the way to the stateline in Brockway, which is basically a residential area. The current speed limit is 30mph in Kings

Beach. That would take two minutes to legally drive this one mile of road. A reduction to 25mph increases the driving time by 4/10's of a minute, or 24 seconds.

PLEASE, people.

From: Larry W. Dowdle, 9699 North Lake Blvd., Brockway, CA 96143

In regards to the sidewalks and roads in the commercial core improvement project of Kings Beach: We need to get the traffic back under control. Why are we the only part of the north shore to have to tolerate a four lane highway through our community?

One way to slow down the west bound traffic though town is to keep the speed at twenty-five mph coming into California from Crystal Bay. What's happening now is, the drivers slow down for the 25 mph speed limit coming through Crystal Bay then as they enter California on highway 28 there is a speed limit sign for 35 mph. Naturally most drivers assume that is the minimum allowable speed and if you're in front of them and not going at least thirty-five, you will get a demonstration of what tailgating is. This speed is only 35 mph for 8/10's of a mile. The last 2/10's are down a fairly steep grade in to Kings Beach where by now the 35 minimum mph driver is going approximately fifty miles an hour. Not wanting to lose their momentum that they built up since entering California, they just kind of glide through town at way over the once again changed speed limit which is now 30 mph.

What I don't seem to grasp is who thought it was so important to raise the speed limit entering Brockway California for only 8/10's of a mile, which by the way is solid residential with at least one home's front door only 15 feet from the white line on the shoulder of the road and another's not much further than that. What is the point of encouraging the drivers to speed up for less than two minutes and then expecting them to slow back down?

To compound the problem, all the hotel guests and residents of Brockway and Crystal Bay have only one route available to them to walk to Kings Beach. On the 4 foot shoulder of Hwy.28. Would you feel okay knowing your kids or other loved ones were walking down that narrow shoulder with cars going 50 mph within 3 feet of their shoulder?

I hope the only reason the situation exists is that the problem hasn't ever been brought to your attention before and not because of some illogical cookie cutter rule in a manual.

I support the three lane option with roundabouts through Kings Beach, but I don't believe a roundabout is warranted at Fox St.

To Whom It May Concern:

Having attended several meetings regarding the proposed Kings Beach Community Plan Improvements, I would like to take this opportunity to express my support for **Option B: Roundabouts**.

I have studied community and land use planning for over a decade, inclusive of my pursuit of a degree in Geography and Environmental Studies. Over the past six years I have worked as an active professional in land use planning in Oregon and California, inclusive of three years of consulting work in the Lake Tahoe Basin.

I strongly support the direction and vision dictated by the North Tahoe Community Plans, inclusive of the Kings Beach Community Plan, adpoted April 1, 1996. The Kings Beach Community Plan advocates a "pedestrian tourist village oriented toward the main street, and Lake Tahoe." The number one transportation objective and goal of this community plan is to "Provide a safe and efficient transportation system for the residents of Kings Beach area and others who use this system." Of the various proposals, **Option B** is the only one that I believe meets this vision for the land use of the Kings Beach Downtown Commercial Area.

I encourage the committee to study the use of roundabouts in Portland, Oregon. I grew up in Portland, a city that is nationally regarded for progressive land use policies. The City of Portland has effectively utilized roundabouts as a traffic mitigation solution with beneficial social and economic side effects. The neighborhoods of Northwest and Southeast Portland previously suffered similar problems to those which the Kings Beach Community Plan Improvements seek to resolve. The use of roundabouts has solved traffic problems and had a positive effect in creating pedestrian friendly, mixed use neighborhoods. Thesee previously blighted areas, over the past decade since the institution of roundabouts, have become some of the most desirable locations in the city for businesses and residents alike.

The investment incurred through the Community Plan Improvements will be substantial. The project needs to evaluate all the options thoroughly to insure that the return on this investment reaches beyond moving a higher volume of traffic and benefits the long term social and economic vitality of Kings Beach as one of the gateways to Tahoe's North Shore.

Yours Sincerely,

Wyatt Ogilvy

Kings Beach Resident

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7 - 9 PM

Name/Nombre Thirlish May Duoday
Address/Domicilio Prog 790 thurs with 96 148
Comments/Commentarios
2) I fully 504/10st roundations societ a rox street
2 Two loves not four
To remove SEZ'S HOW THE Parking Corations
More public induly as
B) More Dublic meetings
(6) with we are smart educated funny
and we have solding !!!
(7) Tomores project is a tille disappointing in
it's confusion - I wish the appropriate said stands
IN WINTER ATRAC CTC. JCALLON UST

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (dlaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: dlaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 531-6231.

DATE RECEIVED

DEC 1 2 2002

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7 - 9 PM

Name/Nombre Davie Ower
Address/Domicilio PO Box 472 - 7525 NORTH AVE - KINGS BEDEN
Comments/Commentarios
ATRK THE TAKE OF 3 LOWES & ROUNDABOUTS.
HOW TO DEAL WITH SNOW REMOUNZ - PERN?
SINKOUNIUS AKK GRENT.
DIRTISTS RENDITIONS SHOW NON NATIVE HIGH WATER
REQUIREINANT PLANTS?
CAN ENOUGH LAND BE MADE INTO PARKING TO
HANNALE OLL BENCH & BUSSINKES REQUIREMENTS?
ANY PLANS FOR KINGS BEDEIT "BACK STREATS" IMPROVENERS
TRAFFIC KLOW - WOULD GINGLIE LANKE TRAFFIC BACK THROUGH
ROUNDABOUTS KROM 267 STOP 216AT?
THANKS FOR THE OPPORTUNITY TO COMMENT!

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (dlaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: dlaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 531-5231.

RECEIVED

DEC 1 2 2002

PLACER COUNTY DPW
TAHOE OFFICE

DEC 0 9 5005

PLANNING DEPARTMENT

DESIGN / CONSTRUCTION DIVISION

December 23, 2002

Mr. Bob Costa Public Works Placer County, CA

RE: COMMENTS ON KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT

Dear Mr. Costa:

I would like to submit comments in support of Alternative Two (Three Lanes with Roundabouts). As a long-time resident of Kings Beach, the inconvenience of having three lanes instead of four will be more than offset to the benefit of Kings Beach by 1) the improvements in parking, bike lanes, and sidewalks, 2) the hopefully slower traffic coming through town (which is rarely 30 mph), and 3) the ability to turn left from the center lane 365 days a year, which should continuously facilitate traffic flow and help local businesses. The middle turn lane works great in front of Safeway and all along Incline Village, so it should certainly work here. Having better bike lanes will make it easier to ride a bicycle to the post office and Safeway (which is not a particularly pleasant trip at the moment to either walk or bicycle along the highway), and I am very much looking forward to that.

I doubt very much that roundabouts are needed, again based on watching traffic here day in and day out as a local resident. It is doubtful their use for a few hours a year will compensate for the high cost. But I will live with them if that is the only option involving three lanes.

In addition, I would like to strongly suggest that a sidewalk on one side be extended from Chipmunk east to the state line. There are many workers who walk that road at all hours, and it is not safe for either drivers or workers for them to be walking in the highway without a sidewalk. Particularly in winter. A wider bike lane would also be appreciated.

Finally, I hope you will continue to give consideration to improving the drainage on lower Chipmunk. The drainage has steadily improved over the last few years thanks to county and Caltrans efforts, but there is still a significant amount of runoff from upper Kings Beach and the highway that is depositing directly into the lake at the bottom of Chipmunk.

Sincerely yours,

Kathryn E' Kelly U 99 Chipmunk, Kings Beach kek@mindspring.com

Dec-30-02 12:29PM;

Page 3

FROM:

FAX NO. :

Dec. 13 2002 10:41AM P4

276-2002 500 must be

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7-9PM

Λ Λ
Name/Nombre Authors E (-PAERER
Address Bandalla
Commonle Com
That the Kings &
WILL ALOUP
GROW IN the Right diesetion is Total
The Act of the Country on the Country of the Country on the Country of the Country on the Country on the Country on the Country of the Country on the Country of the Country on the Countr
Scent & WATER QUALITY AGUAL AC
THE AVENTY LEAVING Y LANGE IS LIST ALL
Stopliable Apa
not accept a limit of the contract of
1996 KB
1996 KB Community Plantard TRPA objectives
3-3.

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Piecer County Department of Public Works, P. O. Box 1909, Takes City, CA 96145, or by e-mail to Dan LaPlante (diapient@placer.ca.gov).

Antes de salir del Tallero Público e les nueve de la noche (\$ PM), ponge los commentarios en la caja de comentarios. O si quieren, pueden der sus comentarios por corréo: Al Condado de Piscer, Departamento de Public Works, P. O. Box 1908, Tahos City, CA 98145, O por corréo electrónice e: displant@plecer.cs.nov

Gracias por eu ayuda y cooperación. Si tiene cualquier progunta por favor liame la oficina al numero (530) 581-8231,

DEC 2 4 2002

ACER COUNT RECEIVED

DEC 1 9 2002

. . .

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002
7 -- 9 PM

Name/Nombre Trin + Priscilla Mills
Address/Domicilio PO Box 987 Kings Beach Ca. 96143
Commentarios
We believe that 3 lanes in KB would be
superior to the present 4 lanes. We are
excited about the round-about idea. We'd
like kings beach to be forward-thinking
and set an example of how these ideas scould
Work, Ned like 1, to see people show down
as they arive through our town-

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (diaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarlos en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: diaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.



PLACER COUNTY DATE RECEIVED

DEC 1 9 2002

RECEIVED
PLACER COUNTY DPW
TAHOE OFFICE

PROJECT COMMENT SHEET

DEC 1 3 2002

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECTION DIVISION PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7 - 9 PM

Name/Nombre Scott Shane
Address/Domicilio 8352 Specked Ave. Po Day 4/7 Kines Black 64-96143
Comments/Commentarios Primary person: social Fix: Slow Feeth's
Down: 28 weeks to be more pedentein friendly.
3 vs. 9 /mes: Be smart. Experiment with 3 proces temporarily
with concrete barriers and contes + see of it works
Question? Whey does KB Hore I have 4 lanes when it is suppossed
by 2 lines on each of 3 sides. Morning Flothe that KB only to
be consested on 2 langs doesn't make some Of feel there will be 3 low
Arms of concession /spidlack with 3 on 4 lanes. 3 fares will improve
Comments pedestate trained strosphere I em dio continued that
menersed Abothe on fish and mound shorts with increased concession on
As Con local steels be sinced with "local to this all " since to the
include Stop signs to deter spreding

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (diaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: diaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.

RECEIVED

DEC 2.4 2002

BY:

PLACER COUNTY DATE RECEIVED

DEC 1 9 2002

RECEIVED PLACER COUNTY DPW TAHOE OFFICE

RECEIVED

DEC 2 4 2002

PAJIN

PROJECT COMMENT SHEET

DEC 1 3 2002

PAJINA COMENTARIO DEL PROYECTO GNI CONSTRUCTION DIVISION

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/
PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH
PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA
RE

DATE RECEIVED

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002
7-9 PM

DEC 1 9 2002

PLANNING DEPAR Name/Nombre Address/Domicilio RVR 4 7/9352 Speckled Avenue Comments/Commenterios Okings Brach is Right now its dangerous to onics the street s som wy cones and marker Bike lanes (5) How much land Nee. Round about side water Darking and bike lanes Liants Cross was tand or And CATRANS desire to "move tra Please deposit this sheet into the comment box before the end of the Public Workshop 19 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (diaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: diapiant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.

We have a vibrant, pedestrian. Oriented community who does not want to be sovered from our most precious resource: Lake Tahoe. And puting 4 lanes in KB will not solve anything w/ 2 lanes on all 3 sides (TC, IV; 267). I suggest you spend more on innovative public transit alternatives — and marketing to get folks to use it and making it run on time so I'd consider using it,

some mare moughts ...

also-when are the abandoned buildings
oping to be forn down? isna there smething
the country can do to push property owners
along faster?

Parking may become anissue. They not buy a few lots on 200 streets in to make paid parking?

what about bike lunes/sidewalks on some streets oping up to speckled? What about marketing our trails more? Linking the National ave. trail to the rest of KB? (i to Boys-n-birls club)

What about affordable housing? Too many ZND tomes going in KB lately. Not good for commor economy;

A Suggestion for the Kings Beach Commercial Core Project

I fully support the plan for a three lane SR 28, ped and bicycle lanes, parallel parking, and roundabouts for the strip through Kings Beach. One thing I haven't heard discussed is speed limit.

The current speed limit of 30 mph is too fast. With most people figuring The current speed limit of 30 mph is too fast. With most people figuring "the man" will let them have at least 5 (mph), 35 to 40 through KB unfortunately becomes the norm. Any cognizant driver that can take the temperature of their particular traffic situation knows that 30 through KB on an August weekend is too fast by an order of about 2x. Many tourist towns (Crested Butte, Idaho Falls, Telluride) have very low speed limits through their core districts. A speed limit of 15 or 20 mph is progressive, sends a deliberate message to drivers, and is SAFE! Virtually all serious accidents can be avoided with very low speed limits. Even at 15 mph, it will only take a few extra moments to drive through Kings Beach. The adjoining SR 28 through Tahoe Vista (posted at 35) is also way too fast. This stretch is experiencing an increase in bicycle and pedestrian traffic—and accidents. It is embarrassing that these inflated speed limits have not yet been addressed by our community.

you, Randall Osterhuber, Tahoe Vista

(530) 546-4491

A Suggestion for the Kings Beach Commercial Core Project

I fully support the plan for a three lane SR 28, ped and bicycle lanes, parallel parking, and roundabouts for the strip through Kings Beach. One

thing I haven't heard discussed is speed limit.

The current speed limit of 30 mph is too fast. With most people figuring "the man" will let them have at least 5 (mph), 35 to 40 through KB unfortunately becomes the norm. Any cognizant driver that can take the temperature of their particular traffic situation knows that 30 through KB on an August weekend is too fast by an order of about 2x. Many tourist towns (Crested Butte, Idaho Falls, Telluride) have very low speed limits through their core districts. A speed limit of 15 or 20 mph is progressive, sends a deliberate message to drivers, and is SAFE! Virtually all serious accidents can be avoided with very low speed limits. Even at 15 mph, it will only take a few extra moments to drive through Kings Beach. The adjoining SR 28 through Tahoe Vista (posted at 35) is also way too fast. This stretch is experiencing an increase in bicycle and pedestrian traffic—and accidents. It is embarrassing that these inflated speed limits have not yet been addressed by our community.

Thank you, Randall Osterhuber, Tahoe Vista

(530) 546-4491

RECEIVED
PLACER COUNTY DPW
TAHOE OFFICE

Jean Wernett C.O. 2361 Kunp Bean, CA 96143



Placen Country Dept of P.O. Box 1909 Tahoe City, CA 96145

9610541909

Ms. Lori Lawrence, Environmental Division Placer County Planning Department 11414 B Avenue Auburn, California 95603

Dear Ms. Lawrence,

My name is William M. Johnson Jr. 8634 Brockway Vista Avenue Kings Beach, CA 96143

I'm for option B: Roundabouts.

- 1) <u>Consensus:</u> Taken by local newspapers (editorials & staff reporters) show the majority of residents also approve of option B. See exhibit's A E which are attached herein.
- 2) The 1996 K. B. Community Plan states 4 lanes was and is detrimental to the character & identity and economic vitality of Kings Beach according to the original draft of fact finding. The objectives & goals of the community plan is community enhancements based on a pedestrian friendly old style Tahoe road not four lanes. There would be a significant impact against the community plan if option A, 4 lanes was to be chosen by staff.
- 3) <u>Cal Trans</u>: (I.E. State Of California) must take advantage of this project to realign North Lake Blvd. By moving the right away <u>South to CA State</u> <u>property, the beach</u>, between Bear & Coon street thereby not having to eliminate any productive use of private property being affected by option B.
- 4) <u>Safety</u> is a big concern to K.B. residents. The National Institute Of Highway Safety has recently found roundabouts have decreased accidents in these type of intersections. Enclosed exhibit F executive summary peer

review analysis of the traffic circle program City Of Portland's neighborhood traffic management program studied for 5 years shows accidents were reduced & decreased by 58 %. In addition it shows as other scientific studies that roundabouts will eliminate very fast vehicles and are chosen over other devices because they do not divert local traffic or restrict access to adjacent streets or land uses.

- 5) <u>Roundabouts</u> slow traffic but ensure it remains at a steady flow, thus roundabouts reduce congestion and the peril posed by speeding motorists an would likely benefit emergency vehicles. (see exhibit C)
- 6) Air quality can also be enhanced because roundabouts ensure a steady flow of traffic instead of cars stopping at traffic lights emitting emissions.
- 7) Water quality can also be enhanced by utilizing the roundabouts to install water infiltrators in them.
- 8) <u>Scenic quality</u> can also be enhanced by utilizing roundabouts, no unsightly traffic lights & wires, they also add an old style main street feel of a small town. Which is one of the goals of the community plan.
- 9) <u>Pedestrian circulation</u> Roundabouts allow wider sidewalks, pedestrian friendly plaza opportunities & landscaping opportunities which is consistent with TRPA scenic threshold objectives.
- 10) Please take this opportunity to take advantage of a first class world opportunity to design a walkable community that also has enormous benefits to scenic & water quality. I suggest we take down this Berlin Wall (I.E. the four lane freeway separating the public from the beach & lake front.) If we do, we will be the envy of the Tahoe Basin.
- 11) Ms. Lawrence, please consider & address the above comments on the project as specifically addressed an as required by C.E.Q.A law.

Respectfully

William M. Johnson Jr.

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002
7 – 9 PM

Name/Nombre William Sphuse
Address/Domicilio 9634 Brockway Vista KB
Comments/Commentarios
MAILING Address, F.O. 130x 1334 Crystal 1304
See Factored to spar better and while
14- F"

Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (dlaplant@placer.ca.gov).

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: dlaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.

TXHIBE TOWED 12-12-02

1 tight

Kings Beach residents sound off on sidewalks

By Megan Feldman

ahoe World Staff

After requests from Kings Beach citizens to build roundabouts instead of stoplights as part of a \$26 million public works project, Placer County has included traffic circles in its notice of preparation for the Environmental Impact Report. The notice was presented to the public last Thursday at an informational meeting at the North Tahoe Conference Center.

the Norus Janoc Come 28 to one lane in Narrowing Highway 28 to one lane and each direction with a center turn lane and roundabouts at Bear, Coon and Fox streets is one of two traffic configurations the is one of two traffic as part of the Kings

Project

Most residents favor that option over

Most very would fail to decrease speed,
worry would fail to decrease speed,
if like the three lanes and roundabouts

"I like the three lanes and roundabouts

right now we've got a highway that
goes ripping through this town—it would
slow people down, said Kings Beach resident and teacher Priscilla Mills.

The potential roadway changes are part

ident and teacher Frisching.

The potential roadway changes are part of a large-scale project intended to create a sort of "Main Street" in Kings Beach, and visitors. Also anning to enhance scenic quality as rated by the Tahoe Regional inc quality as rated by the Tahoe Regional



CER COUNTY DATE DATE

PLANNING DEPARTMENT

rom Page A1 mprovements

Planning Agency, the county streetlights, bike racks and planters separating pedestrians plans to add sidewalks, benches, from the road.

turn pockets at each of the four-lane highway approach, which provides for sidewalks Most people are against the and additional traffic signals at Bear and Fox streets, along with town's four signals.

will go faster — they're designtimes, and it's overkill," said Kings Beach resident Mike "Four lanes means people ing this project for traffic we have 20 days a year during peak Thomas.

sustain traffic as well as four anes during peak vacation improving the town for those One of the criticisms of the ect should be geared toward who live there, not just for times, adding to congestion. But three-lane option is that it won't Thomas and others say the projourists and motorists.

"The goal is not to get through Kings Beach fast, the goal is to stop people and have them shop, have little Marletta gesturing at a family with a

chairwoman and executive Regional Advisory Council director of the North Tahoe Business Association.

country would decrease polluand gaining popularity in this Roundabout proponents say the traffic circles used in Europe tion and aid traffic flow, as cars wouldn't continually stop and start as they do at stop lights. As for the expense of each option, projected costs of three lanes versus four are not yet available, according to the county.

cisms as well. Some worry a continuous central turn lane would be chaotic, citing the one too many cars turning in too abouts drew wide approval last in Tahoe City as an example of While three lanes with roundweek, there were several critimany places.

"Center turn lanes should only be used for short distances," said Thomas, suggesting a landscaped median in between the two lanes, with occasional opportunities to turn.

way. A Caltrans representative There was also concern about roundabouts taking land away from businesses lining the roadwas perched behind a booth

baby perable to cross the street entitled right-of-way—the in her strong process of purchasing land from May, Diegan, North Jahoe businesses in the path of the propadres building has been torn posed roundabouts. And to the Fried Chicken's outdoor eating where Los Compadres restaufic circle wiping out Kentucky area, Subway and the parcel rant used to be. The Los Comchagrin of many observers. drafts showed one proposed traf-

down. alpine area — that terrifies the neighbors. The draft shows Los ing the roundabouts should be smaller, "You wouldn't want a option, I just think they could do t without encroaching on any businesses," said resident Jim Gardiner. Duggan agreed, say-Santa Barbara roundabout in this Compadres and Subway gone,

est, the roundabouts would have them, but we're going to design it to minimize it [land acquisi-Director of Public Works Ken for right of way in either option, to be pretty large in order for tion] — we think we can shrink Grehm said there are not yet solid estimates of how much land would have to be purchased three lanes or four, "To be honpeople to keep driving through Placer County Assistan them."

Many people suggested said there's, no need, for one on smaller roundabouts, and most Fox Street, where KFC is locatels warrant signals or roundabouts at Fox Street and I hope and suggestions, the county emphasized the importance of ed. "I don't think the traffic levthey take them out it would be overkill," said Jennifer Mer-In response to such criticisms getting public input and analyzing all the options. chant, director of the Transportation Management Association.

milled around informational As more than 100 people booths manned by various agen-Grehm said, "our intention is to let people know we're looking cies involved in the project, at alternatives."

Those who attended the meeting were given comment forms and encouraged to turn them in to the county. "It's not we want, it's about making sure we're studying everything we should be studying - there's room for other proposals," said about which one [traffic model]

Project will be sometime in Jan-The next meeting on the Kings Beach Core Improvement uary and will address the streetscape design. The second Grehm.



December 5, 2002

TAMOE WORLD

More roundabouts may be on the way

By Christina Nelson STAFF Reported Siera Sum.



With little deliberation, the town council voted to invest time and money into roundabouts at two locations in Truckee.

The California Department of Transportation, after some persuading by town staff, gave the town an extra year to examine the feasibility of a roundabout at the Interstate 80/Highway 89 interchange.

Caltrans was planning on putting a traffic signal at the on and off ramps to Interstate 80, which would cost around \$750,000.

"They basically have enough money to slap some lights in and that's it," said Dan Wilkins, town public works director, adding that the light installed by Caltrans would not include pedestrian walkways.

If the town can prove that roundabouts are feasible at that location, Caltrans will donate the \$750,000 to the construction of a roundabout.

But the planned two-lane roundabout would cost up to \$1.5 million, the remainder of the money coming from town funds.

Although the town council considered shifting priorities for AB 1600 funds, money collected for road work from development, there may be other options, Wilkins said.

But, Wilkins noted, the council needs to decide if it wants to support the construction of these roundabouts now, so the opportunity doesn't disappear.

The council also decided to support the construction of a roundabout at Martis Valley Road and Highway 267. Approximately \$150,000 was set aside for the construction of this roundabout, but more money will be needed, Wilkins said.

Although he could not give an exact estimate for the amount of money the town would have to pitch in, he estimated the total cost of the two roundabouts at \$2.3 million.

Citing safety and traffic circulation issues, as well as the preservation of Truckee's small town feel, council members unanimously supported both roundabouts.

"It's not only an issue of safety or movement, but also one of ambiance, of feel," said councilwoman Maia Schneider.



March 14, 2002 TAHUE WURLD

Kings Beach needs roundabouts

Tahoe World Editorial

During his visit to North Tahoe last summer Dan Burden, one of the most listened-to consultants in the country according to Time Magazine, made a very convincing case for what he calls a walkable community.

The concept being that when we get out of our cars and encounter a place on foot, the experience is wholly more satisfying. Picture yourself wandering in and out of stores on a cordoned-off promenade, versus a six-lane boulevard. The former is clearly more appealing.

The benefits go beyond the hollistic. It makes economic sense as well. If a visitor has a specific destination in mind he will drive directly to that store, conduct his business and drive away. If he is encouraged to walk to that store and the environment is conducive to foot traffic, that visitor may on a whim visit any of the numerous stores he passes en route. The amount of foot traffic passing a place of business certainly correlates with sales.

As it is now Kings Beach is NOT a walkable community. The absence of sidewalks aside, the four-lane highway bisecting the town, makes a midday stroll through Kings Beach a precarious affair. Properly designed roundabouts would go far toward restoring the desired character to Kings Beach.

Roundabouts slow down traffic but ensure it remains at a steady flow, thus reducing congestion and the peril posed by speeding motorists. Bryce Keller of the North Tahoe Fire Department said roundabouts would likely benefit emergency vehicles.

Pedestrians would no longer have to cross four lanes of traffic and the one lane they did have to cross would only have cars moving in one direction. With roundabouts, drivers no longer run the risk of a head on collision and accidents that do happen are less severe.

Kings Beach skeptics have raised concerns that there is not enough room for a roundabout and that Caltrans will not permit a roundabout on a state highway. The first argument is a matter for engineers to work out. The second worry is not valid. A Caltrans spokesperson said if it were viable and had the support of the community, roundabouts in Kings Beach would be a real possibility.



Roundabouts have been widely successful in Europe and are gaining popularity across the country. Where they have been unsuccessful, such as in Clearwater, Fla., poor design has been to blame.

If this community is going to spend \$26 million on sidewalks in Kings Beach, the project should affect a sweeping change for the better. Roundabouts would help ensure such an outcome.



May 23, 2002

Land mines no answer to KB congestion

Tahoe World Editorial

One member of the public at Tuesday night's Kings Beach Core Improvements workshop called the roundabouts proposed for Kings Beach "visionary."

That is exactly what they are. Kings Beach residents are unparalleled in their tireless concern for their community. Blight, garbage, trailer parks, go the laundry list for reform reiterated religiously by a cadre of residents at public meeting after public meeting in Kings Beach.

The roundabouts proposed at the intersections of Highway 28 and Bear, Coon and possibly Fox streets, combined with a reduction from four to three lanes, are an opportunity to transform the feel of Kings Beach in one fell \$25 million swoop. A swoop at that price tag darn well better do some felling.

The current thinking as put forth by traffic engineer Gordon Shaw is that a three lane road with roundabouts through Kings Beach will be unable to handle future traffic flows, UNLESS we get rid of on-street parking.

That 'UNLESS' makes the proposal a no-go for many of the business owners along Highway 28. We say keep the on-street parking. All that means is on the busiest days of the year there's going to be more traffic in Kings Beach. Guess what? Short of land mines, there's going to be traffic in Kings Beach during the peak season.

The numbers presented by Shaw suggest there will be gridlock in Kings Beach irrespective of which plan is adopted, one participant keenly noted Tuesday. The roundabouts, coupled with three, instead of four, lanes of traffic, and the larger sidewalks that will accompany the lane reduction, will significantly alter the feel of Kings Beach.

We submit; that such changes would make Kings Beach the envy of the Tahoe Basin.



March 14, 2002

Roundabouts a possible solution for Kings Beach

By Charles Levinson, Tahoe World Staff Reporter

Jennifer Merchant, as the head of the region's Transportation Management Association, is a meeting junkie. From the Tahoe City Public Utility District to the Tahoe Regional Planning Agency to the North Lake Tahoe Resort Association, Merchant can usually be found milling about the back rows at any of the aforementioned monthly board meetings.

As any frequent meeting attendee in North Tahoe knows, when boards meet, dissent is inevitable. Any public project no matter how innocuous it may seem, invariably breeds a throng of angry citizens decrying said project as a harbinger of doom.

Merchant and others responsible for creating and pushing public projects, theoretically for the public good, are generally a jaded lot, convinced that no matter what they propose, angry hordes will call it treasonous.

So when Merchant proclaimed the Feb. 27, Kings Beach Core Improvements Workshop "one of the best meetings I have ever attended," something was afoot.

"It was actually a group of people talking about a community project without complaining," Merchant said. "It was a positive meeting. There wasn't anything negative. Nobody yelled at anybody. It was a breath of fresh air as far as public meetings go."

Her proclamation was surprising, not least because the Kings Beach Core Improvements — read sidewalks— seemingly have all the ingredients for bureaucratic gridlock and public discontent.

The project, which is years in the works, recently ballooned in cost to \$26 million. The Lahontan Regional Water Quality Control Board, Placer County and those in Kings Beach pushing the project have all butted heads on the water treatment aspect of the project. Lahontan does not feel the project as is adequately treats run off before it reaches the lake. The changes desired by Lahontan would add millions of dollars to the project's total cost.

When the evening workshop convened two weeks ago at the North Tahoe Community Conference Center, workshop organizers prepared themselves for an onslaught of questions and concerns over water treatment. Instead, a contingent of the usual Kings Beach suspects brought forth their desire for roundabouts in lieu of stop lights in Kings Beach.

Roundabouts, the European solution to the left turn and the stoplight, would slow down the flow of traffic through Kings Beach while at the same time reducing congestion by keeping traffic flowing at a steady pace. Roundabouts would be easier to navigate than a four-lane highway for pedestrians, and would help retain the small town feel of Kings Beach.

"We don't want to look like South Shore," said roundabout proponent Theresa May Duggan. "Kings Beach is a village. We want the traffic to slow down, look at the beach and shop in our stores. We want our pedestrians to be celebrated."

Among others, Duggan, was joined by Chris Hennessey and Jim Gardner, both long time Kings Beach activists, in her push for roundabouts. Though Gardner said the roundabout idea was first broached three years ago, it didn't pick up steam until a visit last summer by the nationally acclaimed planning

consultant Dan Burden. Burden spent a day examining North Tahoe's traffic woes and that evening gave a presentation on, among other things, the benefits of roundabouts.

Burden's presentation seemed largely forgotten. The videotape of that presentation, until recently tucked away at Merchant's Dollar Hill office, somehow found its way into the hands of the Kings Beach contingent. They in turn brought a well-constructed argument for roundabouts to the sidewalk project's dismayed planners.

"They're passionate and they have ideas," said Merchant after the workshop. "They don't just say we don't want this and we don't that. They say what they do want."

Leah Kaufman, a local planning consultant and the public outreach coordinator for the Kings Beach sidewalks project, was equally uplifted by the experience.

"People really seemed to care about the community and were kind of looking at what would make it nicer," she said. "They didn't want to see an urban transition with a highway and strip malls on both sides. They wanted a true community and I think it is something we need to look at."

Meanwhile, in Clearwater, Fla., one need only mention the word roundabout to provoke a diatribe on inefficiency.

Clearwater is a beach town of about 106,000 people on Florida's Gulf Coast. Like Tahoe it experiences large seasonal influxes of tourists. The busiest week of the year in Clearwater is Spring Break when swarms of students descend upon the town and traffic becomes a nightmare.

The City of Clearwater has built two roundabouts since 1999 that have attracted international attention for the uproar they have caused in the community. The bigger of the two roundabouts opened in December 1999. Between Jan. 1, and Sept. 18, of 2000 there were 323 accidents, according to reports in the St. Petersburg Times.

"My mother does a prayer for me, because I have to drive [the roundabout]," one resident was quoted as saying in a March 2, article in the St. Petersburg Times.

The Wall St. Journal and every major London newspaper has covered the Clearwater roundabout fracas. The city has created a Roundabout Advisory Committee to address the numerous complaints pouring in and recently completed a quarter-million dollar roundabout redesign.

Of course not everyone opposes the roundabout in Clearwater Beach. John Doran is an attorney and real estate broker who has lived in Clearwater since 1983.

"I don't' know how you managed to do it, but I think you managed to get one of the only people who thinks [the roundabout] was a good idea," he said. "It's moved more cars faster than anything we've had before."

Doran maintains that because it was new and different, there were a lot of fender benders in the first few months and that was responsible for much of the uproar. Accidents have steadily declined over time he said.

The Clearwater roundabout's failures have been largely due to poor design, according to just about everyone. And the Clearwater roundabout handles a peak traffic volume of more than 60,000 cars a day. A roundabout in Kings Beach would need to serve a maximum of 24,000 cars a day.

OF LYHIOF T

Date Printed = December 5th, 2002 - Page URL = http://www.trans.ci.portland.or.us/trafficcalming/reports/trafficcircle/Execsum.htm

Page=[/trafficcalming/reports/trafficcircle/Execsum.htm]

Traffic Calming

Peer Review Analysis of the Traffic Circle Program Executive Summary

Traffic circles have been an integral part of the City of Portland's NeighborhoodTraffic Management Program (NTMP) for approximately five years. The NTMP has utilizedtraffic circles as a device to help meet the overother devices because they do not divert truly local traffic and do not restrict access toadjacent streets program objectives of better managing trafficon local streets. Specifically, traffic circles are used to reduce vehicle speeds andeliminate very fast vehicles on local residential streets. They are frequently chosen or land uses.

these traffic circlesand their potential effect on traffic speeds and intersection safety have not beenpreviously circles in this manner. Experience in these cities indicates thattraffic circles are effective in reducing vehicle speeds and can reduce the number andseverity of intersection accidents. However, the actual impact of The City of Portland is just one of many cities throughout the United States and Europeemploying traffic evaluated in the City of Portland.

following tasks were conducted as part of this peer review forevaluating the effect of the NTMP traffic circles Several meetings were held with NTMP staff to define the role and scope of this peerreview evaluation. The on vehicle speed and traffic safety:

- Develop a method to evaluate how vehicles travel around traffic circles and determine if these speed profiles vary by any key traffic circle design elements.
 - Analyze changes in mid-block vehicle speed data that were collected before and after traffic circles were installed and determine if these changes differ by any key traffic circle design elements ۲i
- Analyze changes in the number and severity of accidents that occurred after the installation of traffic က
- Observe traffic at each of the traffic circle sites under day time and night time conditions and assess their operational, visibility, and safety characteristics. 4.

successful at reducing the number of vehicles traveling at high speeds (30-35 mph) on residential streets. On many of these residential streets, 15 percent ormore or the vehicles routinely exceeded 35 mph. After traffic circles were installed, vehicles rarely exceed 35 mph. The new larger circles (12 foot radius) appear to The results of this peer review study have clearly demonstrated that overall thesetraffic circles are

Syptem (5)

reducevehicle speeds more than smaller traffic circle islands.

eliminated, reported accidents, especially multi-vehiclecollisions. Overall, once traffic circle were installed the mersections that are nearby the intersections that had trafficcircles installed was conducted to verify that this reduction in accidents could not beattributed to other extraneous factors. This analysis found that during the monthly rate of reportedaccidents decreased by 58 percent. For comparison, a special analysis of control" same periodthat reported accidents dramatically decreased at intersections with traffic circles,reported accidents increased 6 percent at these nearby control intersection. It should bealso noted that traffic Moreover, this peer review analysis found that traffic circles have dramaticallyreduced, if not almost volumes at intersections with traffic circles did notsignificantly change once the circle was installed

Observations at the traffic circles installed by the NTMP found vehicles did not haveany significant problems circleintersections to assess their condition and operating characteristics during both daylightand nighttime recommendations, including upgrading trafficcircle delineators and signs, are detailed in this report. In conditions. Traffic circle intersections should also be inspected after anaccident occurs in its vicinity. negotiating around the islands. However, their nighttimevisibility can be improved. Several specific addition, the City ofPortland should establish a program of routinely inspecting these traffic

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7 - 9 PM

Name/Nombre	
Address/Domicilio 8331 Nathlake Blod, P.O. Box 39 Kins	Beach CA
Comments/Commentarios It mutters what you decide for our bush	معامون معمده
operty values on the blod. Town abried my o business on the blod for 13 ye	China ous her
The premise is wrong that we are a pedes trian town - we how	no chopping
centers and the shops mainly left are service, foor / restaurant/small lod	ces and office
2) no one can cultard all there amount in a - 11001 tours intour ex a	ecaus for
shalowalks, planters track, etc. Notato parallel parking and traffic show	red alat
So people can see our businesses o signs and people can get ach	ion The
street safely year round, we don't need trees to block our business	a marbility
3) priking to to in the accas with high mexican density aren't	come to be
used due to safety espico. The trailer parks, a pret ment houses du	valexes etc.
must be closured up and up to state o county codes, People don	if even Wh
hoing the basket hall courts in the seemmer because of alothe me	ex Can Gamo
4) Weathe Roadway Boption - it would be better to have a roun	dalout on
HWY 267 and 28 entering than so many right in the middle of town.	
Please deposit this sheet into the comment box before the end of the Public Workshop (9	ih
PM). Or if you wish, send comments by mail to Placer County Department of Public	7 .
Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante	4
(dlaplant@placer.ca.gov).	

Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: dlaplant@placer.ca.gov

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.

5) Det if you can extend posidewalk a bike trail up HWY26; a ways so people can feel rate walking on the HWY 267 to town from houses a condo's near town. Bike path so people can get to town to the regional park wike paths and can get to town to the regional park wike paths and borest service logging trails would really be helpful,
but up to say Kings wood village maybe Kings Run but
withat area. Bus service at least in the Summer
couple times a day from Kings Beach to Truckee with
a stop at Northstar would help alot!

PROJECT COMMENT SHEET

PAJINA COMENTARIO DEL PROYECTO

KINGS BEACH COMMERCIAL CORE IMPROVEMENT PROJECT/ PROYECTO COMMERCIAL MEJORAMIENTE DE KINGS BEACH PUBLIC WORKSHOP/TALLERO PÚBLICO EN PERSONA

THURSDAY, DECEMBER 5, 2002/JUEVES, DICIEMBRE 5, 2002 7 – 9 PM

Name/Nombre MARI ANN BURT Address/Domicilio PO BY 347 Comments/Commentarios Tulte VISTA Cu 96/48	
see sheet	
Please deposit this sheet into the comment box before the end of the Public Workshop (9 PM). Or if you wish, send comments by mail to Placer County Department of Public Works, P. O. Box 1909, Tahoe City, CA 96145, or by e-mail to Dan LaPlante (dlaplant@placer.ca.gov).	
Antes de salir del Tallero Público a las nueve de la noche (9 PM), ponga los commentarios en la caja de comentarios. O si quieren, pueden dar sus comentarios por corréo: Al Condado de Placer, Departamento de Public Works, P. O. Box 1909, Tahoe City, CA 96145, O por corréo electrónica a: <u>dlaplant@placer.ca.gov</u>	

Gracias por su ayuda y cooperación. Si tiene cualquier pregunta por favor llame la oficina al numero (530) 581-6231.

PLANNING DEPARTMENT

Dear Sirs,

;Thank you for letting me respond toyour prosals.

Your plan of putting round-a-bouts in Kinfs Beach makes no sense. Round-a-bouts do nothing for anyone. First of all, you must be knowledgeable about driving in one. Who has the right of way, What does the yeild mean when you are entering, and how dp I get out of one? The population at North Tahoe is not educated to this. WE VOTE NO TO ANY ROUBD-A-BOUYS.

Your proposals to make lane changes is not good. If you have drovem anywhere around the lake recently, you wait for 4 lanes to pass a truck, bus, or sight seeer. My following a bus on Highway 89 from Emerald Bay to Tahoe City was very slow and the pollution from the bus was terrible 15 need all the 4 lanes we can get.

Kings Beach needs its 4 lanes to keep traffic moving and safe.

What we need is more policemen to catch the speeders. Then every one will be able to nake turns and stop when needed.

Why do we need side walks? We live at 62000 feet in the mountains. We are not a city but a town. You just need to enjoy what is here. And people do.

Just look at Tahoe City and see how silly they are. Mot only did we loose half of our parking spaces, you have to wait for then to be shovled to walk on them in the Winter.

To solve your parking spaces, put your drainage mosquito ponds under ground and make day use parking on top. In Kings Beach, Carneilian Bay, Tahoe City and Tahoe Vista.

Mary am Bent

Thank you.

ON DATE RECEIVED

11EC 24 7000 L

PLANNING DEPARTMENT

December 23, 2002

Mr. Charles Emmett
Transportation Projects Manager
Tahoe Transportation District
c/o Tahoe Regional Planning Agency
(via Fax: 775 588 4527)

cc: Lori Lawrence, Environmental Review Clerk Jerry Wells, Deputy Director, TRPA Theresa May Duggin, Chairwoman, NTRAC John Paul Harries, League to Save Lake Tahoe

Re: Notice of Preparation, Kings Beach Core Improvement Project

Dear Mr. Emmett:

Thanks for taking a few minutes last week to discuss some of the concerns I have regarding the current proposal. Below, I have included the text of the comments I gave to the Placer County project team at the last meeting:

"We appreciate your response to the desire of many people in our community for a creative alternative to a 4-lane highway with stoplights. Option B is clearly an effort to give us the 2-lane highway with roundabouts that we would like, but we are concerned that Option B is designed to fail because of the placement and the size of the roundabouts.

- (1) The roundabout placed at Fox Street would adversely affect the businesses, which is not good for our town and, by your own admission, would not be supported by the County anyway. Fox Street is also a key pedestrian hub.
- (2) There should be a roundabout at 267; otherwise the free-flowing traffic from the east will be stopped at the intersection, causing backups to the roundabouts and undermining the entire design.

These issues were raised at a previous meeting, and the design does not appear to have been changed. We identified CalTrans policies flexible enough to create a good design, one that would reflect the values of the community. The roundabouts could be smaller. They could be located so that they support, rather

than impede, the existing patterns of pedestrian traffic. The lanes could be narrower enabling us to keep existing businesses and properties.

What will it take to get these modifications incorporated into Option B?"

So, in writing this letter I'm asking that a "community-based" option, "Option C", be included in the options evaluated in the EIR/EIS. This third option would include one travel lane in each direction; sensible placement of roundabouts instead of stop lights; and the creative application of current CalTrans policies to facilitate "Context Sensitive Design." The proposal should be further refined to include:

- •There should be a roundabout 300 feet west of Chipmunk (east/west traffic only, no side streets) to announce arrival in Kings Beach. Provides opportunity for sculpture or landscape detail to help establish artistic theme envisioned for Kings Beach in the community plan. Roundabout in this location will begin to slow traffic prior to reaching Fox Street.
- •The Fox Street/Highway 28 intersection is a very active pedestrian node in Kings Beach. Instead of placing a roundabout at this intersection—a roundabout that would harm or destroy several viable businesses—design a pedestrian crossing point that recognizes existing pedestrian circulation patterns. A similar "pedestrian crossing plaza" could also be located at Deer Street, another busy crossing point.
- •"Option C" should include sections of landscaped infiltration facilities in the center median with occasional left turn pockets. Along with improving scenic quality, the objective of landscaped medians is also to provide a measurable reduction in land coverage. Landscaping, "pocket" art plazas, transit stops, bicycle facilities, lighting and street furniture, to name a few, would also be included in the proposal. Best Management Practices such as the drainage improvements would remain a part of the proposal.

Along with improving safety conditions for pedestrians, one of the key objectives of the proposal should be the revitalization of downtown Kings